

Washington Municipal Airport



Pavement Management Report

PREPARED BY

Applied Pavement Technology, Inc.
1908 South First Street, Suite 201
Champaign, Illinois 61820
(217) 398-3977
www.appliedpavement.com

AUGUST 2026



The preparation of this document was financed in part through an Airport Improvement Program grant from the Federal Aviation Administration (Project Number 3-19-0000-033-2025) as provided under Section 505 of the Airport and Airway Improvement Act of 1982, as amended. The contents do not necessarily reflect the DOT's official views or the policy of the FAA. Acceptance of this report by the FAA does not in any way constitute a commitment on the part of the United States to participate in any development depicted therein nor does it indicate the proposed development is environmentally acceptable in accordance with appropriate public laws

WASHINGTON MUNICIPAL AIRPORT PAVEMENT MANAGEMENT REPORT

Prepared For:



Iowa Department of Transportation
Modal Transportation Bureau
800 Lincoln Way
Ames, Iowa 50010
515-239-1691
<https://iowadot.gov/modes-travel/aviation>

Prepared By:



Applied Pavement Technology, Inc.
1908 South First Street, Suite 201
Champaign, Illinois 61820
217-398-3977
<https://www.appliedpavement.com>

In Association With:



Robinson Engineering Company
Consulting Engineers
1545 Dalton Street
Jesup, Iowa 50648
319-334-7211

TABLE OF CONTENTS

INTRODUCTION.....	1
PAVEMENT INVENTORY.....	3
PAVEMENT EVALUATION.....	6
Pavement Evaluation Procedure	6
Pavement Evaluation Results.....	8
Inspection Comments.....	13
Runways	13
Taxiways	13
Apron	13
T-Hangar.....	14
PAVEMENT MAINTENANCE AND REHABILITATION PROGRAM	15
Analysis Parameters.....	15
Critical PCIs	15
Localized Preventive Maintenance Policies and Unit Costs.....	15
Major Rehabilitation Unit Costs.....	15
Budget and Inflation Rate.....	15
Analysis Approach.....	15
Analysis Results	16
General Maintenance Recommendations.....	17
FAA Requirements (Public Law 103-305).....	17
FAA Advisory Circular 150/5830-7B, Appendix A. Pavement Management Program (PMP)	18
SUMMARY	24
REFERENCES.....	25

LIST OF FIGURES

Figure 1. Pavement condition versus cost of repair.	1
Figure 2. Pavement area by branch use at Washington Municipal Airport.....	4
Figure 3. Washington Municipal Airport network definition map.....	5
Figure 4. Visual representation of PCI scale on typical pavement surfaces.....	7
Figure 5. PCI versus repair type.....	8
Figure 6. Pavement area by PCI range at Washington Municipal Airport.....	9
Figure 7. Area-weighted PCI by branch use at Washington Municipal Airport.	9
Figure 8. Washington Municipal Airport PCI map.....	10

LIST OF TABLES

Table 1. 2026 pavement evaluation results.....	11
Table 2. 5-year M&R program under an unlimited funding analysis scenario.	16
Table 3. Pavement inspection report.....	20

APPENDICES

Appendix A. Cause of Distress TablesA-1

Appendix B. Inspection PhotographsB-1

Appendix C. Inspection Report..... C-1

Appendix D. Work History Report D-1

Appendix E. Localized Preventive Maintenance Policies and Unit Cost Tables.....E-1

Appendix F. Year 2026 Localized Preventive Maintenance Details F-1


INTRODUCTION

Applied Pavement Technology, Inc. (APTech), with assistance from Robinson Engineering Company Consulting Engineers (Robinson), updated the airport pavement management system (APMS) for the Iowa Department of Transportation, Modal Transportation Bureau (Iowa DOT). The APMS provides a means to monitor the condition of the pavements in the State of Iowa and to proactively plan for their preservation.

As part of this project, pavement conditions at Washington Municipal Airport were visually assessed in March 2026 using the Pavement Condition Index (PCI) procedure. During a PCI inspection, the types, severities, and amounts of distress present on the pavement surface are quantified. This information is then used to develop a composite index that represents the overall condition of the pavement in numerical terms, ranging from 0 (*Failed*) to 100 (*Excellent*). The PCI provides an overall measure of condition and an indication of the level of work that will be required to maintain or repair a pavement. The distress information also provides insight into what is causing the pavement to deteriorate, which is the first step in selecting the appropriate repair action to correct the problem.

Programmed into an APMS, PCI data and results are used to determine when preventive maintenance actions (such as crack or joint sealing) are advisable and to identify the most cost-effective time to perform major rehabilitation (such as an overlay or whitetopping). Delaying maintenance and rehabilitation (M&R) until a pavement structure has seriously degraded can cost many times more than if M&R was applied earlier in a pavement's life cycle, as shown in Figure 1. From a safety perspective, pavement distresses, such as cracks and loose debris, may pose risks in terms of the potential for aircraft tire damage and the ability of a pilot to safely control aircraft.

Figure 1. Pavement condition versus cost of repair.



The pavement evaluation results for Washington Municipal Airport are presented in this report and can be used by Washington Municipal Airport, the Iowa DOT, and the Federal Aviation Administration (FAA) to identify, prioritize, and schedule pavement M&R actions at the airport. In addition to this report, the web-based interactive pavement data visualization tool IDEA, containing the information collected during this project, was updated and may be accessed from the [Iowa DOT's website](#) or directly ([Iowa APMS IDEA](#)).

PAVEMENT INVENTORY

The project began with a review of the existing inventory information pertaining to the pavements at Washington Municipal Airport. The date of original construction, along with the date of any subsequent rehabilitation; the location of completed work; and the type of work undertaken were gathered. The information was used to update the pavement management database and associated maps, as necessary, to account for pavement-related work that had been undertaken since the last time the airport was evaluated in 2022.

The pavement network at Washington Municipal Airport was then divided into branches, sections, and sample units. A branch is a single entity that serves a distinct function. For example, a runway is considered a branch because it serves a single function (allowing aircraft to take off and land). Taxiways, aprons, and T-hangars are also separate branches.

Each branch was further divided into sections. Traditionally, sections are defined as parts of the branch that share common attributes, such as cross section, date of last construction, traffic level, and performance. Using this approach, if a runway was built in 1968 and then extended in 1984, it would contain two separate sections.

To estimate the overall condition of a pavement section, each section was subdivided into sample units. Portions of these sample units were evaluated during the pavement inspection, and the collected information was extrapolated to predict the overall section condition and quantities of distress.

Approximately 825,700 square feet of pavement were evaluated at Washington Municipal Airport, as illustrated in Figure 2. This figure also shows the area-weighted age in years of the pavements at the time of the inspection. Figure 3 is a map that details how the pavement network was divided into management units and identifies the sample units that were evaluated during the pavement inspection at Washington Municipal Airport.

Figure 2. Pavement area by branch use at Washington Municipal Airport.





FIGURE 3. NETWORK DEFINITION MAP.



NETWORK DEFINITION LEGEND

- BRANCH IDENTIFIER
- SECTION IDENTIFIER
- PCI VALUE
- SECTION BREAK LINE
- SAMPLE UNIT BREAK LINE
- SLAB JOINT
- SAMPLE UNIT NUMBER
- SAMPLE UNIT INSPECTED
- ADDITIONAL SAMPLE UNIT

 1906 South First Street, Suite 201 Champaign, Illinois 61820 Tel: 217-998-3977 Fax: 217-998-4027			
AGENCY: Iowa Department of Transportation			
Modal Transportation Bureau			
LOCATION: Washington Municipal Airport			
Washington, Iowa			
PAGE TITLE: Network Definition Map			
PROJECT DATE: NOV. 2025	CREATION DATE: NOV. 2025	PROJECT MANAGER: LJR	JOB NUMBER: 2021-125-AM04
DRAWING SCALE: 1"=300'	LAST MODIFIED DATE: JUN. 2026	REVISED BY: KEW	DRAWN BY: KEW
FILENAME: Washington.dwg		LAYOUT NAME/NUMBER: NET. DEF.	PAGE NUMBER: 5

PAVEMENT EVALUATION

Pavement Evaluation Procedure

APTech visually inspected the pavements at Washington Municipal Airport using the PCI procedure described in the following publications:

- FAA Advisory Circular 150/5380-6C, *Guidelines and Procedures for Maintenance of Airport Pavements* (FAA 2014a).
- FAA Advisory Circular 150/5380-7B, *Airport Pavement Management Program (PMP)*; (FAA 2014b).
- ASTM D5340, *Standard Test Method for Airport Pavement Condition Index Surveys* (ASTM 2024).
- USACE *PAVER Distress Identification Manuals* (USACE 2009a, 2009b).

During the PCI inspection, a cursory inspection of the entirety of a pavement section was performed. Sample units identified for more detailed inspection were verified, and adjustments to the selected sample units for inspection were made as needed to ensure an accurate assessment of the pavement's condition. Data pertaining to the types, severities, and quantities of observed pavement distresses were then collected within each sample unit. These data were then used to calculate the composite PCI of each pavement section. The PCI provides a numerical indication of overall pavement condition, as illustrated in Figure 4. The PCI ranges from a value of 0, which represents a pavement in a *Failed* condition, to a value of 100, which represents a pavement in *Excellent* condition with no visible signs of deterioration. It is important to note that factors other than overall PCI need to be considered when identifying the appropriate type of repair, including types of distress present and rate of deterioration. Also, since the PCI does not assess the structural integrity or capacity of the pavement structure, further testing may be needed to validate and refine the treatment strategy.


Figure 4. Visual representation of PCI scale on typical pavement surfaces.



Note: Photographs shown are not specific to Washington Municipal Airport.

Generally, pavements with relatively high PCIs that are not exhibiting significant load-related distress will benefit from preventive maintenance actions, such as crack sealing or joint resealing. As the PCI drops, the pavements may require major rehabilitation, such as an overlay or whitetopping. In some situations where the PCI has dropped low enough, reconstruction may be the only viable alternative due to the substantial damage to the pavement structure. Figure 5 illustrates how the appropriate repair type varies with the PCI of a pavement section and provides the corresponding colors used on the maps and charts in this report for each PCI range.

Figure 5. PCI versus repair type.



The types of distress identified during the PCI inspection provide insight into the cause of pavement deterioration, which is useful when selecting M&R strategies. Understanding the cause of distress helps in selecting a rehabilitation alternative that corrects the cause and thus eliminates or delays its recurrence. Appendix A identifies the distress types considered during a PCI inspection and describes the likely cause of each distress type. The PCI procedure is based on visual signs of pavement deterioration and does not provide a measure of structural capacity. PCI distress types are characterized as follows:

- Load-related distress types are caused by aircraft or vehicular traffic and may indicate a structural deficiency. Examples of load-related distress include alligator cracking on asphalt-surfaced pavements and shattered slabs or corner breaks on concrete pavements.
- Climate- and durability-related distress types often signify the presence of aged or environmentally susceptible (or both) material and include durability-related issues. Examples of climate- and durability-related distress include weathering on asphalt-surfaced pavements, which is climate related, and durability cracking on concrete pavements, which is durability related.
- Other distress types cannot be attributed solely to load or climate/durability. Examples of this type of distress include depressions on asphalt-surfaced pavements and shrinkage cracking on concrete pavements.

Pavement Evaluation Results

The pavements at Washington Municipal Airport were inspected in March 2026. The 2026 area-weighted condition of Washington Municipal Airport is 88, with conditions ranging from 18 to 99 (on a scale of 0 [*Failed*] to 100 [*Excellent*]). During the previous pavement inspection in 2022, the area-weighted PCI of the airport was 89.

Figure 6 summarizes the overall condition of the pavements at Washington Municipal Airport, and Figure 7 presents area-weighted condition (average PCI adjusted to account for the relative size of the pavement sections) by branch use. Figure 8 is a map that displays the condition of the evaluated pavements. Table 1 summarizes the results of the pavement evaluation. Appendix B presents photographs taken during the PCI inspection, and Appendix C contains detailed information on the distress types observed during the visual survey. Appendix D includes detailed work history information that was collected during the record review process.

Figure 6. Pavement area by PCI range at Washington Municipal Airport.




Figure 7. Area-weighted PCI by branch use at Washington Municipal Airport.
(Values on chart are area weighted.)

FIGURE 8. PCI MAP.



LEGEND

BRANCH IDENTIFIER
SECTION IDENTIFIER
PCI VALUE

SECTION BREAK LINE

PAVEMENT CONDITION INDEX

PCI

86-100
71-85
56-70
41-55
26-40
11-25
0-10

applied pavement TECHNOLOGY

1908 South First Street, Suite 201
Champaign, Illinois 61820
Tel: 217-398-3977
Fax: 217-398-4027

Robinson Engineering Company

1545 Dalton Street
Jesup, Iowa 50648
563-920-5382

AGENCY: Iowa Department of Transportation
Modal Transportation Bureau

LOCATION: Washington Municipal Airport
Washington, Iowa

PAGE TITLE: 2026 Pavement Condition Index Map

PROJECT DATE: NOV. 2025	CREATION DATE: NOV. 2025	PROJECT MANAGER: LJR	JOB NUMBER: 2021-125-AM04
DRAWING SCALE: 1" = 300'	LAST MODIFIED DATE: JUL. 2026	REVISED BY: KEW	DRAWN BY: KEW
FILENAME: Washington.dwg		LAYOUT NAME/NUMBER: PCI	PAGE NUMBER: 10

Table 1. 2026 pavement evaluation results.

Branch	Section	Surface Type	Section Area (sf)	LCD	2026 PCI	% Distress Due to Load	% Distress Due to Climate/Durability	% Distress Due to Other	Type of Distress
A01WA	01	PCC	14,582	6/2/1964	77	0	25	75	Corner Spalling, Faulting, Joint Spalling, Joint Seal Damage, Shrinkage Cracking
A01WA	02	PCC	10,978	10/1/2004	86	0	43	57	Faulting, Joint Spalling, Joint Seal Damage, Large Patch, Shrinkage Cracking
A01WA	03	PCC	3,625	6/1/1984	68	42	27	31	Corner Break, Joint Spalling, Joint Seal Damage, LTD Cracking, Shrinkage Cracking, Small Patch
A01WA	04	PCC	2,659	6/1/1986	75	19	48	33	Corner Spalling, Faulting, Joint Seal Damage, LTD Cracking
A01WA	05	PCC	11,384	8/1/1964	18	79	8	13	Corner Break, Joint Spalling, Joint Seal Damage, Large Patch, LTD Cracking, Shattered Slab, Small Patch
A01WA	06	PCC	1,471	6/30/1994	50	69	11	20	Corner Break, Faulting, Joint Spalling, Joint Seal Damage, Shattered Slab
A01WA	07	PCC	43,029	3/10/2003	91	0	72	28	Faulting, Joint Seal Damage
A01WA	08	PCC	57,327	6/1/2016	92	8	71	21	Corner Spalling, Joint Spalling, Joint Seal Damage, LTD Cracking
A01WA	09	PCC	4,154	1/1/2003	79	75	23	2	Corner Break, Joint Spalling, Joint Seal Damage, LTD Cracking, Shattered Slab
R13WA	01	PCC	198,270	6/3/2015	91	0	90	10	Corner Spalling, Joint Spalling, Joint Seal Damage
R18WA	01	PCC	307,422	6/1/1991	88	0	61	39	ASR, Corner Spalling, Faulting, Joint Spalling, Joint Seal Damage
T03WA	01	PCC	18,055	6/3/2015	91	0	100	0	Joint Seal Damage
T04WA	01	PCC	17,620	6/3/2015	90	0	84	16	Faulting, Joint Seal Damage
TA1WA	01	PCC	32,237	7/1/1991	87	33	48	19	Corner Break, Corner Spalling, Joint Seal Damage, Large Patch, LTD Cracking, Small Patch
TBWA	01	PCC	22,995	6/1/2003	90	0	54	46	Corner Spalling, Joint Spalling, Joint Seal Damage

Table 1. 2026 pavement evaluation results (continued).

Branch	Section	Surface Type	Section Area (sf)	LCD	2026 PCI	% Distress Due to Load	% Distress Due to Climate/Durability	% Distress Due to Other	Type of Distress
TBWA	02	PCC	7,410	6/3/2015	90	29	60	11	Joint Spalling, Joint Seal Damage, LTD Cracking
TBWA	03	PCC	20,474	3/3/2020	99	33	0	67	ASR, Corner Break, Joint Spalling
TH01WA	01	PCC	33,422	3/10/2003	93	0	100	0	Joint Seal Damage
TH01WA	02	PCC	6,606	1/1/1994	77	13	41	46	Joint Spalling, Joint Seal Damage, LTD Cracking, Small Patch
TH01WA	03	PCC	11,948	1/1/1994	65	69	26	5	Faulting, Joint Seal Damage, LTD Cracking

Table notes:

1. See Figure 3 for the location of the branch and section.
2. Surface type: AC = asphalt cement concrete; AAC = asphalt overlay on AC; PCC = portland cement concrete; APC = asphalt overlay on concrete.
3. LCD = last construction date.
4. Distress due to load includes distress types that are attributed to a structural deficiency in the pavement, such as alligator cracking or rutting on asphalt-surfaced pavements or shattered slabs on concrete pavements.
5. Distress due to climate or durability includes distress types that are attributed to either the aging of the pavement and the effects of the environment (such as weathering, raveling, or block cracking on asphalt-surfaced pavements) or to a materials-related problem (such as durability cracking or alkali-silica reaction [ASR] on concrete pavements). If materials-related distresses were recorded during the inspection, further laboratory testing is required to definitively determine the type present.
6. Distress due to other refers to distress types that are not attributed to one factor but rather may be caused by a combination of factors.
7. Distress types are defined by ASTM D5340. L&T cracking = longitudinal and transverse cracking; LTD cracking = longitudinal, transverse, and diagonal cracking; ASR = alkali-silica reaction.

Inspection Comments

Washington Municipal Airport was inspected on March 24, 2026. Twenty pavement sections were defined during the inspection. Alkali-silica reaction (ASR) was recorded at this airport according to the PCI procedure where evidence of a precipitate was observed within some of the cracking in the concrete surface. It should be noted that laboratory testing in the form of petrographic analysis is the only definitive way to validate the presence of ASR; however, the formation of a precipitate is evidence of a reaction consistent with this type of materials-related distress.

Runways

Runway 13/31 consisted of one section that contained low- and high-severity corner spalling, medium- and high-severity joint seal damage, and low-severity joint spalling.

Runway 18/36 was defined by one section. Section 01 had low- and medium-severity ASR, joint spalling, and corner spalling; low-severity faulting; and medium- and high-severity joint seal damage identified. An atypical area of high-severity joint spalling was observed and recorded as an additional sample unit in accordance with ASTM D5340.

Taxiways

Taxiway 03 consisted of one section. Medium- and high-severity joint seal damage were observed throughout Section 01.

Taxiway 04 contained one section. Section 01 had low-severity faulting and medium- and high-severity joint seal damage recorded during the inspection.

Taxiway A1 was defined by one section containing low-severity corner break, corner spalling, and large patching; medium-severity joint seal damage and small patching; and low- and medium-severity longitudinal, transverse, and diagonal (LTD) cracking.

Taxiway B consisted of three sections. Section 01 contained low- and medium-severity corner spalling and joint seal damage and medium- and high-severity joint spalling. Medium-severity joint seal damage and joint spalling and low-severity LTD cracking were observed in Section 02. Section 03 was in *Excellent* condition with no distress except for two atypical areas that contained low-severity ASR, corner break, and joint spalling. These areas were recorded as additional sample units in accordance with ASTM D5340.

Apron

The apron area was defined by nine sections. Section 01 contained all severities of joint spalling and corner spalling, low-severity faulting, medium-severity joint seal damage, and shrinkage cracking. Low-severity faulting; medium-severity joint seal damage, joint spalling, and large patching; and shrinkage cracking were recorded in Section 02. Areas of low-severity corner break, joint spalling, and LTD cracking; high-severity joint seal damage and small patching; and shrinkage cracking were identified in Section 03. Medium-severity corner spalling, low-severity faulting and LTD cracking, and high-severity joint seal damage were recorded in Section 04. Section 05 was in *Poor* condition with all severities of corner break; high-severity joint seal damage; low-severity joint spalling, small patching, and large patching; low- and medium-severity LTD cracking; and medium- and high-severity shattered slab. Section 06 contained low-severity faulting and medium-severity corner break, joint seal damage, joint spalling, and shattered slab. Low-severity faulting and medium-severity joint seal damage were recorded in Section 07. Section 08 had medium-severity corner spalling and low- and medium-severity joint seal damage and joint spalling observed during the inspection. An atypical area of low-severity LTD cracking was identified and recorded as an additional sample unit in accordance with

ASTM D5340. Low-severity corner break and joint spalling and medium-severity joint seal damage, LTD cracking, and shattered slab were noted in Section 09.

T-Hangar

The T-hangar area consisted of three sections. Section 01 contained medium-severity joint seal damage. Section 02 had medium- and high-severity joint seal damage, high-severity joint spalling, and low-severity LTD cracking and small patching identified. Low-severity faulting, high-severity joint seal damage, and low- and medium-severity LTD cracking were noted in Section 03.

PAVEMENT MAINTENANCE AND REHABILITATION PROGRAM

Using the information collected during the pavement inspection, the PAVER pavement management software was used to develop a 5-year M&R program for Washington Municipal Airport (USACE 2021). In addition, a 1-year plan for localized preventive maintenance (such as crack sealing and patching) was prepared.

Analysis Parameters

Critical PCIs

PAVER uses critical PCIs to determine whether localized preventive maintenance or major rehabilitation is the appropriate repair action. Above the critical PCI, localized preventive maintenance activities are recommended. Below the critical PCI, major rehabilitation actions, such as an overlay or reconstruction, are recommended. The Iowa DOT set the critical PCIs at 65 for runways, 60 for taxiways, and 55 for aprons and T-hangars.

Localized Preventive Maintenance Policies and Unit Costs

Localized preventive maintenance policies were developed for asphalt-surfaced and concrete pavements. These policies, shown in Appendix E, identify the localized preventive maintenance actions that the Iowa DOT considered appropriate to correct the various distress types and severities. The Iowa DOT provided unit costs for each of the localized preventive maintenance actions included in these policies. These costs are detailed in Appendix E. This information is of a general nature for the entire State. The localized preventive maintenance policies and unit costs may require adjustments to reflect specific conditions at Washington Municipal Airport.

Major Rehabilitation Unit Costs

PAVER estimates the cost of major rehabilitation based on the predicted PCI of the pavement section. The Iowa DOT provided the costs for major rehabilitation. These costs are detailed in Appendix E. If major rehabilitation is recommended in the 5-year program, further engineering investigation will be needed to identify the most appropriate rehabilitation action and to estimate the cost of such work more accurately.

Budget and Inflation Rate

An unlimited budget with a start date of August 1, 2026, and an inflation rate of 2.3 percent was used during the analysis.

Analysis Approach

The 5-year M&R program was prepared with the goal of maintaining the pavements above established critical PCIs. During this analysis, major rehabilitation was recommended for pavements in the year they dropped below their critical PCI. For the first year (2026) of the analysis only, a localized preventive maintenance plan was developed for those pavement sections that were above their critical PCI. If major rehabilitation was triggered for a section in 2027 or 2028, then localized preventive maintenance was not recommended for 2026. While localized preventive maintenance should be an annual undertaking at Washington Municipal Airport, it is not possible to accurately predict the propagation of cracking and other distress types. Therefore, the airport should budget for maintenance every year and can use the 2026 localized preventive maintenance plan as a baseline for that work. As the pavements age, it can be assumed that the amount of localized preventive maintenance required will increase.

Analysis Results

A summary of the M&R program for Washington Municipal Airport is presented in Table 2. Detailed information on the recommended localized preventive maintenance plan for 2026 is in Appendix F.

Table 2. 5-year M&R program under an unlimited funding analysis scenario.

Year	Branch	Section	Surface Type	Type of Repair	Estimated Cost
2026	A01WA	01	PCC	Preventive Maintenance	\$8,366
2026	A01WA	02	PCC	Preventive Maintenance	\$8,106
2026	A01WA	03	PCC	Preventive Maintenance	\$1,105
2026	A01WA	04	PCC	Preventive Maintenance	\$1,271
2026	A01WA	05	PCC	Major Rehabilitation	\$219,711
2026	A01WA	06	PCC	Major Rehabilitation	\$13,640
2026	A01WA	07	PCC	Preventive Maintenance	\$29,434
2026	A01WA	08	PCC	Preventive Maintenance	\$27,820
2026	A01WA	09	PCC	Preventive Maintenance	\$4,305
2026	R13WA	01	PCC	Preventive Maintenance	\$122,605
2026	R18WA	01	PCC	Preventive Maintenance	\$179,412
2026	T03WA	01	PCC	Preventive Maintenance	\$11,111
2026	T04WA	01	PCC	Preventive Maintenance	\$10,843
2026	TA1WA	01	PCC	Preventive Maintenance	\$12,498
2026	TBWA	01	PCC	Preventive Maintenance	\$6,729
2026	TBWA	02	PCC	Preventive Maintenance	\$4,869
2026	TBWA	03	PCC	Preventive Maintenance	\$27
2026	TH01WA	01	PCC	Preventive Maintenance	\$20,290
2026	TH01WA	02	PCC	Preventive Maintenance	\$3,180
2026	TH01WA	03	PCC	Preventive Maintenance	\$7,608
2030	TH01WA	03	PCC	Major Rehabilitation	\$119,473

Total Estimated Cost: \$812,000

Table notes:

1. See Figure 3 for the location of the branch and section.
2. Surface type: AC = asphalt cement concrete; AAC = asphalt overlay on AC; PCC = portland cement concrete; APC = asphalt overlay on concrete.
3. Type of repair: major rehabilitation, such as pavement reconstruction or an overlay; localized preventive maintenance, such as crack sealing or patching.
4. The estimated costs provided are of a general nature for the entire State and may require adjustments to reflect specific conditions at Washington Municipal Airport.

The recommendations made in this report are based on a broad network-level analysis and meant to provide Washington Municipal Airport with an indication of the type of pavement-related work required during the next 5 years. Further engineering investigation may be necessary to identify which repair action is most appropriate. In addition, the cost estimates provided are based on overall unit costs for the entire State, and Washington Municipal Airport should adjust the plan to reflect local costs.

Because an unlimited budget was used in the analysis, it is possible that the pavement repair program may need to be adjusted to consider economic or operational constraints. The identification of a project need does not necessarily mean that State or Federal funding will be available in the year it is indicated. It is important to remember that regardless of the recommendations presented within this report, Washington Municipal Airport is responsible for repairing pavements where existing conditions pose a hazard to safe operations.

General Maintenance Recommendations

In addition to the specific maintenance actions presented in Appendix F, it is recommended that the following strategies be considered for prolonging pavement life:

1. Regularly inspect all safety areas of the airport and document all inspection activity. A sample form that can be used to perform these inspections is provided in Table 3 of this report.
2. Track all maintenance activities that occur and have the documentation available if requested by the FAA and the Iowa DOT. This is important because this information is used to update the APMS records and is required to remain in compliance with Public Law 103-305 (see the next section of this report for further information on this law).
3. Conduct an aggressive campaign against weed growth through timely herbicide applications and mowing programs of the safety areas. Vegetation growth in pavement cracks is destructive and significantly increases the rate of pavement deterioration.
4. Implement a periodic crack and joint sealing program. Keeping water and debris out of the pavement system by sealing cracks and joints is a proven and cost-effective method for extending the life of the pavement system.
5. Ensure all edges of pavement maintain the required 1.5-inch lip. This enables the water to drain away from the pavement system.
6. Closely monitor the movement of heavy equipment, such as farming, construction, mowing, emergency, and fueling equipment, to ensure such equipment is only operating on pavement designed to accommodate heavy loads. Failure to restrict heavy equipment to appropriate areas may result in the premature failure of airport pavements.
7. Other maintenance necessities include keeping all pavement markings well painted, safety signage clear of debris and weeds, the lighting systems continuously operational, and the operating areas free of debris found.

These recommendations are only a portion of the responsibility each sponsor has in maintaining an airport. Each airport sponsor must provide regular airport maintenance to all its aviation facilities both in the aircraft movement areas and all adjacent areas supporting aviation. It is particularly important to be vigilant in repairing pavements where conditions can pose a hazard to safe operations.

FAA Requirements (Public Law 103-305)

Because Washington Municipal Airport is in the National Plan of Integrated Airport Systems (NPIAS), the airport sponsor is required to keep the airport in a viable operating condition. This includes maintaining airport pavements in accordance with Public Law 103-305 (GPO 1994). Public Law 103-305 states that after January 1, 1995, NPIAS airport sponsors must provide assurances or certifications that an airport has implemented an effective airport pavement maintenance management system (PMMS) before the airport will be considered for Federal funding of pavement replacement or reconstruction projects. To be in full compliance with Federal law, the PMMS must include the following components at minimum: pavement inventory, pavement inspections, record keeping, information retrieval, and program funding.

By undertaking this project, the Iowa DOT has provided Washington Municipal Airport with an excellent basis for meeting the requirements of this law. This report serves as a complete pavement inventory and detailed inspection. To remain in compliance with the law, Washington Municipal Airport will also need to undertake monthly drive-by inspections of pavement conditions and track pavement-related maintenance activities.

FAA Advisory Circular [150/5380-7B](#) (FAA 2014b) provides detailed guidance pertaining to the requirements for an acceptable pavement management program (PMP). Appendix A of the FAA Advisory Circular outlines what needs to be included in a PMP to remain in compliance with this law and Grant Assurance 11. The following is a copy of this appendix, along with instructions for supplementing this report so that all requirements are met. **Note that the italicized text is a direct quotation from the FAA Advisory Circular.**

FAA Advisory Circular 150/5830-7B, Appendix A. Pavement Management Program (PMP)

A-1.0. An effective PMP specifies the procedures to follow to assure that proper preventative and remedial pavement maintenance is performed. The program should identify funding or anticipated funding and other resources available to provide remedial and preventive maintenance activities. An airport sponsor may use any format deemed appropriate, but the program needs to, as a minimum, include the following:

A-1.1. Pavement Inventory. The following must be depicted:

- a. Identification of all runways, taxiways, and aprons with pavement broken down into sections each having similar properties.***

The network definition map in Figure 3 of this report shows the location of all runways, taxiways, aprons, and T-hangars at Washington Municipal Airport. If any new pavements are constructed or any pavement areas are permanently closed, this map must be updated. Project plans should be submitted to the Iowa DOT after project completion.

- b. Dimensions of pavement sections.***

The dimensions of all runways, taxiways, aprons, and T-hangars are stored in the PAVER database. Appendix C provides information on length, width, and area. In addition, the network definition map in Figure 3 is drawn to scale. Any changes to pavement dimensions must be recorded.

- c. Type of pavement surface.***

The type of pavement for each section at Washington Municipal Airport is listed in Table 1 of this report and is also stored in the PAVER database. Any changes to the pavement type through an overlay or reconstruction must be recorded.

- d. Year of construction and/or most recent major rehabilitation.***

Dates for pavement construction, rehabilitation, or reconstruction must be recorded. The current pavement history for Washington Municipal Airport is in Appendix D of this report.

- e. Whether AIP [Airport Improvement Program] or PFC [Passenger Facility Charge] funds were used to construct, reconstruct, or repair the pavement.***

Funding sources for all pavement projects should be recorded.

A-1.2. PMP Pavement Inspection Schedule. Airports must perform a detailed inspection of airfield pavements at least once a year for the PMP. If a pavement condition index (PCI) survey is performed, as set forth in ASTM D5340, Standard Test Method for Airport Pavement

Condition Index Surveys, the frequency of the detailed inspection by PCI surveys may be extended to three years. Less comprehensive routine daily, weekly, and monthly maintenance inspections required for operations should be addressed.

This report consists of a detailed inspection that will extend the inspection period to 3 years. It is the airport sponsor's responsibility to perform monthly drive-by inspections. A sample pavement inspection report form is provided in Table 3 of this report.

A-1.3. Record Keeping. *The airport must record and keep on file complete information about all detailed inspections and maintenance performed until the pavement system is replaced. The types of distress, their locations, and remedial action, scheduled or performed, must be documented. The minimum information recorded includes:*

- a. Inspection date*
- b. Location*
- c. Distress types*
- d. Maintenance scheduled or performed*

Items a through c are satisfied by this inspection report. Item d is the responsibility of the airport, as is record keeping of the monthly drive-by inspections.

A-1.4. Information Retrieval. *An airport sponsor may use any form of record keeping it deems appropriate so long as the information and records from the pavement survey can generate required reports, as necessary.*

Keep this report, monthly drive-by inspection reports, construction updates, and all records of maintenance activities in a readily accessible location so that they can be easily retrieved as requested by the FAA.

Table 3. Pavement inspection report.

Inspected By: _____

Date Inspected: _____

Branch	Section	Distress Description/Dimensions/Severity/ Recommended Action	Description of Repair	Date Performed	Cost	Funding Source
A01WA	01					
A01WA	02					
A01WA	03					
A01WA	04					
A01WA	05					
A01WA	06					

Table 3. Pavement inspection report (continued).

Inspected By: _____

Date Inspected: _____

Branch	Section	Distress Description/Dimensions/Severity/ Recommended Action	Description of Repair	Date Performed	Cost	Funding Source
A01WA	07					
A01WA	08					
A01WA	09					
R13WA	01					
R18WA	01					
T03WA	01					

Table 3. Pavement inspection report (continued).

Inspected By: _____

Date Inspected: _____

Branch	Section	Distress Description/Dimensions/Severity/ Recommended Action	Description of Repair	Date Performed	Cost	Funding Source
T04WA	01					
TA1WA	01					
TBWA	01					
TBWA	02					
TBWA	03					
TH01WA	01					

Table 3. Pavement inspection report (continued).

Inspected By: _____

Date Inspected: _____

Branch	Section	Distress Description/Dimensions/Severity/ Recommended Action	Description of Repair	Date Performed	Cost	Funding Source
TH01WA	02					
TH01WA	03					

Table note: See Figure 3 for the location of the branch and section.

SUMMARY

This report documents the results of the pavement evaluation conducted at Washington Municipal Airport. A visual inspection of the pavements in 2026 found that the overall condition of the pavement network is a PCI of 88. A 5-year pavement repair program, shown in Table 2, was generated for Washington Municipal Airport, which revealed that approximately \$812,000 needs to be expended on M&R. Washington Municipal Airport should utilize these study results to assist in planning for future maintenance needs as part of the airport CIP planning process.

REFERENCES

ASTM International (ASTM). 2024. *Standard Test Method for Airport Pavement Condition Index Surveys*. ASTM D5340. ASTM International, West Conshohocken, PA.

Federal Aviation Administration (FAA). 2014a. [*Guidelines and Procedures for Maintenance of Airport Pavements*](#). Advisory Circular 150/5380-6C. Federal Aviation Administration, Washington, DC.

Federal Aviation Administration (FAA). 2014b. [*Airport Pavement Management Program \(PMP\)*](#). Advisory Circular 150/5380-7B. Federal Aviation Administration, Washington, DC.

Government Printing Office (GPO). 1994. *Federal Aviation Administration Authorization Act of 1994*. P.L. 103-305. Vol 108. Stat. 1569.

U.S. Army Corps of Engineers (USACE). 2009a. [*Asphalt Surfaced Airfields. PAVER Distress Identification Manual*](#). USACE, Washington, DC.

U.S. Army Corps of Engineers (USACE). 2009b. [*Concrete Surfaced Airfields. PAVER Distress Identification Manual*](#). USACE, Washington, DC.

U.S. Army Corps of Engineers (USACE). 2021. PAVER. (Software). USACE, Transportation Systems Center, Omaha, NE.

APPENDIX A

CAUSE OF DISTRESS TABLES

Table A-1. Cause of pavement distress, asphalt-surfaced pavements (USACE 2009a).

Distress Type	Probable Cause of Distress
Alligator Cracking	Fatigue failure of the asphalt surface under repeated traffic loading.
Bleeding	Excessive amounts of asphalt cement or tars in the mix or low air void content, or both.
Block Cracking	Shrinkage of the asphalt and daily temperature cycling; it is not load associated.
Corrugation	Traffic action combined with an unstable pavement layer.
Depression	Settlement of the foundation soil or can be “built up” during construction.
Jet-Blast Erosion	Bituminous binder has been burned or carbonized.
Joint Reflection Cracking	Movement of the concrete slab beneath the asphalt surface due to thermal and moisture changes.
L&T Cracking	Cracks may be caused by (1) a poorly constructed paving lane joint, (2) shrinkage of the asphalt surface due to low temperatures or hardening of the asphalt, or (3) reflective cracking caused by cracks in an underlying concrete slab.
Oil Spillage	Deterioration or softening of the pavement surface caused by the spilling of oil, fuel, or other solvents.
Patching	N/A
Polished Aggregate	Repeated traffic applications.
Raveling	Asphalt binder may have hardened significantly, causing coarse aggregate pieces to dislodge.
Rutting	Usually caused by consolidation or lateral movement of the materials due to traffic loads.
Shoving	Where concrete pavements adjoin flexible pavements, concrete “growth” may shove the asphalt pavement.
Slippage Cracking	Low-strength surface mix or poor bond between the surface and the next layer of the pavement structure.
Swelling	Usually caused by frost action or by swelling soil.
Weathering	Asphalt binder and/or fine aggregate may wear away as the pavement ages and hardens.

Table A-2. Cause of pavement distress, concrete pavements (USACE 2009b).

Distress Type	Probable Cause of Distress
ASR	Chemical reaction of alkalis in the cement with certain reactive silica minerals. ASR may be accelerated by the use of chemical pavement deicers.
Blowup	Incompressible materials in the joints.
Corner Break	Load repetition combined with loss of support and curling stresses.
Durability Cracking	Concrete's inability to withstand environmental factors, such as freeze–thaw cycles.
Faulting	Upheaval or consolidation.
Joint Seal Damage	Stripping of joint sealant, extrusion of joint sealant, weed growth, hardening of the filler (oxidation), loss of bond to the slab edges, or absence of sealant in the joint.
LTD Cracking	Combination of load repetition, curling stresses, and shrinkage stresses.
Patching (Small and Large)	N/A
Popouts	Freeze–thaw action in combination with expansive aggregates.
Pumping	Poor drainage, poor joint sealant.
Scaling	Over finishing of concrete, deicing salts, improper construction, freeze–thaw cycles, and poor aggregate.
Shattered Slab	Load repetition.
Shrinkage Cracking	Setting and curing of the concrete.
Spalling (Joint and Corner)	Excessive stresses at the joint caused by infiltration of incompressible materials or traffic loads; weak concrete at the joint combined with traffic loads.

APPENDIX B

INSPECTION PHOTOGRAPHS

A01WA-01. Overview.



A01WA-01. Joint Spalling (Sample Unit No. 01).



A01WA-02. Overview.



A01WA-02. Joint Spalling (Sample Unit No. 03).



A01WA-03. Overview.



A01WA-03. LTD Cracking (Sample Unit No. 01).



A01WA-04. Overview.



A01WA-04. LTD Cracking (Sample Unit No. 01).



A01WA-05. Overview.



A01WA-05. Corner Break (Sample Unit No. 02).



A01WA-05. LTD Cracking (Sample Unit No. 02).



A01WA-06. Overview.



A01WA-06. Corner Break (Sample Unit No. 01).



A01WA-07. Overview.



A01WA-07. Joint Seal Damage (Sample Unit No. 17).



A01WA-08. Overview.



A01WA-08. Joint Spalling (Sample Unit No. 02).



A01WA-08. LTD Cracking (Additional Sample Unit No. 03).



A01WA-09. Overview.



A01WA-09. LTD Cracking (Sample Unit No. 01).



A01WA-09. Shattered Slab (Sample Unit No. 01).




R13WA-01. Overview.



R13WA-01. Corner Spalling (Sample Unit No. 85).



R13WA-01. Joint Seal Damage (Sample Unit No. 45).



R18WA-01. Overview.



R18WA-01. ASR (Additional Sample Unit No. 08).



R18WA-01. ASR (Sample Unit No. 12).



R18WA-01. Joint Seal Damage (Sample Unit No. 03).



R18WA-01. Joint Spalling (Additional Sample Unit No. 08).



T03WA-01. Overview.



T03WA-01. Joint Seal Damage (Sample Unit No. 02).



T04WA-01. Overview.



T04WA-01. Faulting (Sample Unit No. 02).



T04WA-01. Joint Seal Damage (Sample Unit No. 09).



TA1WA-01. Overview.



TA1WA-01. Corner Break (Sample Unit No. 02).



TA1WA-01. Small Patching (Sample Unit No. 02).



TBWA-01. Overview.



TBWA-01. Joint Seal Damage (Sample Unit No. 05).



TBWA-01. Joint Spalling (Sample Unit No. 02).



TBWA-02. Overview.



TBWA-02. Joint Seal Damage (Sample Unit No. 02).



TBWA-02. LTD Cracking (Sample Unit No. 03).



TBWA-03. Overview.



TBWA-03. ASR (Additional Sample Unit No. 10).




TBWA-03. Joint Spalling (Additional Sample Unit No. 12).



TH01WA-01. Overview.



TH01WA-01. Joint Seal Damage (Sample Unit No. 02).



TH01WA-02. Overview.



TH01WA-02. Joint Seal Damage (Sample Unit No. 02).



TH01WA-02. Joint Spalling (Sample Unit No. 01).



TH01WA-03. Overview.



TH01WA-03. Joint Seal Damage (Sample Unit No. 01).



TH01WA-03. LTD Cracking (Sample Unit No. 01).



APPENDIX C

INSPECTION REPORT

RE-INSPECTION REPORT

WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 1

Branch - Section ID: A01WA - 001

Branch Name: APRON 01

Use: APRON

LCD: 6/2/1964

PCI Family: IowaPCCAP_SE_General

Surface Type: PCC

Rank: P

Section Area (sf): 14,582.00

Length (ft): 151.00

Width (ft): 100.00

From: .

To: .

Slabs: 77

Section Comments:

Slab Length (ft): 12.50

Slab Width (ft): 15.00

Joint Length (ft): 1,870.03

Last Insp Date: 3/24/2026

Inspection Comments:

PCI: 77

Total Samples: 4

Surveyed: 3

Sample Number: 001

Sample Type: R

Sample Comments:

Sample PCI: 81

Sample Area (Slabs): 20.00

65 JT SEAL DMG	M	20.00 Slabs
73 SHRINKAGE CR	N	1.00 Slabs
74 JOINT SPALL	L	2.00 Slabs
74 JOINT SPALL	M	2.00 Slabs
75 CORNER SPALL	L	1.00 Slabs

Sample Number: 002

Sample Type: R

Sample Comments:

Sample PCI: 83

Sample Area (Slabs): 20.00

65 JT SEAL DMG	M	20.00 Slabs
74 JOINT SPALL	L	1.00 Slabs
74 JOINT SPALL	M	1.00 Slabs
75 CORNER SPALL	L	1.00 Slabs
75 CORNER SPALL	M	1.00 Slabs

Sample Number: 003

Sample Type: R

Sample Comments:

Sample PCI: 68

Sample Area (Slabs): 20.00

65 JT SEAL DMG	M	20.00 Slabs
71 FAULTING	L	3.00 Slabs
74 JOINT SPALL	H	1.00 Slabs
74 JOINT SPALL	M	1.00 Slabs
75 CORNER SPALL	H	1.00 Slabs

RE-INSPECTION REPORT

WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 2

Branch - Section ID: A01WA - 002

Branch Name: APRON 01

Use: APRON

LCD: 10/1/2004

PCI Family: IowaPCCAP_SE_General

Surface Type: PCC

Rank: P

Section Area (sf): 10,978.00

Length (ft): 224.00

Width (ft): 50.00

From: .

To: .

Slabs: 110

Section Comments:

Slab Length (ft): 10.00

Slab Width (ft): 10.00

Joint Length (ft): 1,927.03

Last Insp Date: 3/24/2026

Inspection Comments:

PCI: 86

Total Samples: 6

Surveyed: 4

Sample Number: 001

Sample Type: R

Sample Comments:

Sample PCI: 81

Sample Area (Slabs): 24.00

65 JT SEAL DMG

M

24.00 Slabs

71 FAULTING

L

4.00 Slabs

73 SHRINKAGE CR

N

1.00 Slabs

Sample Number: 003

Sample Type: R

Sample Comments:

Sample PCI: 81

Sample Area (Slabs): 20.00

65 JT SEAL DMG

M

20.00 Slabs

67 LARGE PATCH

M

1.00 Slabs

74 JOINT SPALL

M

1.00 Slabs

Sample Number: 004

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 20.00

65 JT SEAL DMG

M

20.00 Slabs

Sample Number: 005

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 15.00

65 JT SEAL DMG

M

15.00 Slabs

RE-INSPECTION REPORT WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 3

Branch - Section ID: A01WA - 003

Branch Name: APRON 01

Use: APRON

LCD: 6/1/1984

PCI Family: IowaPCCAP_SE_General

Surface Type: PCC

Rank: P

Section Area (sf): 3,625.00

Length (ft): 65.00

Width (ft): 60.00

From: .

To: .

Slabs: 12

Section Comments:

Slab Length (ft): 15.00

Slab Width (ft): 20.00

Joint Length (ft): 306.73

Last Insp Date: 3/24/2026

Inspection Comments:

PCI: 68

Total Samples: 1

Surveyed: 1

Sample Number: 001

Sample Type: R

Sample Comments:

Sample PCI: 68

Sample Area (Slabs): 12.00

62 CORNER BREAK

L

1.00 Slabs

63 LINEAR CR

L

2.00 Slabs

65 JT SEAL DMG

H

12.00 Slabs

66 SMALL PATCH

H

1.00 Slabs

73 SHRINKAGE CR

N

1.00 Slabs

74 JOINT SPALL

L

1.00 Slabs

RE-INSPECTION REPORT WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 4

Branch - Section ID: A01WA - 004

Branch Name: APRON 01

Use: APRON

LCD: 6/1/1986

PCI Family: IowaPCCAP_SE_General

Surface Type: PCC

Rank: P

Section Area (sf): 2,659.00

Length (ft): 130.00

Width (ft): 25.00

From: .

To: .

Slabs: 21

Section Comments:

Slab Length (ft): 10.00

Slab Width (ft): 12.50

Joint Length (ft): 345.98

Last Insp Date: 3/24/2026

Inspection Comments:

PCI: 75

Total Samples: 1

Surveyed: 1

Sample Number: 001

Sample Type: R

Sample Comments:

Sample PCI: 75

Sample Area (Slabs): 21.00

63 LINEAR CR

L

1.00 Slabs

65 JT SEAL DMG

H

21.00 Slabs

71 FAULTING

L

1.00 Slabs

75 CORNER SPALL

M

1.00 Slabs

RE-INSPECTION REPORT

WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 5

Branch - Section ID: A01WA - 005

Branch Name: APRON 01

Use: APRON

LCD: 8/1/1964

PCI Family: IowaPCCAP_SE_General

Surface Type: PCC

Rank: P

Section Area (sf): 11,384.00

Length (ft): 135.00

Width (ft): 115.00

From: .

To: .

Slabs: 33

Section Comments:

Slab Length (ft): 17.00

Slab Width (ft): 20.00

Joint Length (ft): 1,055.53

Last Insp Date: 3/24/2026

Inspection Comments:

PCI: 18

Total Samples: 2

Surveyed: 2

Sample Number: 001

Sample Type: R

Sample Comments:

Sample PCI: 13

Sample Area (Slabs): 12.00

62 CORNER BREAK	M	1.00 Slabs
63 LINEAR CR	L	1.00 Slabs
63 LINEAR CR	M	7.00 Slabs
65 JT SEAL DMG	H	12.00 Slabs
66 SMALL PATCH	L	2.00 Slabs
67 LARGE PATCH	L	7.00 Slabs
72 SHAT. SLAB	M	2.00 Slabs
74 JOINT SPALL	L	1.00 Slabs

Sample Number: 002

Sample Type: R

Sample Comments:

Sample PCI: 21

Sample Area (Slabs): 21.00

62 CORNER BREAK	H	1.00 Slabs
62 CORNER BREAK	L	1.00 Slabs
62 CORNER BREAK	M	2.00 Slabs
63 LINEAR CR	L	5.00 Slabs
63 LINEAR CR	M	3.00 Slabs
65 JT SEAL DMG	H	21.00 Slabs
67 LARGE PATCH	L	11.00 Slabs
72 SHAT. SLAB	H	2.00 Slabs

RE-INSPECTION REPORT WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 6

Branch - Section ID: A01WA - 006

Branch Name: APRON 01

Use: APRON

LCD: 6/30/1994

PCI Family: IowaPCCAP_SE_General

Surface Type: PCC

Rank: P

Section Area (sf): 1,471.00

Length (ft): 120.00

Width (ft): 9.00

From: A01WA-02

To: A01WA-01

Slabs: 13

Section Comments:

Slab Length (ft): 12.50

Slab Width (ft): 9.00

Joint Length (ft): 105.42

Last Insp Date: 3/24/2026

Inspection Comments:

PCI: 50

Total Samples: 1

Surveyed: 1

Sample Number: 001

Sample Type: R

Sample Comments:

Sample PCI: 50

Sample Area (Slabs): 13.00

62 CORNER BREAK

M

2.00 Slabs

65 JT SEAL DMG

M

13.00 Slabs

71 FAULTING

L

1.00 Slabs

72 SHAT. SLAB

M

1.00 Slabs

74 JOINT SPALL

M

1.00 Slabs

RE-INSPECTION REPORT WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 7

Branch - Section ID: A01WA - 007

Branch Name: APRON 01

Use: APRON

LCD: 3/10/2003

PCI Family: IowaPCCAP_SE_General

Surface Type: PCC

Rank: P

Section Area (sf): 43,029.00

Length (ft): 327.00

Width (ft): 130.00

From: TBWA-01

To: SEE MAP

Slabs: 495

Section Comments:

Slab Length (ft): 10.00

Slab Width (ft): 8.70

Joint Length (ft): 8,786.18

Last Insp Date: 3/24/2026

Inspection Comments:

PCI: 91

Total Samples: 25

Surveyed: 7

Sample Number: 01

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 24.00

65 JT SEAL DMG

M

24.00 Slabs

Sample Number: 04

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 20.00

65 JT SEAL DMG

M

20.00 Slabs

Sample Number: 08

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 20.00

65 JT SEAL DMG

M

20.00 Slabs

Sample Number: 12

Sample Type: R

Sample Comments:

Sample PCI: 80

Sample Area (Slabs): 20.00

65 JT SEAL DMG

M

20.00 Slabs

71 FAULTING

L

4.00 Slabs

Sample Number: 15

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 20.00

65 JT SEAL DMG

M

20.00 Slabs

Sample Number: 17

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 20.00

65 JT SEAL DMG

M

20.00 Slabs

RE-INSPECTION REPORT WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 8

Sample Number: 21

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 20.00

65 JT SEAL DMG

M

20.00 Slabs

RE-INSPECTION REPORT

WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 9

Branch - Section ID: A01WA - 008

Branch Name: APRON 01

Use: APRON

LCD: 6/1/2016

PCI Family: IowaPCCAP_SE_General

Surface Type: PCC

Rank: P

Section Area (sf): 57,327.00

Length (ft): 500.00

Width (ft): 50.00

From: .

To: .

Slabs: 579

Section Comments:

Slab Length (ft): 10.00

Slab Width (ft): 10.00

Joint Length (ft): 10,302.82

Last Insp Date: 3/24/2026

Inspection Comments:

PCI: 92

Total Samples: 31

Surveyed: 9

Sample Number: 02

Sample Type: R

Sample Comments:

Sample PCI: 94

Sample Area (Slabs): 20.00

65 JT SEAL DMG

L

20.00 Slabs

74 JOINT SPALL

M

1.00 Slabs

Sample Number: 03

Sample Type: A

Sample Comments:

Sample PCI: 86

Sample Area (Slabs): 20.00

63 LINEAR CR

L

2.00 Slabs

65 JT SEAL DMG

L

20.00 Slabs

75 CORNER SPALL

M

1.00 Slabs

Sample Number: 05

Sample Type: R

Sample Comments:

Sample PCI: 91

Sample Area (Slabs): 20.00

65 JT SEAL DMG

L

20.00 Slabs

74 JOINT SPALL

M

2.00 Slabs

Sample Number: 11

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 20.00

65 JT SEAL DMG

M

20.00 Slabs

Sample Number: 14

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 20.00

65 JT SEAL DMG

M

20.00 Slabs

RE-INSPECTION REPORT

WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 10

Sample Number: 19

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 25.00

65 JT SEAL DMG

M

25.00 Slabs

Sample Number: 21

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 16.00

65 JT SEAL DMG

M

16.00 Slabs

Sample Number: 25

Sample Type: R

Sample Comments:

Sample PCI: 91

Sample Area (Slabs): 20.00

65 JT SEAL DMG

M

20.00 Slabs

74 JOINT SPALL

L

1.00 Slabs

Sample Number: 27

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 16.00

65 JT SEAL DMG

M

16.00 Slabs

RE-INSPECTION REPORT WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 11

Branch - Section ID: A01WA - 009

Branch Name: APRON 01

Use: APRON

LCD: 1/1/2003

PCI Family: IowaPCCAP_SE_General

Surface Type: PCC

Rank: P

Section Area (sf): 4,154.00

Length (ft): 75.00

Width (ft): 61.00

From: A01WA-05

To: SEE MAP

Slabs: 49

Section Comments:

Slab Length (ft): 9.50

Slab Width (ft): 9.00

Joint Length (ft): 775.33

Last Insp Date: 3/24/2026

Inspection Comments:

PCI: 79

Total Samples: 2

Surveyed: 2

Sample Number: 01

Sample Type: R

Sample Comments:

Sample PCI: 62

Sample Area (Slabs): 21.00

62 CORNER BREAK

L

2.00 Slabs

63 LINEAR CR

M

2.00 Slabs

65 JT SEAL DMG

M

21.00 Slabs

72 SHAT. SLAB

M

1.00 Slabs

Sample Number: 02

Sample Type: R

Sample Comments:

Sample PCI: 92

Sample Area (Slabs): 28.00

65 JT SEAL DMG

M

28.00 Slabs

74 JOINT SPALL

L

1.00 Slabs

RE-INSPECTION REPORT WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 12

Branch - Section ID: R13WA - 001

Branch Name: RUNWAY 13/31

Use: RUNWAY

LCD: 6/3/2015

PCI Family: IowaPCCRW_SE_General

Surface Type: PCC

Rank: S

Section Area (sf): 198,270.00

Length (ft): 3,400.00

Width (ft): 60.00

From: RUNWAY 31 APPROACH

To: RUNWAY 13 APPROACH

Slabs: 1,983

Section Comments: TYP SLAB SIZE ENTERED; SOME VARY

Slab Length (ft): 10.00

Slab Width (ft): 10.00

Joint Length (ft): 36,291.19

Last Insp Date: 3/24/2026

Inspection Comments:

PCI: 91

Total Samples: 85

Surveyed: 9

Sample Number: 005

Sample Type: R

Sample Comments:

Sample PCI: 88

Sample Area (Slabs): 24.00

65 JT SEAL DMG

H

24.00 Slabs

Sample Number: 015

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 24.00

65 JT SEAL DMG

M

24.00 Slabs

Sample Number: 025

Sample Type: R

Sample Comments:

Sample PCI: 91

Sample Area (Slabs): 24.00

65 JT SEAL DMG

M

24.00 Slabs

75 CORNER SPALL

L

1.00 Slabs

Sample Number: 035

Sample Type: R

Sample Comments:

Sample PCI: 92

Sample Area (Slabs): 24.00

65 JT SEAL DMG

M

24.00 Slabs

74 JOINT SPALL

L

1.00 Slabs

Sample Number: 040

Sample Type: R

Sample Comments:

Sample PCI: 90

Sample Area (Slabs): 24.00

65 JT SEAL DMG

M

24.00 Slabs

74 JOINT SPALL

L

2.00 Slabs

RE-INSPECTION REPORT

WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 13

Sample Number: 045

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 24.00

65 JT SEAL DMG

M

24.00 Slabs

Sample Number: 065

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 24.00

65 JT SEAL DMG

M

24.00 Slabs

Sample Number: 075

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 24.00

65 JT SEAL DMG

M

24.00 Slabs

Sample Number: 085

Sample Type: R

Sample Comments:

Sample PCI: 87

Sample Area (Slabs): 24.00

65 JT SEAL DMG

M

24.00 Slabs

74 JOINT SPALL

L

1.00 Slabs

75 CORNER SPALL

H

1.00 Slabs

RE-INSPECTION REPORT

WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 14

Branch - Section ID: R18WA - 001

Branch Name: RUNWAY 18/36

Use: RUNWAY

LCD: 6/1/1991

PCI Family: IowaPCCRW_SE_General

Surface Type: PCC

Rank: P

Section Area (sf): 307,422.00

Length (ft): 4,000.00

Width (ft): 75.00

From: .

To: .

Slabs: 1,921

Section Comments:

Slab Length (ft): 12.80

Slab Width (ft): 12.50

Joint Length (ft): 44,435.29

Last Insp Date: 3/24/2026

Inspection Comments:

PCI: 88

Total Samples: 82

Surveyed: 10

Sample Number: 03

Sample Type: R

Sample Comments:

Sample PCI: 88

Sample Area (Slabs): 24.00

65 JT SEAL DMG

H

24.00 Slabs

Sample Number: 08

Sample Type: A

Sample Comments:

Sample PCI: 65

Sample Area (Slabs): 24.00

65 JT SEAL DMG

M

24.00 Slabs

74 JOINT SPALL

H

2.00 Slabs

74 JOINT SPALL

M

1.00 Slabs

75 CORNER SPALL

M

1.00 Slabs

76 ASR

L

2.00 Slabs

Sample Number: 12

Sample Type: R

Sample Comments:

Sample PCI: 80

Sample Area (Slabs): 24.00

65 JT SEAL DMG

M

24.00 Slabs

75 CORNER SPALL

M

1.00 Slabs

76 ASR

M

1.00 Slabs

Sample Number: 22

Sample Type: R

Sample Comments:

Sample PCI: 86

Sample Area (Slabs): 24.00

65 JT SEAL DMG

M

24.00 Slabs

76 ASR

L

3.00 Slabs

Sample Number: 32

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 24.00

65 JT SEAL DMG

M

24.00 Slabs

RE-INSPECTION REPORT

WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 15

Sample Number: 42

Sample Type: R

Sample Comments:

Sample PCI: 90

Sample Area (Slabs): 24.00

65 JT SEAL DMG

M

24.00 Slabs

75 CORNER SPALL

L

2.00 Slabs

Sample Number: 52

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 24.00

65 JT SEAL DMG

M

24.00 Slabs

Sample Number: 62

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 24.00

65 JT SEAL DMG

M

24.00 Slabs

Sample Number: 72

Sample Type: R

Sample Comments:

Sample PCI: 80

Sample Area (Slabs): 24.00

65 JT SEAL DMG

M

24.00 Slabs

71 FAULTING

L

2.00 Slabs

74 JOINT SPALL

L

1.00 Slabs

75 CORNER SPALL

L

1.00 Slabs

76 ASR

L

1.00 Slabs

Sample Number: 80

Sample Type: R

Sample Comments:

Sample PCI: 88

Sample Area (Slabs): 24.00

65 JT SEAL DMG

M

24.00 Slabs

74 JOINT SPALL

L

1.00 Slabs

74 JOINT SPALL

M

1.00 Slabs

RE-INSPECTION REPORT WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 16

Branch - Section ID: T03WA - 001

Branch Name: TAXIWAY 03

Use: TAXIWAY

LCD: 6/3/2015

PCI Family: IowaPCCTW_SE_General

Surface Type: PCC

Rank: P

Section Area (sf): 18,055.00

Length (ft): 495.00

Width (ft): 35.00

From: SEE MAP

To: SEE MAP

Slabs: 206

Section Comments: SLAB SIZE VARIES

Slab Length (ft): 10.00

Slab Width (ft): 8.75

Joint Length (ft): 3,316.60

Last Insp Date: 3/24/2026

Inspection Comments:

PCI: 91

Total Samples: 10

Surveyed: 5

Sample Number: 02

Sample Type: R

Sample Comments:

Sample PCI: 88

Sample Area (Slabs): 20.00

65 JT SEAL DMG

H

20.00 Slabs

Sample Number: 03

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 20.00

65 JT SEAL DMG

M

20.00 Slabs

Sample Number: 07

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 24.00

65 JT SEAL DMG

M

24.00 Slabs

Sample Number: 09

Sample Type: R

Sample Comments:

Sample PCI: 88

Sample Area (Slabs): 24.00

65 JT SEAL DMG

H

24.00 Slabs

Sample Number: 10

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 24.00

65 JT SEAL DMG

M

24.00 Slabs

RE-INSPECTION REPORT WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 17

Branch - Section ID: T04WA - 001

Branch Name: TAXIWAY 04

Use: TAXIWAY

LCD: 6/3/2015

PCI Family: IowaPCCTW_SE_General

Surface Type: PCC

Rank: P

Section Area (sf): 17,620.00

Length (ft): 495.00

Width (ft): 35.00

From: SEE MAP

To: SEE MAP

Slabs: 201

Section Comments: SLAB SIZE VARIES

Slab Length (ft): 10.00

Slab Width (ft): 8.75

Joint Length (ft): 3,236.69

Last Insp Date: 3/24/2026

Inspection Comments:

PCI: 90

Total Samples: 10

Surveyed: 5

Sample Number: 02

Sample Type: R

Sample Comments:

Sample PCI: 80

Sample Area (Slabs): 20.00

65 JT SEAL DMG

M

20.00 Slabs

71 FAULTING

L

4.00 Slabs

Sample Number: 03

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 21.00

65 JT SEAL DMG

M

21.00 Slabs

Sample Number: 06

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 20.00

65 JT SEAL DMG

M

20.00 Slabs

Sample Number: 09

Sample Type: R

Sample Comments:

Sample PCI: 88

Sample Area (Slabs): 20.00

65 JT SEAL DMG

H

20.00 Slabs

Sample Number: 10

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 20.00

65 JT SEAL DMG

M

20.00 Slabs

RE-INSPECTION REPORT

WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 18

Branch - Section ID: TA1WA - 001

Branch Name: TAXIWAY A1

Use: TAXIWAY

LCD: 7/1/1991

PCI Family: IowaPCCTW_SE_General

Surface Type: PCC

Rank: P

Section Area (sf): 32,237.00

Length (ft): 755.00

Width (ft): 45.50

From: .

To: .

Slabs: 147

Section Comments:

Slab Length (ft): 12.50

Slab Width (ft): 17.50

Joint Length (ft): 3,669.87

Last Insp Date: 3/24/2026

Inspection Comments:

PCI: 87

Total Samples: 7

Surveyed: 4

Sample Number: 002

Sample Type: R

Sample Comments:

Sample PCI: 87

Sample Area (Slabs): 26.00

62 CORNER BREAK

L

1.00 Slabs

65 JT SEAL DMG

M

26.00 Slabs

66 SMALL PATCH

M

1.00 Slabs

Sample Number: 003

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 22.00

65 JT SEAL DMG

M

22.00 Slabs

Sample Number: 005

Sample Type: R

Sample Comments:

Sample PCI: 88

Sample Area (Slabs): 22.00

65 JT SEAL DMG

M

22.00 Slabs

67 LARGE PATCH

L

2.00 Slabs

Sample Number: 006

Sample Type: R

Sample Comments:

Sample PCI: 79

Sample Area (Slabs): 22.00

63 LINEAR CR

L

1.00 Slabs

63 LINEAR CR

M

1.00 Slabs

65 JT SEAL DMG

M

22.00 Slabs

75 CORNER SPALL

L

1.00 Slabs

RE-INSPECTION REPORT WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 19

Branch - Section ID: TBWA - 001

Branch Name: TAXIWAY B

Use: TAXIWAY

LCD: 6/1/2003

PCI Family: IowaPCCTW_SE_General

Surface Type: PCC

Rank: P

Section Area (sf): 22,995.00

Length (ft): 657.00

Width (ft): 35.00

From: APRON 01 SECT 01

To: SEE MAP

Slabs: 131

Section Comments:

Slab Length (ft): 15.00

Slab Width (ft): 11.67

Joint Length (ft): 2,811.44

Last Insp Date: 3/24/2026

Inspection Comments:

PCI: 90

Total Samples: 7

Surveyed: 4

Sample Number: 02

Sample Type: R

Sample Comments:

Sample PCI: 76

Sample Area (Slabs): 21.00

65 JT SEAL DMG

M

21.00 Slabs

74 JOINT SPALL

H

1.00 Slabs

74 JOINT SPALL

M

2.00 Slabs

75 CORNER SPALL

L

1.00 Slabs

Sample Number: 03

Sample Type: R

Sample Comments:

Sample PCI: 89

Sample Area (Slabs): 21.00

65 JT SEAL DMG

M

21.00 Slabs

75 CORNER SPALL

M

1.00 Slabs

Sample Number: 05

Sample Type: R

Sample Comments:

Sample PCI: 98

Sample Area (Slabs): 21.00

65 JT SEAL DMG

L

21.00 Slabs

Sample Number: 06

Sample Type: R

Sample Comments:

Sample PCI: 98

Sample Area (Slabs): 15.00

65 JT SEAL DMG

L

15.00 Slabs

RE-INSPECTION REPORT WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 20

Branch - Section ID: TBWA - 002

Branch Name: TAXIWAY B

Use: TAXIWAY

LCD: 6/3/2015

PCI Family: IowaPCCTW_SE_General

Surface Type: PCC

Rank: P

Section Area (sf): 7,410.00

Length (ft): 202.00

Width (ft): 35.00

From: SEE MAP

To: SEE MAP

Slabs: 85

Section Comments:

Slab Length (ft): 10.00

Slab Width (ft): 8.75

Joint Length (ft): 1,339.46

Last Insp Date: 3/24/2026

Inspection Comments:

PCI: 90

Total Samples: 4

Surveyed: 3

Sample Number: 02

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 20.00

65 JT SEAL DMG

M

20.00 Slabs

Sample Number: 03

Sample Type: R

Sample Comments:

Sample PCI: 87

Sample Area (Slabs): 20.00

63 LINEAR CR

L

2.00 Slabs

65 JT SEAL DMG

M

20.00 Slabs

Sample Number: 04

Sample Type: R

Sample Comments:

Sample PCI: 89

Sample Area (Slabs): 20.00

65 JT SEAL DMG

M

20.00 Slabs

74 JOINT SPALL

M

1.00 Slabs

RE-INSPECTION REPORT WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 21

Branch - Section ID: TBWA - 003

Branch Name: TAXIWAY B

Use: TAXIWAY

LCD: 3/3/2020

PCI Family: IowaPCCTW_SE_General

Surface Type: PCC

Rank: P

Section Area (sf): 20,474.00

Length (ft): 460.00

Width (ft): 35.00

From: .

To: .

Slabs: 234

Section Comments:

Slab Length (ft): 10.00

Slab Width (ft): 8.75

Joint Length (ft): 3,757.81

Last Insp Date: 3/24/2026

Inspection Comments:

PCI: 99

Total Samples: 12

Surveyed: 8

Sample Number: 03

Sample Type: R

Sample Comments:

Sample PCI: 100

Sample Area (Slabs): 22.00

NO DISTRESS

Sample Number: 04

Sample Type: R

Sample Comments:

Sample PCI: 100

Sample Area (Slabs): 18.00

NO DISTRESS

Sample Number: 06

Sample Type: R

Sample Comments:

Sample PCI: 100

Sample Area (Slabs): 20.00

NO DISTRESS

Sample Number: 07

Sample Type: R

Sample Comments:

Sample PCI: 100

Sample Area (Slabs): 20.00

NO DISTRESS

Sample Number: 08

Sample Type: R

Sample Comments:

Sample PCI: 100

Sample Area (Slabs): 20.00

NO DISTRESS

Sample Number: 09

Sample Type: R

Sample Comments:

Sample PCI: 100

Sample Area (Slabs): 20.00

NO DISTRESS

RE-INSPECTION REPORT

WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 22

Sample Number: 10

Sample Type: A
Sample PCI: 96
Sample Area (Slabs): 24.00
76 ASR

Sample Comments:

L

1.00 Slabs

Sample Number: 12

Sample Type: A
Sample PCI: 92
Sample Area (Slabs): 21.00
62 CORNER BREAK
74 JOINT SPALL

Sample Comments:

L

1.00 Slabs

L

3.00 Slabs

RE-INSPECTION REPORT WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 23

Branch - Section ID: TH01WA - 001

Branch Name: T-HANGAR 01

Use: T-HANGAR

LCD: 3/10/2003

PCI Family: IowaPCCTH_SE

Surface Type: PCC

Rank: P

Section Area (sf): 33,422.00

Length (ft): 995.00

Width (ft): 25.00

From: .

To: .

Slabs: 413

Section Comments:

Slab Length (ft): 9.00

Slab Width (ft): 9.00

Joint Length (ft): 6,056.64

Last Insp Date: 3/24/2026

Inspection Comments:

PCI: 93

Total Samples: 20

Surveyed: 7

Sample Number: 02

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 21.00

65 JT SEAL DMG

M

21.00 Slabs

Sample Number: 05

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 20.00

65 JT SEAL DMG

M

20.00 Slabs

Sample Number: 08

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 20.00

65 JT SEAL DMG

M

20.00 Slabs

Sample Number: 10

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 20.00

65 JT SEAL DMG

M

20.00 Slabs

Sample Number: 12

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 20.00

65 JT SEAL DMG

M

20.00 Slabs

Sample Number: 16

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 20.00

65 JT SEAL DMG

M

20.00 Slabs

RE-INSPECTION REPORT

WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 24

Sample Number: 19

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 24.00

65 JT SEAL DMG

M

24.00 Slabs

RE-INSPECTION REPORT WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 25

Branch - Section ID: TH01WA - 002

Branch Name: T-HANGAR 01

Use: T-HANGAR

LCD: 1/1/1994

PCI Family: IowaPCCTH_SE

Surface Type: PCC

Rank: P

Section Area (sf): 6,606.00

Length (ft): 150.00

Width (ft): 30.00

From: .

To: .

Slabs: 31

Section Comments: avg

Slab Length (ft): 14.00

Slab Width (ft): 15.00

Joint Length (ft): 648.02

Last Insp Date: 3/24/2026

Inspection Comments:

PCI: 77

Total Samples: 2

Surveyed: 2

Sample Number: 01

Sample Type: R

Sample Comments:

Sample PCI: 59

Sample Area (Slabs): 15.00

63 LINEAR CR

L

2.00 Slabs

65 JT SEAL DMG

H

15.00 Slabs

66 SMALL PATCH

L

1.00 Slabs

74 JOINT SPALL

H

3.00 Slabs

Sample Number: 02

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 16.00

65 JT SEAL DMG

M

16.00 Slabs

RE-INSPECTION REPORT

WASHINGTON MUNICIPAL AIRPORT

Pavement Database: IA 2025

Generate Date: 7/15/2026

Network ID: AWG

Page 26

Branch - Section ID: TH01WA - 003

Branch Name: T-HANGAR 01

Use: T-HANGAR

LCD: 1/1/1994

PCI Family: IowaPCCTH_SE

Surface Type: PCC

Rank: P

Section Area (sf): 11,948.00

Length (ft): 278.00

Width (ft): 40.00

From: .

To: .

Slabs: 119

Section Comments:

Slab Length (ft): 10.00

Slab Width (ft): 10.00

Joint Length (ft): 2,047.92

Last Insp Date: 3/24/2026

Inspection Comments:

PCI: 65

Total Samples: 6

Surveyed: 4

Sample Number: 01

Sample Type: R

Sample Comments:

Sample PCI: 62

Sample Area (Slabs): 20.00

63 LINEAR CR

M

4.00 Slabs

65 JT SEAL DMG

H

20.00 Slabs

71 FAULTING

L

2.00 Slabs

Sample Number: 02

Sample Type: R

Sample Comments:

Sample PCI: 75

Sample Area (Slabs): 20.00

63 LINEAR CR

M

2.00 Slabs

65 JT SEAL DMG

H

20.00 Slabs

Sample Number: 04

Sample Type: R

Sample Comments:

Sample PCI: 58

Sample Area (Slabs): 20.00

63 LINEAR CR

L

2.00 Slabs

63 LINEAR CR

M

5.00 Slabs

65 JT SEAL DMG

H

20.00 Slabs

Sample Number: 05

Sample Type: R

Sample Comments:

Sample PCI: 63

Sample Area (Slabs): 20.00

63 LINEAR CR

L

1.00 Slabs

63 LINEAR CR

M

4.00 Slabs

65 JT SEAL DMG

H

20.00 Slabs

APPENDIX D

WORK HISTORY REPORT

WORK HISTORY

Pavement Database: IA 2025

Generate Date: 6/29/2026

Network ID: AWG

Page 1

Network: WASHINGTON MUNICIPAL AIRPORT

Branch - Section ID: A01WA - 001

LCD: 6/2/1964
Use: APRON
Rank: P
Surface: PCC

Length (ft): 151.00
Width (ft): 100.00
True Area (sf): 14,582.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
06-02-1964	NC-PC	New Construction - PCC	-	6.00	True	6" PCC
06-01-1964	BA-AG	Base Course - Aggregate	-	6.00	False	6" P-209 Base

Branch - Section ID: A01WA - 002

LCD: 10/1/2004
Use: APRON
Rank: P
Surface: PCC

Length (ft): 224.00
Width (ft): 50.00
True Area (sf): 10,978.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
10-01-2004	CR-PC	Complete Reconstruction - PCC	-	-	True	-
06-01-1964	NC-PC	New Construction - PCC	-	-	True	-

Branch - Section ID: A01WA - 003

LCD: 6/1/1984
Use: APRON
Rank: P
Surface: PCC

Length (ft): 65.00
Width (ft): 60.00
True Area (sf): 3,625.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
06-01-1984	NC-PC	New Construction - PCC	-	-	True	-

Branch - Section ID: A01WA - 004

LCD: 6/1/1986
Use: APRON
Rank: P
Surface: PCC

Length (ft): 130.00
Width (ft): 25.00
True Area (sf): 2,659.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
06-01-1986	NC-PC	New Construction - PCC	-	-	True	-

Branch - Section ID: A01WA - 005

LCD: 8/1/1964
Use: APRON
Rank: P
Surface: PCC

Length (ft): 135.00
Width (ft): 115.00
True Area (sf): 11,384.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
06-14-2022	PA-PP	Patching - PCC Partial Depth	-	-	False	ESTIMATED
08-01-1964	NC-PC	New Construction - PCC	-	-	True	-

WORK HISTORY

Pavement Database: IA 2025

Generate Date: 6/29/2026

Network ID: AWG

Page 2

Branch - Section ID: A01WA - 006

LCD: 6/30/1994
Use: APRON
Rank: P
Surface: PCC

Length (ft): 120.00
Width (ft): 9.00
True Area (sf): 1,471.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
06-30-1994	NC-PC	New Construction - PCC	-	-	True	-

Branch - Section ID: A01WA - 007

LCD: 3/10/2003
Use: APRON
Rank: P
Surface: PCC

Length (ft): 327.00
Width (ft): 130.00
True Area (sf): 43,029.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
03-10-2003	NC-PC	New Construction - PCC	-	6.00	True	6" Iowa DOT PCC
03-09-2003	SB-AG	Subbase - Aggregate	-	6.00	False	6" P-154 Aggregate
03-08-2003	SG-CO	Subgrade - Compacted	-	12.00	False	12" P-152

Branch - Section ID: A01WA - 008

LCD: 6/1/2016
Use: APRON
Rank: P
Surface: PCC

Length (ft): 500.00
Width (ft): 50.00
True Area (sf): 57,327.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
06-01-2016	NC-IN	New Construction - Initial	-	-	True	-

Branch - Section ID: A01WA - 009

LCD: 1/1/2003
Use: APRON
Rank: P
Surface: PCC

Length (ft): 75.00
Width (ft): 61.00
True Area (sf): 4,154.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
01-01-2003	NC-IN	New Construction - Initial	-	-	True	ESTIMATED, BETWEEN 1994 AND 2004

Branch - Section ID: R13WA - 001

LCD: 6/3/2015
Use: RUNWAY
Rank: S
Surface: PCC

Length (ft): 3,400.00
Width (ft): 60.00
True Area (sf): 198,270.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
06-03-2015	CR-PC	Complete Reconstruction - PCC	-	6.00	True	6" P-501 PCC
06-02-2015	BA-AG	Base Course - Aggregate	-	6.00	False	6" P-209 GRANULAR BASE
06-01-2015	SG-CO	Subgrade - Compacted	-	12.00	False	12" P-152 COMPACTED SUBGRADE
06-03-1964	NC-PC	New Construction - PCC	-	6.00	True	6" P-501 PCC
06-02-1964	SB-AG	Subbase - Aggregate	-	6.00	False	6" P-154
06-01-1964	SG-CO	Subgrade - Compacted	-	6.00	False	6" P-152 COMPACTED SG

WORK HISTORY

Pavement Database: IA 2025

Generate Date: 6/29/2026

Network ID: AWG

Page 3

Branch - Section ID: R18WA - 001

LCD: 6/1/1991
Use: RUNWAY
Rank: P
Surface: PCC

Length (ft): 4,000.00
Width (ft): 75.00
True Area (sf): 307,422.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
06-01-1991	NC-PC	New Construction - PCC	-	-	True	-

Branch - Section ID: T03WA - 001

LCD: 6/3/2015
Use: TAXIWAY
Rank: P
Surface: PCC

Length (ft): 495.00
Width (ft): 35.00
True Area (sf): 18,055.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
06-03-2015	NC-PC	New Construction - PCC	-	6.00	True	6" P-501 PCC
06-02-2015	BA-AG	Base Course - Aggregate	-	6.00	False	6" P-209 GRANULAR SUBBASE
06-01-2015	SG-CO	Subgrade - Compacted	-	12.00	False	12" P-152 COMPACTED SUBGRADE

Branch - Section ID: T04WA - 001

LCD: 6/3/2015
Use: TAXIWAY
Rank: P
Surface: PCC

Length (ft): 495.00
Width (ft): 35.00
True Area (sf): 17,620.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
06-03-2015	NC-PC	New Construction - PCC	-	6.00	True	6" P-501 PCC
06-02-2015	BA-AG	Base Course - Aggregate	-	6.00	False	6" P-209 GRANULAR SUBBASE
06-01-2015	SG-CO	Subgrade - Compacted	-	12.00	False	6" P-152 COMPACTED SUBGRADE

Branch - Section ID: TA1WA - 001

LCD: 7/1/1991
Use: TAXIWAY
Rank: P
Surface: PCC

Length (ft): 755.00
Width (ft): 45.50
True Area (sf): 32,237.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
07-01-1991	NC-PC	New Construction - PCC	-	-	True	-

Branch - Section ID: TBWA - 001

LCD: 6/1/2003
Use: TAXIWAY
Rank: P
Surface: PCC

Length (ft): 657.00
Width (ft): 35.00
True Area (sf): 22,995.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
06-01-2003	CR-PC	Complete Reconstruction - PCC	-	-	True	-
06-02-1964	NC-PC	New Construction - PCC	-	6.00	True	6" PCC
06-01-1964	BA-AG	Base Course - Aggregate	-	6.00	False	6" P-209 Base

WORK HISTORY

Pavement Database: IA 2025

Generate Date: 6/29/2026

Network ID: AWG

Page 4

Branch - Section ID: TBWA - 002

LCD: 6/3/2015
Use: TAXIWAY
Rank: P
Surface: PCC

Length (ft): 202.00
Width (ft): 35.00
True Area (sf): 7,410.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
06-03-2015	CR-PC	Complete Reconstruction - PCC	-	6.00	True	6" P-501 PCC
06-02-2015	BA-AG	Base Course - Aggregate	-	6.00	False	6" P-209 GRANULAR SUBBASE
06-01-2015	SG-CO	Subgrade - Compacted	-	12.00	False	12" P-152 COMPACTED SUBGRADE
06-01-2003	CR-PC	Complete Reconstruction - PCC	-	-	True	-
06-02-1964	NC-PC	New Construction - PCC	-	6.00	True	6" PCC
06-01-1964	BA-AG	Base Course - Aggregate	-	6.00	False	6" P-209 Base

Branch - Section ID: TBWA - 003

LCD: 3/3/2020
Use: TAXIWAY
Rank: P
Surface: PCC

Length (ft): 460.00
Width (ft): 35.00
True Area (sf): 20,474.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
03-03-2020	NC-PC	New Construction - PCC	-	6.00	True	6" P-501
03-02-2020	BA-AG	Base Course - Aggregate	-	6.00	False	6" P-209
03-01-2020	SG-CO	Subgrade - Compacted	-	12.00	False	12" Imported Suitable Fill Material

Branch - Section ID: TH01WA - 001

LCD: 3/10/2003
Use: T-HANGAR
Rank: P
Surface: PCC

Length (ft): 995.00
Width (ft): 25.00
True Area (sf): 33,422.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
03-10-2003	NC-PC	New Construction - PCC	-	6.00	True	6" Iowa DOT PCC
03-09-2003	SB-AG	Subbase - Aggregate	-	6.00	False	6" P-154 Aggregate
03-08-2003	SG-CO	Subgrade - Compacted	-	12.00	False	12" P-152

Branch - Section ID: TH01WA - 002

LCD: 1/1/1994
Use: T-HANGAR
Rank: P
Surface: PCC

Length (ft): 150.00
Width (ft): 30.00
True Area (sf): 6,606.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
01-01-1994	NC-IN	New Construction - Initial	-	-	True	UNKNOWN, PRE 1994

Branch - Section ID: TH01WA - 003

LCD: 1/1/1994
Use: T-HANGAR
Rank: P
Surface: PCC

Length (ft): 278.00
Width (ft): 40.00
True Area (sf): 11,948.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
01-01-1994	NC-IN	New Construction - Initial	-	-	True	UNKNOWN, PRE 1994

APPENDIX E

LOCALIZED PREVENTIVE MAINTENANCE POLICIES AND UNIT COST TABLES

Table E-1. Localized preventive maintenance policy, asphalt-surfaced pavements.

Distress Type	Severity Level	Maintenance Action
Alligator Cracking	Low	Monitor
Alligator Cracking	Medium	Asphalt Patch
Alligator Cracking	High	Asphalt Patch
Bleeding	N/A	Monitor
Block Cracking	Low	Monitor
Block Cracking	Medium	Crack Seal—Asphalt
Block Cracking	High	Crack Seal—Asphalt
Corrugation	Low	Monitor
Corrugation	Medium	Asphalt Patch
Corrugation	High	Asphalt Patch
Depression	Low	Monitor
Depression	Medium	Monitor
Depression	High	Asphalt Patch
Jet-Blast Erosion	N/A	Asphalt Patch
Joint Reflection Cracking	Low	Monitor
Joint Reflection Cracking	Medium	Crack Seal—Asphalt
Joint Reflection Cracking	High	Crack Seal—Asphalt
L&T Cracking	Low	Monitor
L&T Cracking	Medium	Crack Seal—Asphalt
L&T Cracking	High	Crack Seal—Asphalt
Oil Spillage	N/A	Asphalt Patch
Patching	Low	Monitor
Patching	Medium	Asphalt Patch
Patching	High	Asphalt Patch
Polished Aggregate	N/A	Monitor
Raveling	Low	Monitor
Raveling	Medium	Asphalt Patch
Raveling	High	Asphalt Patch
Rutting	Low	Monitor
Rutting	Medium	Monitor
Rutting	High	Asphalt Patch
Shoving	Low	Monitor
Shoving	Medium	Asphalt Patch
Shoving	High	Asphalt Patch
Slippage Cracking	N/A	Asphalt Patch
Swelling	Low	Monitor
Swelling	Medium	Monitor
Swelling	High	Asphalt Patch
Weathering	Low	Monitor
Weathering	Medium	Monitor
Weathering	High	Asphalt Patch

Table E-2. Localized preventive maintenance policy, concrete pavements.

Distress Type	Severity Level	Maintenance Action
ASR	Low	Monitor
ASR	Medium	Slab Replacement
ASR	High	Slab Replacement
Blowup	Low	Slab Replacement
Blowup	Medium	Slab Replacement
Blowup	High	Slab Replacement
Corner Break	Low	Crack Seal—Concrete
Corner Break	Medium	Full-Depth Concrete Patch
Corner Break	High	Full-Depth Concrete Patch
Durability Cracking	Low	Monitor
Durability Cracking	Medium	Full-Depth Concrete Patch
Durability Cracking	High	Slab Replacement
Faulting	Low	Monitor
Faulting	Medium	Grinding
Faulting	High	Slab Replacement
Joint Seal Damage	Low	Monitor
Joint Seal Damage	Medium	Joint Seal
Joint Seal Damage	High	Joint Seal
LTD Cracking	Low	Monitor
LTD Cracking	Medium	Crack Seal—Concrete
LTD Cracking	High	Slab Replacement
Patching (Small and Large)	Low	Monitor
Patching (Small and Large)	Medium	Full-Depth Concrete Patch
Patching (Small and Large)	High	Full-Depth Concrete Patch
Popouts	N/A	Monitor
Pumping	N/A	Monitor
Scaling	Low	Monitor
Scaling	Medium	Partial-Depth Concrete Patch
Scaling	High	Slab Replacement
Shattered Slab	Low	Crack Seal—Concrete
Shattered Slab	Medium	Slab Replacement
Shattered Slab	High	Slab Replacement
Shrinkage Cracking	N/A	Monitor
Spalling (Joint and Corner)	Low	Monitor
Spalling (Joint and Corner)	Medium	Partial-Depth Concrete Patch
Spalling (Joint and Corner)	High	Partial-Depth Concrete Patch

Table E-3. 2026 unit costs for localized preventive maintenance actions.

Maintenance Action	Unit Cost
Asphalt Patch—Asphalt-Surfaced Pavement	\$16.27/sf
Crack Sealing—Asphalt-Surfaced Pavement	\$2.78/lf
Partial-Depth Concrete Patch—Concrete Pavement	\$41.68/sf
Full-Depth Concrete Patch—Concrete Pavement	\$18.61/sf
Crack Sealing—Concrete Pavement	\$3.35/lf
Joint Sealing—Concrete Pavement	\$3.35/lf
Grinding—Concrete Pavement	\$0.40/sf
Slab Replacement—Concrete Pavement	\$18.61/sf

Table note: The unit cost estimates are based on broad statewide numbers and should be adjusted to reflect local costs.

Table E-4. 2026 unit costs (per square foot) based on pavement type and PCI ranges.

Pavement Type	PCI Range 0–40	PCI Range 40–50	PCI Range 50–60	PCI Range 60–70	PCI Range 70–80	PCI Range 80–90	PCI Range 90–100
Asphalt-Surfaced	\$11.55	\$5.46	\$5.46	\$5.46	\$0.00	\$0.00	\$0.00
Concrete	\$19.30	\$9.13	\$9.13	\$9.13	\$0.00	\$0.00	\$0.00

Table notes:

1. The unit cost estimates are based on broad statewide numbers and should be adjusted to reflect local costs.
2. Pavement type: asphalt-surfaced = AC (asphalt cement concrete), AAC (asphalt overlay on AC), or APC (asphalt overlay on concrete).

APPENDIX F

YEAR 2026 LOCALIZED PREVENTIVE MAINTENANCE DETAILS

Table F-1. Year 2026 localized preventive maintenance details.

Branch	Section	Distress Type	Severity	Distress Quantity	Distress Unit	Maintenance Action	Unit Cost	2026 Estimated Cost
A01WA	01	Corner Spalling	Medium	1	Slabs	Patching - PCC Partial Depth	\$41.68	\$144
A01WA	01	Corner Spalling	High	1	Slabs	Patching - PCC Partial Depth	\$41.68	\$144
A01WA	01	Joint Seal Damage	Medium	77	Slabs	Joint Seal (Localized)	\$3.35	\$6,265
A01WA	01	Joint Spalling	Medium	5	Slabs	Patching - PCC Partial Depth	\$41.68	\$1,382
A01WA	01	Joint Spalling	High	1	Slabs	Patching - PCC Partial Depth	\$41.68	\$432
A01WA	02	Joint Seal Damage	Medium	110	Slabs	Joint Seal (Localized)	\$3.35	\$6,456
A01WA	02	Joint Spalling	Medium	1	Slabs	Patching - PCC Partial Depth	\$41.68	\$375
A01WA	02	Large Patch	Medium	1	Slabs	Patching - PCC Full Depth	\$18.61	\$1,275
A01WA	03	Corner Break	Low	1	Slabs	Crack Sealing - PCC	\$3.35	\$27
A01WA	03	Joint Seal Damage	High	12	Slabs	Joint Seal (Localized)	\$3.35	\$1,028
A01WA	03	Small Patch	High	1	Slabs	Patching - PCC Full Depth	\$18.61	\$50
A01WA	04	Corner Spalling	Medium	1	Slabs	Patching - PCC Partial Depth	\$41.68	\$112
A01WA	04	Joint Seal Damage	High	21	Slabs	Joint Seal (Localized)	\$3.35	\$1,159
A01WA	07	Joint Seal Damage	Medium	495	Slabs	Joint Seal (Localized)	\$3.35	\$29,434
A01WA	08	Corner Spalling	Medium	1	Slabs	Patching - PCC Partial Depth	\$41.68	\$112
A01WA	08	Joint Seal Damage	Medium	417	Slabs	Joint Seal (Localized)	\$3.35	\$24,832
A01WA	08	Joint Spalling	Medium	11	Slabs	Patching - PCC Partial Depth	\$41.68	\$2,875
A01WA	09	Corner Break	Low	2	Slabs	Crack Sealing - PCC	\$3.35	\$55
A01WA	09	Joint Seal Damage	Medium	49	Slabs	Joint Seal (Localized)	\$3.35	\$2,597
A01WA	09	LTD Cracking	Medium	2	Slabs	Crack Sealing - PCC	\$3.35	\$62
A01WA	09	Shattered Slab	Medium	1	Slabs	Slab Replacement - PCC	\$18.61	\$1,591
R13WA	01	Corner Spalling	High	9	Slabs	Patching - PCC Partial Depth	\$41.68	\$1,030

Table F-1. Year 2026 localized preventive maintenance details (continued).

Branch	Section	Distress Type	Severity	Distress Quantity	Distress Unit	Maintenance Action	Unit Cost	2026 Estimated Cost
R13WA	01	Joint Seal Damage	Medium	1,763	Slabs	Joint Seal (Localized)	\$3.35	\$108,067
R13WA	01	Joint Seal Damage	High	220	Slabs	Joint Seal (Localized)	\$3.35	\$13,508
R18WA	01	ASR	Medium	9	Slabs	Slab Replacement - PCC	\$18.61	\$26,151
R18WA	01	Corner Spalling	Medium	10	Slabs	Patching - PCC Partial Depth	\$41.68	\$1,097
R18WA	01	Joint Seal Damage	Medium	1,710	Slabs	Joint Seal (Localized)	\$3.35	\$132,525
R18WA	01	Joint Seal Damage	High	211	Slabs	Joint Seal (Localized)	\$3.35	\$16,333
R18WA	01	Joint Spalling	Medium	10	Slabs	Patching - PCC Partial Depth	\$41.68	\$2,633
R18WA	01	Joint Spalling	High	2	Slabs	Patching - PCC Partial Depth	\$41.68	\$673
T03WA	01	Joint Seal Damage	Medium	125	Slabs	Joint Seal (Localized)	\$3.35	\$6,746
T03WA	01	Joint Seal Damage	High	81	Slabs	Joint Seal (Localized)	\$3.35	\$4,365
T04WA	01	Joint Seal Damage	Medium	161	Slabs	Joint Seal (Localized)	\$3.35	\$8,696
T04WA	01	Joint Seal Damage	High	40	Slabs	Joint Seal (Localized)	\$3.35	\$2,147
TA1WA	01	Corner Break	Low	2	Slabs	Crack Sealing - PCC	\$3.35	\$44
TA1WA	01	Joint Seal Damage	Medium	147	Slabs	Joint Seal (Localized)	\$3.35	\$12,294
TA1WA	01	LTD Cracking	Medium	2	Slabs	Crack Sealing - PCC	\$3.35	\$80
TA1WA	01	Small Patch	Medium	2	Slabs	Patching - PCC Full Depth	\$18.61	\$80
TBWA	01	Corner Spalling	Medium	2	Slabs	Patching - PCC Partial Depth	\$41.68	\$188
TBWA	01	Joint Seal Damage	Medium	71	Slabs	Joint Seal (Localized)	\$3.35	\$5,071
TBWA	01	Joint Spalling	Medium	3	Slabs	Patching - PCC Partial Depth	\$41.68	\$904
TBWA	01	Joint Spalling	High	2	Slabs	Patching - PCC Partial Depth	\$41.68	\$565
TBWA	02	Joint Seal Damage	Medium	85	Slabs	Joint Seal (Localized)	\$3.35	\$4,487
TBWA	02	Joint Spalling	Medium	1	Slabs	Patching - PCC Partial Depth	\$41.68	\$381
TBWA	03	Corner Break	Low	1	Slabs	Crack Sealing - PCC	\$3.35	\$27

Table F-1. Year 2026 localized preventive maintenance details (continued).

Branch	Section	Distress Type	Severity	Distress Quantity	Distress Unit	Maintenance Action	Unit Cost	2026 Estimated Cost
TH01WA	01	Joint Seal Damage	Medium	413	Slabs	Joint Seal (Localized)	\$3.35	\$20,290
TH01WA	02	Joint Seal Damage	Medium	16	Slabs	Joint Seal (Localized)	\$3.35	\$1,120
TH01WA	02	Joint Seal Damage	High	15	Slabs	Joint Seal (Localized)	\$3.35	\$1,050
TH01WA	02	Joint Spalling	High	3	Slabs	Patching - PCC Partial Depth	\$41.68	\$1,009
TH01WA	03	Joint Seal Damage	High	119	Slabs	Joint Seal (Localized)	\$3.35	\$6,861
TH01WA	03	LTD Cracking	Medium	22	Slabs	Crack Sealing - PCC	\$3.35	\$747

Table notes:

1. See Figure 3 for the location of the branch and section.
2. Distress types are defined by ASTM D5340. L&T cracking = longitudinal and transverse cracking; LTD cracking = longitudinal, transverse, and diagonal cracking; ASR = alkali-silica reaction.
3. The costs provided are of a general nature for the entire State and may require adjustments to reflect specific conditions at Washington Municipal Airport.



PREPARED FOR

Iowa Department of Transportation
Modal Transportation Bureau
800 Lincoln Way
Ames, Iowa 50010
515-239-1691
<https://iowadot.gov/modes-travel/aviation>

AUGUST 2026