


BENCH MARK :




* THIS DIMENSION MAY VARY. TILTING OF THE PAVEMENT SUPPORT SECTION DURING CONSTRUCTION MAY BE NECESSARY TO ACCOMMODATE PROPER SETTING OF THE STRIP SEAL EXPANSION DEVICE OPENING.




REAR ELEVATION

DETAIL "C"



SECTION THROUGH ABUTMENT
EXPANSION DEVICE NOT SHOWN




ABUTMENT STEP DIAGRAM
REAR ELEVATION

POINT	ABUTMENT	ABUTMENT
ELEV. A		
BOTT. BACKWALL ELEV.		
BOTT. FTG. ELEV.		


STEP	ABUTMENT	ABUTMENT
a		

NOTE :
PLACE 5m1 AND 5n1 BARS
UNDER EACH BEAM.




PART PLAN VIEW

PART SECTION THROUGH BACKWALL



SECTION E-E



PILING LAYOUT

NOTE :
DIMENSIONS SHOWN ON PILING LAYOUT ARE AT BOTTOM OF FOOTING. BATTER PILES IN THE DIRECTION SHOWN.
---- - HPI0x42 STEEL BEARING PILING REQUIRED AT EACH ABUTMENT.


NOTE: BARRIER RAIL NOT SHOWN IN DETAILS.

ABUTMENT FOOTING DETAILS


IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____

ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 2092-BTCD - THIS SHEET ISSUED 07-08.

BENCH MARK :




* THIS DIMENSION MAY VARY. TILTING OF THE PAVEMENT SUPPORT SECTION DURING CONSTRUCTION MAY BE NECESSARY TO ACCOMMODATE PROPER SETTING OF THE STRIP SEAL EXPANSION DEVICE OPENING.




REAR ELEVATION

DETAIL "C"



SECTION THROUGH ABUTMENT
EXPANSION DEVICE NOT SHOWN




ABUTMENT STEP DIAGRAM
REAR ELEVATION

POINT	ABUTMENT	ABUTMENT
ELEV. A		
BOTT. BACKWALL ELEV.		
BOTT. FTG. ELEV.		


STEP	ABUTMENT	ABUTMENT
a		

NOTE :
PLACE 5m1 AND 5n1 BARS UNDER EACH BEAM. FLARE 5m1 BARS AND FIELD CUT 5n1 BARS TO FIT STEPS AT THE EXTERIOR BEAMS.




PART SECTION THROUGH BACKWALL

PART PLAN VIEW



SECTION E-E

NOTE :
SEE DESIGN SHEET FOR VIEWS A-A & B-B.



PILING LAYOUT

NOTE :
DIMENSIONS SHOWN ON PILING LAYOUT ARE AT BOTTOM OF FOOTING. BATTER PILES IN THE DIRECTION SHOWN. --- - HPI0x42 STEEL BEARING PILING REQUIRED AT EACH ABUTMENT.


NOTE: BARRIER RAIL NOT SHOWN IN DETAILS.

ABUTMENT FOOTING DETAILS


IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____

ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 2094-BTCD - THIS SHEET ISSUED 07-08.

BENCH MARK :




* THIS DIMENSION MAY VARY. TILTING OF THE PAVEMENT SUPPORT SECTION DURING CONSTRUCTION MAY BE NECESSARY TO ACCOMMODATE PROPER SETTING OF THE STRIP SEAL EXPANSION DEVICE OPENING.




REAR ELEVATION

DETAIL "C"



SECTION THROUGH ABUTMENT
EXPANSION DEVICE NOT SHOWN




ABUTMENT STEP DIAGRAM
REAR ELEVATION

POINT	ABUTMENT	ABUTMENT
ELEV. A		
BOTT. BACKWALL ELEV.		
BOTT. FTG. ELEV.		

STEP	ABUTMENT	ABUTMENT
a		


NOTE :
PLACE 5m1 AND 5n1 BARS UNDER EACH BEAM. FLARE 5m1 BARS AND FIELD CUT 5n1 BARS TO FIT STEPS AT THE EXTERIOR BEAMS.




PART PLAN VIEW

NOTE :
SEE DESIGN SHEET FOR VIEWS A-A & B-B.

PART SECTION THROUGH BACKWALL



SECTION E-E



PILING LAYOUT

NOTE :
DIMENSIONS SHOWN ON PILING LAYOUT ARE AT BOTTOM OF FOOTING. BATTER PILES IN THE DIRECTION SHOWN.
---- - HP10x42 STEEL BEARING PILING REQUIRED AT EACH ABUTMENT.


NOTE: BARRIER RAIL NOT SHOWN IN DETAILS.

ABUTMENT FOOTING DETAILS


IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____

REVISED 10-10 - ADDED 2 ADDITIONAL 5g1 BARS IN LOWER BACKWALL. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 2094-BTE - THIS SHEET ISSUED 07-08.

BENCH MARK :




* THIS DIMENSION MAY VARY. TILTING OF THE PAVEMENT SUPPORT SECTION DURING CONSTRUCTION MAY BE NECESSARY TO ACCOMMODATE PROPER SETTING OF THE STRIP SEAL EXPANSION DEVICE OPENING.




REAR ELEVATION

DETAIL "C"



SECTION THROUGH ABUTMENT
EXPANSION DEVICE NOT SHOWN



ABUTMENT STEP DIAGRAM
REAR ELEVATION


POINT	ABUTMENT	ABUTMENT
ELEV. A		
BOTT. BACKWALL ELEV.		
BOTT. FTG. ELEV.		

STEP	ABUTMENT	ABUTMENT
a		

NOTE :
PLACE 5m1 AND 5n1 BARS UNDER EACH BEAM. FLARE 5m1 BARS AND FIELD CUT 5n1 BARS TO FIT STEPS AT THE EXTERIOR BEAMS.

NOTE :
DIMENSIONS SHOWN ON PILING LAYOUT ARE AT BOTTOM OF FOOTING. BATTER PILES IN THE DIRECTION SHOWN. --- - HPI0x42 STEEL BEARING PILING REQUIRED AT EACH ABUTMENT.


NOTE: BARRIER RAIL NOT SHOWN IN DETAILS.



PART PLAN VIEW

SECTION E-E

PART SECTION THROUGH BACKWALL



PILING LAYOUT

ABUTMENT FOOTING DETAILS


IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____

ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 2095-BTCD - THIS SHEET ISSUED 07-08.

BENCH MARK :




* THIS DIMENSION MAY VARY. TILTING OF THE PAVEMENT SUPPORT SECTION DURING CONSTRUCTION MAY BE NECESSARY TO ACCOMMODATE PROPER SETTING OF THE STRIP SEAL EXPANSION DEVICE OPENING.




REAR ELEVATION

NOTE :
PLACE 5m1 AND 5n1 BARS UNDER EACH BEAM. FLARE 5m1 BARS AND FIELD CUT 5n1 BARS TO FIT STEPS AT THE EXTERIOR BEAMS.

DETAIL "C"




SECTION THROUGH ABUTMENT
EXPANSION DEVICE NOT SHOWN



ABUTMENT STEP DIAGRAM
REAR ELEVATION

POINT	ABUTMENT	ABUTMENT
ELEV. A		
BOTT. BACKWALL ELEV.		
BOTT. FTG. ELEV.		

STEP	ABUTMENT	ABUTMENT
a		




PART PLAN VIEW

SECTION E-E

PART SECTION THROUGH BACKWALL

NOTE :
SEE DESIGN SHEET FOR VIEWS A-A & B-B.



PILING LAYOUT

NOTE :
DIMENSIONS SHOWN ON PILING LAYOUT ARE AT BOTTOM OF FOOTING. BATTER PILES IN THE DIRECTION SHOWN. --- HPI0x42 STEEL BEARING PILING REQUIRED AT EACH ABUTMENT.


NOTE: BARRIER RAIL NOT SHOWN IN DETAILS.

ABUTMENT FOOTING DETAILS


IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____

ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 2097-BTCD - THIS SHEET ISSUED 07-08.

BENCH MARK :




* THIS DIMENSION MAY VARY. TILTING OF THE PAVEMENT SUPPORT SECTION DURING CONSTRUCTION MAY BE NECESSARY TO ACCOMMODATE PROPER SETTING OF THE STRIP SEAL EXPANSION DEVICE OPENING.




REAR ELEVATION

DETAIL "C"



SECTION THROUGH ABUTMENT
EXPANSION DEVICE NOT SHOWN




ABUTMENT STEP DIAGRAM
REAR ELEVATION

POINT	ABUTMENT	ABUTMENT
ELEV. A		
BOTT. BACKWALL ELEV.		
BOTT. FTG. ELEV.		

STEP	ABUTMENT	ABUTMENT
a		

NOTE :
PLACE 5m1 AND 5n1 BARS UNDER EACH BEAM. FLARE 5m1 BARS AND FIELD CUT 5n1 BARS TO FIT STEPS AT THE EXTERIOR BEAMS.



PART PLAN VIEW

PART SECTION THROUGH BACKWALL

SECTION E-E

- SPACES @ 0'-6" = 5g2 DOWELS (ONE AT EACH 5g1).
- SPACES @ 1'-0" = 6d1 BARS
- SPACES @ 1'-0" = 5d2 & 4d6 BARS
- SPACES @ 1'-0" = 5d3 & 5d4 BARS
- SPACES @ 2'-0" = 5d5 BARS

NOTE :
SEE DESIGN SHEET ??
FOR VIEWS A-A & B-B.

NOTE :
DIMENSIONS SHOWN ON PILING LAYOUT ARE AT BOTTOM OF FOOTING. BATTER PILES IN THE DIRECTION SHOWN.
---- - HPI0x42 STEEL BEARING PILING REQUIRED AT EACH ABUTMENT.

NOTE: BARRIER RAIL NOT SHOWN IN DETAILS.


PILING LAYOUT

ABUTMENT FOOTING DETAILS


IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
DESIGN SHEET NO. ___ OF ___ FILE NO. ___ DESIGN NO. ___

ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 2098-BTCD - THIS SHEET ISSUED 07-08.

BENCH MARK :




* THIS DIMENSION MAY VARY. TILTING OF THE PAVEMENT SUPPORT SECTION DURING CONSTRUCTION MAY BE NECESSARY TO ACCOMMODATE PROPER SETTING OF THE STRIP SEAL EXPANSION DEVICE OPENING.




REAR ELEVATION

NOTE :
PLACE 5m1 AND 5n1 BARS UNDER EACH BEAM. FLARE 5m1 BARS AND FIELD CUT 5n1 BARS TO FIT STEPS AT THE EXTERIOR BEAMS.

DETAIL "C"




SECTION THROUGH ABUTMENT
EXPANSION DEVICE NOT SHOWN



ABUTMENT STEP DIAGRAM
REAR ELEVATION

POINT	ABUTMENT	ABUTMENT
ELEV. A		
BOTT. BACKWALL ELEV.		
BOTT. FTG. ELEV.		

STEP	ABUTMENT	ABUTMENT
a		




PART PLAN VIEW

PART SECTION THROUGH BACKWALL

SECTION E-E

NOTE :
SEE DESIGN SHEET ??
FOR VIEWS A-A & B-B.


- SPACES @ 0'-6 = 5g2 DOWELS (ONE AT EACH 5g1).
- SPACES @ 1'-0 = 6d1 BARS
- SPACES @ 1'-0 = 5d2 & 4d6 BARS
- SPACES @ 1'-0 = 5d3 & 5d4 BARS
- SPACES @ 2'-0 = 5d5 BARS



PILING LAYOUT

NOTE :
DIMENSIONS SHOWN ON PILING LAYOUT ARE AT BOTTOM OF FOOTING. BATTER PILES IN THE DIRECTION SHOWN.
---- - HPI0x42 STEEL BEARING PILING REQUIRED AT EACH ABUTMENT.

NOTE: BARRIER RAIL NOT SHOWN IN DETAILS.






ABUTMENT FOOTING DETAILS

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
DESIGN SHEET NO. ___ OF ___ FILE NO. ___ DESIGN NO. ___

REVISED 10-10 - ADDED 2 ADDITIONAL 5g1 BARS IN LOWER BACKWALL. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 2098-BTE - THIS SHEET ISSUED 07-08.

CORRECTION 04-14 - CHANGED NOTE ABOUT BARRIER RAIL BARS 5c3 & 5c14 TO BARRIER RAIL QTYS. INSTEAD OF BRIDGE DECK QTYS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 2099-BTCD - THIS SHEET ISSUED 07-08.





SECTION C-C
 NOTE: BARRIER RAIL NOT SHOWN IN SECTION C-C.
 Δ NOTE: SEE DESIGN SHEET ---- IN THESE PLANS FOR DETAILS OF BARRIER RAIL WING EXTENSIONS. REINFORCING BARS 5c3 AND 5c14 ARE INCLUDED IN THE BARRIER RAIL QUANTITIES.

LOCATION	ELEV. G	ELEV. H	ELEV. I

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. ____ OF ____ FILE NO. ____ DESIGN NO. ____



CORRECTION 04-14 - CHANGED NOTE ABOUT BARRIER RAIL BARS 5c3 & 5c14 TO BARRIER RAIL QTYS. INSTEAD OF BRIDGE DECK QTYS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 2099-BTE - THIS SHEET ISSUED 07-08.




LOCATION	ELEV. G	ELEV. H	ELEV. I

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____

CORRECTION 04-14 - CHANGED NOTE ABOUT BARRIER RAIL BARS 5c3 & 5c14 TO BARRIER RAIL QTYS. INSTEAD OF BRIDGE DECK QTYS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 2100-BTCD - THIS SHEET ISSUED 07-08.




PART SECTION D-D



SECTION C-C

NOTE: BARRIER RAIL NOT SHOWN IN SECTION C-C.

Δ NOTE: SEE DESIGN SHEET ---- IN THESE PLANS FOR DETAILS OF BARRIER RAIL WING EXTENSIONS. REINFORCING BARS 5c3 AND 5c14 ARE INCLUDED IN THE BARRIER RAIL QUANTITIES.







PART SECTION F-F

TABLE OF WINGWALL ELEVATIONS			
LOCATION	ELEV. G	ELEV. H	ELEV. I

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____

CORRECTION 04-14 - CHANGED NOTE ABOUT BARRIER RAIL BARS 5c3 & 5c14 TO BARRIER RAIL QTYS. INSTEAD OF BRIDGE DECK QTYS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 2100-BTE - THIS SHEET ISSUED 07-08.



LOCATION	ELEV. G	ELEV. H	ELEV. I

SECTION C-C
 NOTE: BARRIER RAIL NOT SHOWN IN SECTION C-C.
 Δ NOTE: SEE DESIGN SHEET ---- IN THESE PLANS FOR DETAILS OF BARRIER RAIL WING EXTENSIONS. REINFORCING BARS 5c3 AND 5c14 ARE INCLUDED IN THE BARRIER RAIL QUANTITIES.

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____

CORRECTION 04-14 - CHANGED NOTE ABOUT BARRIER RAIL BARS 5c3 & 5c14 TO BARRIER RAIL QTYS. INSTEAD OF BRIDGE DECK QTYS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 2101-BTCD - THIS SHEET ISSUED 07-08.








TABLE OF WINGWALL ELEVATIONS			
LOCATION	ELEV. G	ELEV. H	ELEV. I


SECTION C-C
 NOTE: BARRIER RAIL NOT SHOWN IN SECTION C-C.
 Δ NOTE: SEE DESIGN SHEET ---- IN THESE PLANS FOR DETAILS OF BARRIER RAIL WING EXTENSIONS. REINFORCING BARS 5c3 AND 5c14 ARE INCLUDED IN THE BARRIER RAIL QUANTITIES.

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____

CORRECTION 04-14 - CHANGED NOTE ABOUT BARRIER RAIL BARS 5c3 & 5c14 TO BARRIER RAIL QTYS. INSTEAD OF BRIDGE DECK QTYS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 2101-BTE - THIS SHEET ISSUED 07-08.




NOTE: FOR LOCATION OF VIEWS A-A & B-B SEE DESIGN SHEET ----
 * SEE PART PLAN & LONGIT. SECTION SHEET FOR PVC PIPE LOCATION.



SECTION C-C

NOTE: BARRIER RAIL NOT SHOWN IN SECTION C-C.
 Δ NOTE: SEE DESIGN SHEET ---- IN THESE PLANS FOR DETAILS OF BARRIER RAIL WING EXTENSIONS. REINFORCING BARS 5c3 AND 5c14 ARE INCLUDED IN THE BARRIER RAIL QUANTITIES.

POSITION THIS 5e2 BAR 2" CLEAR FROM FACE OF CONCRETE TO ACCOMMODATE SKEW



PART SECTION F-F

TABLE OF WINGWALL ELEVATIONS			
LOCATION	ELEV. G	ELEV. H	ELEV. I

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. ____ OF ____ FILE NO. ____ DESIGN NO. ____

CORRECTION 04-14 - CHANGED NOTE ABOUT BARRIER RAIL BARS 5c3 & 5c14 TO BARRIER RAIL QTYS. INSTEAD OF BRIDGE DECK QTYS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 2102-BTCD - THIS SHEET ISSUED 07-08.







TABLE OF WINGWALL ELEVATIONS			
LOCATION	ELEV. G	ELEV. H	ELEV. I





NOTE: BARRIER RAIL NOT SHOWN IN SECTION C-C.


Δ NOTE: SEE DESIGN SHEET ---- IN THESE PLANS FOR DETAILS OF BARRIER RAIL WING EXTENSIONS. REINFORCING BARS 5c3 AND 5c14 ARE INCLUDED IN THE BARRIER RAIL QUANTITIES.

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____

CORRECTION 04-14 - CHANGED NOTE ABOUT BARRIER RAIL BARS 5c3 & 5c14 TO BARRIER RAIL QTYS. INSTEAD OF BRIDGE DECK QTYS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 2102-BTE - THIS SHEET ISSUED 07-08.




SECTION C-C
 NOTE: BARRIER RAIL NOT SHOWN IN SECTION C-C.
 Δ NOTE: SEE DESIGN SHEET ---- IN THESE PLANS FOR DETAILS OF BARRIER RAIL WING EXTENSIONS. REINFORCING BARS 5c3 AND 5c14 ARE INCLUDED IN THE BARRIER RAIL QUANTITIES.



LOCATION	ELEV. G	ELEV. H	ELEV. I

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. ____ OF ____ FILE NO. ____ DESIGN NO. ____

CORRECTION 04-14 - CHANGED NOTE ABOUT BARRIER RAIL BARS 5c3 & 5c14 TO BARRIER RAIL QTYS. INSTEAD OF BRIDGE DECK QTYS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 2103-BTCD - THIS SHEET ISSUED 07-08.




VIEW A-A

VIEW B-B

PART SECTION D-D


NOTE: FOR LOCATION OF VIEWS A-A & B-B SEE DESIGN SHEET ----.
 * SEE PART PLAN & LONGIT. SECTION SHEET FOR PVC PIPE LOCATION.



SECTION C-C

NOTE: BARRIER RAIL NOT SHOWN IN SECTION C-C.

Δ NOTE: SEE DESIGN SHEET ---- IN THESE PLANS FOR DETAILS OF BARRIER RAIL WING EXTENSIONS. REINFORCING BARS 5c3 AND 5c14 ARE INCLUDED IN THE BARRIER RAIL QUANTITIES.




PART SECTION F-F


TABLE OF WINGWALL ELEVATIONS			
LOCATION	ELEV. G	ELEV. H	ELEV. I

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. ____ OF ____ FILE NO. ____ DESIGN NO. ____


CORRECTION 04-14 - CHANGED NOTE ABOUT BARRIER RAIL BARS 5c3 & 5c14 TO BARRIER RAIL QTYS. INSTEAD OF BRIDGE DECK QTYS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 2103-BTE - THIS SHEET ISSUED 07-08.



NOTE: FOR LOCATION OF VIEWS A-A & B-B SEE DESIGN SHEET ----
 * SEE PART PLAN & LONGIT. SECTION SHEET FOR PVC PIPE LOCATION.



SECTION C-C
 NOTE: BARRIER RAIL NOT SHOWN IN SECTION C-C.
 Δ NOTE: SEE DESIGN SHEET ---- IN THESE PLANS FOR DETAILS OF BARRIER RAIL WING EXTENSIONS. REINFORCING BARS 5c3 AND 5c14 ARE INCLUDED IN THE BARRIER RAIL QUANTITIES.




POSITION THIS 5e2 BAR 2" CLEAR FROM FACE OF CONCRETE TO ACCOMMODATE SKEW

TABLE OF WINGWALL ELEVATIONS			
LOCATION	ELEV. G	ELEV. H	ELEV. I

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____

DESIGN TEAM	"BTE" BEAM STUB ABUT. DETAILS - (L.A.) 0°01' - 7°30' SKEW	STANDARD SHEET 2103-BTE	COUNTY	PROJECT NUMBER
6/26/2015 1:27:19 PM bkloss	W:\Highway\Bridges\MethodsSection\CADD Concept Drafts\EnglishBTStubBridges.dgn	2103-BTE 11x17.pdf.pltcfgr		SHEET NUMBER


CORRECTION 04-14 - CHANGED NOTE ABOUT BARRIER RAIL BARS 5c3 & 5c14 TO BARRIER RAIL QTYS. INSTEAD OF BRIDGE DECK QTYS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 2104-BTCD - THIS SHEET ISSUED 07-08.



FIELD BEND 5h4 BAR AS NECESSARY TO AVOID PILE IN ABUTMENT WING.

NOTE: FOR LOCATION OF VIEWS A-A & B-B SEE DESIGN SHEET ----.

* SEE PART PLAN & LONGIT. SECTION SHEET FOR PVC PIPE LOCATION.




SECTION C-C

NOTE: BARRIER RAIL NOT SHOWN IN SECTION C-C.

Δ NOTE: SEE DESIGN SHEET ---- IN THESE PLANS FOR DETAILS OF BARRIER RAIL WING EXTENSIONS. REINFORCING BARS 5c3 AND 5c14 ARE INCLUDED IN THE BARRIER RAIL QUANTITIES.

POSITION THIS 5e2 BAR 2" CLEAR FROM FACE OF CONCRETE TO ACCOMMODATE SKEW







PART SECTION F-F

TABLE OF WINGWALL ELEVATIONS			
LOCATION	ELEV. G	ELEV. H	ELEV. I

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
DESIGN SHEET NO. ____ OF ____ FILE NO. ____ DESIGN NO. ____

CORRECTION 04-14 - CHANGED NOTE ABOUT BARRIER RAIL BARS 5c3 & 5c14 TO BARRIER RAIL QTYS. INSTEAD OF BRIDGE DECK QTYS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 2105-BTCD - THIS SHEET ISSUED 07-08.




LOCATION	ELEV. G	ELEV. H	ELEV. I


Δ NOTE: SEE DESIGN SHEET ---- IN THESE PLANS FOR DETAILS OF BARRIER RAIL WING EXTENSIONS. REINFORCING BARS 5c3 AND 5c14 ARE INCLUDED IN THE BARRIER RAIL QUANTITIES.

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. ____ OF ____ FILE NO. ____ DESIGN NO. ____

CORRECTION 04-14 - CHANGED NOTE ABOUT BARRIER RAIL BARS 5c3 & 5c14 TO BARRIER RAIL QTYS. INSTEAD OF BRIDGE DECK QTYS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 2105-BTE - THIS SHEET ISSUED 07-08.



NOTE: FOR LOCATION OF VIEWS A-A & B-B SEE DESIGN SHEET ----
 * SEE PART PLAN & LONGIT. SECTION SHEET FOR PVC PIPE LOCATION.



SECTION C-C
 NOTE: BARRIER RAIL NOT SHOWN IN SECTION C-C.
 Δ NOTE: SEE DESIGN SHEET ---- IN THESE PLANS FOR DETAILS OF BARRIER RAIL WING EXTENSIONS. REINFORCING BARS 5c3 AND 5c14 ARE INCLUDED IN THE BARRIER RAIL QUANTITIES.




TABLE OF WINGWALL ELEVATIONS			
LOCATION	ELEV. G	ELEV. H	ELEV. I


IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. ____ OF ____ FILE NO. ____ DESIGN NO. ____

REVISED 07-14 - CHANGED THE 5m1 HORIZONTAL BAR LENGTH TO 2'-8 TO ACCOMMODATE THE 3'-0 TRANSVERSE DISTANCE OF THE BEAM STEPS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 2107-BTCD - THIS SHEET ISSUED 07-08.

ABUTMENT NOTES:

MINIMUM CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR IS TO BE 2" UNLESS OTHERWISE NOTED OR SHOWN.
 THE MASKWALL IS TO BE POURED BEFORE THE SUPERSTRUCTURE DECK IS POURED.
 CONSTRUCTION JOINT KEYWAYS ARE TO BE FORMED WITH BEVELED 2x6's.
 THE PORTION OF THE BACKWALL CONTAINING THE ABUTMENT ANCHORAGE OF THE EXPANSION DEVICE IS TO BE PLACED AFTER THE BRIDGE DECK IS PLACED.
 CONCRETE SEALER IS TO BE APPLIED TO THE ABUTMENT BRIDGE SEAT IN ACCORDANCE WITH THE CURRENT IOWA D.O.T. STANDARD SPECIFICATIONS.
 THE COST OF PREFORMED EXPANSION JOINT FILLER, AND COST OF FURNISHING AND PLACING CONCRETE SEALER IS TO BE INCLUDED IN THE PRICE BID FOR "STRUCTURAL CONCRETE (BRIDGE)".
 PAVING NOTCH DOWELS SHALL BE STAINLESS STEEL DEFORMED BAR GRADE 60, MEETING THE REQUIREMENTS OF MATERIALS I.M. 452.
 IF NECESSARY TO PREVENT DAMAGE TO THE END OF THE BRIDGE DECK AND BACKWALL FROM CONSTRUCTION EQUIPMENT, AN APPROPRIATE METHOD OF PROTECTION APPROVED BY THE ENGINEER SHALL BE PROVIDED BY THE BRIDGE CONTRACTOR AT NO EXTRA COST TO THE STATE.

BENT BAR DETAILS



REINFORCING BAR LIST - ONE ABUTMENT

BAR	LOCATION	SHAPE	NO.	LENGTH	WEIGHT
8a1	FOOTING LONGITUDINAL		26		
8a2	WING FOOTING		5	VARIES	
8a3	WING FOOTING		5		
8a4	WING FOOTING		5	VARIES	
8a5	WING FOOTING		5		
5b1	FOOTING HOOPS	⊠		17'-0	
5b2	WING FOOTING HOOPS	⊠	6	14'-0	88
6d1	BACKWALL VERTICAL B.F.				
5d2	BACKWALL VERTICAL F.F.				
5d3	PAVING NOTCH			4'-2	
5d4	PAVING NOTCH			3'-5	
4d6	BACKWALL VERTICAL HOOP	⊠		7'-9	
5d8	WING EXTENSION FF HORIZONTAL			8'-8	
5d9	WING EXTENSION BF HORIZONTAL			8'-8	
5e1	MASKWALL VERTICAL		16		
5e2	WING EXTENSION VERTICAL		28		
5f3	MASKWALL HORIZONTAL		10		
5f4	MASKWALL HORIZONTAL		10		
5g1	BACKWALL LONGITUDINAL				
5g2	BACKWALL DOWELS		28	4'-5	129
5g3	PAVING NOTCH LONGITUDINAL				
5h2	WING EXTENSION BF HORIZONTAL		6	4'-11	31
5h4	WING EXTENSION FF HORIZONTAL		6	4'-11	31
5m1	BEAM STEPS TRANSVERSE	⊠		5'-8	
5n1	BEAM STEPS LONGITUDINAL			2'-8	
REINFORCING STEEL - EPOXY COATED - TOTAL (LBS.)					
5d5	PAVING NOTCH DOWELS (STAINLESS STEEL)			3'-6	
STAINLESS STEEL - TOTAL (LBS.)					

CONCRETE PLACEMENT QUANTITIES

LOCATION	ABUT.	ABUT.
FOOTING AND STEPS		
BACKWALL BELOW CONSTR. JOINT		
BACKWALL ABOVE CONSTR. JOINT		
? WING EXTENSION		
? WING EXTENSION		
? WING MASKWALL		
? WING MASKWALL		
TOTAL (C.Y.)		

NOTE:
 CONCRETE AND REINFORCING STEEL QUANTITIES ARE INCLUDED ON THE SUMMARY QUANTITIES SHEET.

ABUTMENT QUANTITIES


IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. ____ OF ____ FILE NO. ____ DESIGN NO. ____

REVISED 07-14 - CHANGED THE 5m1 HORIZONTAL BAR LENGTH TO 2'-8 TO ACCOMMODATE THE 3'-0 TRANSVERSE DISTANCE OF THE BEAM STEPS.
ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 2108-BTCD - THIS SHEET ISSUED 07-08.

ABUTMENT NOTES:

MINIMUM CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR IS TO BE 2" UNLESS OTHERWISE NOTED OR SHOWN.
 THE MASKWALL IS TO BE POURED BEFORE THE SUPERSTRUCTURE DECK IS POURED.
 CONSTRUCTION JOINT KEYWAYS ARE TO BE FORMED WITH BEVELED 2x6's.
 THE PORTION OF THE BACKWALL CONTAINING THE ABUTMENT ANCHORAGE OF THE EXPANSION DEVICE IS TO BE PLACED AFTER THE BRIDGE DECK IS PLACED.
 CONCRETE SEALER IS TO BE APPLIED TO THE ABUTMENT BRIDGE SEAT IN ACCORDANCE WITH THE CURRENT IOWA D.O.T. STANDARD SPECIFICATIONS.
 THE COST OF PREFORMED EXPANSION JOINT FILLER, AND COST OF FURNISHING AND PLACING CONCRETE SEALER IS TO BE INCLUDED IN THE PRICE BID FOR "STRUCTURAL CONCRETE (BRIDGE)".
 PAVING NOTCH DOWELS SHALL BE STAINLESS STEEL DEFORMED BAR GRADE 60, MEETING THE REQUIREMENTS OF MATERIALS I.M. 452.
 IF NECESSARY TO PREVENT DAMAGE TO THE END OF THE BRIDGE DECK AND BACKWALL FROM CONSTRUCTION EQUIPMENT, AN APPROPRIATE METHOD OF PROTECTION APPROVED BY THE ENGINEER SHALL BE PROVIDED BY THE BRIDGE CONTRACTOR AT NO EXTRA COST TO THE STATE.

BENT BAR DETAILS



CONCRETE PLACEMENT QUANTITIES

LOCATION	ABUT.	ABUT.
FOOTING AND STEPS		
BACKWALL BELOW CONSTR. JOINT		
BACKWALL ABOVE CONSTR. JOINT		
? WING EXTENSION		
? WING EXTENSION		
? WING MASKWALL		
? WING MASKWALL		
TOTAL (C.Y.)		

NOTE:
 CONCRETE AND REINFORCING STEEL QUANTITIES ARE INCLUDED ON THE SUMMARY QUANTITIES SHEET.


REINFORCING BAR LIST - ONE ABUTMENT

BAR	LOCATION	SHAPE	NO.	LENGTH	WEIGHT
8a1	FOOTING LONGITUDINAL		26		
8a2	WING FOOTING		5	VARIES	
8a3	WING FOOTING		5		
8a4	WING FOOTING		5	VARIES	
8a5	WING FOOTING		5		
5b1	FOOTING HOOPS	⊠		17'-0	
5b2	WING FOOTING HOOPS	⊠	6	14'-0	88
6d1	BACKWALL VERTICAL B.F.				
5d2	BACKWALL VERTICAL F.F.				
5d3	PAVING NOTCH			4'-2	
5d4	PAVING NOTCH			3'-5	
4d6	BACKWALL VERTICAL HOOP	⊠		7'-9	
5d8	WING EXTENSION FF HORIZONTAL			8'-8	
5d9	WING EXTENSION BF HORIZONTAL			8'-8	
5e1	MASKWALL VERTICAL		16		
5e2	WING EXTENSION VERTICAL		28		
5f3	MASKWALL HORIZONTAL		10		
5f4	MASKWALL HORIZONTAL		10		
5g1	BACKWALL LONGITUDINAL				
5g2	BACKWALL DOWELS		28	4'-5	129
5g3	PAVING NOTCH LONGITUDINAL				
5h2	WING EXTENSION BF HORIZONTAL		6	4'-11	31
5h4	WING EXTENSION FF HORIZONTAL		6	4'-11	31
5m1	BEAM STEPS TRANSVERSE	⊠		5'-8	
5n1	BEAM STEPS LONGITUDINAL			2'-8	
REINFORCING STEEL - EPOXY COATED - TOTAL (LBS.)					
5d5	PAVING NOTCH DOWELS (STAINLESS STEEL)			3'-6	
STAINLESS STEEL - TOTAL (LBS.)					

ABUTMENT QUANTITIES


IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. ___ OF ___ FILE NO. ___ DESIGN NO. ___

CORRECTION 10-10 - CONCRETE SEALER ARTICLE 2403.21 D CHANGED TO ARTICLE 2403.03, P, 3. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 4542-BTCDE - THIS SHEET ISSUED 07-08.



NOTE:
PLUG 3" ϕ PVC PIPE WITH EXPANDING FOAM PRIOR TO BACKFILLING BEHIND ABUTMENTS.


PART LONGITUDINAL SECTION NEAR GUTTER
(FOR DETAILS OF INTERMEDIATE DIAPHRAGM SEE DESIGN SHEET ----).




CONCRETE SEALER SHALL BE APPLIED TO THE ABUTMENT SEAT AND PRESTRESSED BEAM ENDS IN ACCORDANCE WITH ARTICLE 2403.03, P, 3, OF THE STANDARD SPECIFICATIONS. THE SEALING SHALL INCLUDE PORTIONS OF THE PRESTRESSED BEAM END THAT ARE NOT EMBEDDED IN THE ABUTMENT DIAPHRAGMS AS DETAILED ON THIS SHEET.

CONCRETE SEALER LIMITS FOR PRESTRESSED BEAM


DETAIL "A"



PART PLAN VIEW




PART SECTION
(SEE CROSS SECTION THRU SLAB FOR NUMBER OF DIAPHRAGM HOOP BARS BETWEEN BEAMS)



PART PLAN TOP OF FIXED PIER DETAILS


IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
DESIGN SHEET NO. ____ OF ____ FILE NO. ____ DESIGN NO. ____

CORRECTION 10-10 - CONCRETE SEALER ARTICLE 2403.21 D CHANGED TO ARTICLE 2403.03, P, 3. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 4543-BTCDE - THIS SHEET ISSUED 07-08.




NOTE:
PLUG 3" ϕ PVC PIPE WITH EXPANDING FOAM PRIOR TO BACKFILLING BEHIND ABUTMENTS.

PART LONGITUDINAL SECTION NEAR GUTTER
(FOR DETAILS OF INTERMEDIATE DIAPHRAGM SEE DESIGN SHEET ----).




CONCRETE SEALER SHALL BE APPLIED TO THE ABUTMENT SEAT AND PRESTRESSED BEAM ENDS IN ACCORDANCE WITH ARTICLE 2403.03, P, 3, OF THE STANDARD SPECIFICATIONS. THE SEALING SHALL INCLUDE PORTIONS OF THE PRESTRESSED BEAM END THAT ARE NOT EMBEDDED IN THE ABUTMENT DIAPHRAGMS AS DETAILED ON THIS SHEET.

CONCRETE SEALER LIMITS FOR PRESTRESSED BEAM




PART SECTION
(SEE CROSS SECTION THRU SLAB FOR NUMBER OF DIAPHRAGM HOOP BARS BETWEEN BEAMS)



PART PLAN TOP OF FIXED PIER DETAILS


IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
DESIGN SHEET NO. ____ OF ____ FILE NO. ____ DESIGN NO. ____

CORRECTION 10-10 - CONCRETE SEALER ARTICLE 2403.21 D CHANGED TO ARTICLE 2403.03, P. 3, ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 4544-BTCD - THIS SHEET ISSUED 07-08.



NOTE:
PLUG 3" ϕ PVC PIPE WITH EXPANDING FOAM PRIOR TO BACKFILLING BEHIND ABUTMENTS.


PART LONGITUDINAL SECTION NEAR GUTTER
(FOR DETAILS OF INTERMEDIATE DIAPHRAGM SEE DESIGN SHEET ----).




CONCRETE SEALER SHALL BE APPLIED TO THE ABUTMENT SEAT AND PRESTRESSED BEAM ENDS IN ACCORDANCE WITH ARTICLE 2403.03, P. 3, OF THE STANDARD SPECIFICATIONS. THE SEALING SHALL INCLUDE PORTIONS OF THE PRESTRESSED BEAM END THAT ARE NOT EMBEDDED IN THE ABUTMENT DIAPHRAGMS AS DETAILED ON THIS SHEET.

CONCRETE SEALER LIMITS FOR PRESTRESSED BEAM

DETAIL "A"




PART PLAN VIEW



PART SECTION


(SEE CROSS SECTION THRU SLAB FOR NUMBER OF DIAPHRAGM HOOP BARS BETWEEN BEAMS)




PART PLAN TOP OF FIXED PIER DETAILS

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
DESIGN SHEET NO. ____ OF ____ FILE NO. ____ DESIGN NO. ____

CORRECTION 10-10 - CONCRETE SEALER ARTICLE 2403.21 D CHANGED TO ARTICLE 2403.03, P. 3. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 4545-BTCDE - THIS SHEET ISSUED 07-08.




PART LONGITUDINAL SECTION NEAR GUTTER
(FOR DETAILS OF INTERMEDIATE DIAPHRAGM SEE DESIGN SHEET ----).




CONCRETE SEALER SHALL BE APPLIED TO THE ABUTMENT SEAT AND PRESTRESSED BEAM ENDS IN ACCORDANCE WITH ARTICLE 2403.03, P. 3, OF THE STANDARD SPECIFICATIONS. THE SEALING SHALL INCLUDE PORTIONS OF THE PRESTRESSED BEAM END THAT ARE NOT EMBEDDED IN THE ABUTMENT DIAPHRAGMS AS DETAILED ON THIS SHEET.

CONCRETE SEALER LIMITS FOR PRESTRESSED BEAM


DETAIL "A"



PART SECTION
(SEE CROSS SECTION THRU SLAB FOR NUMBER OF DIAPHRAGM HOOP BARS BETWEEN BEAMS)




PART PLAN VIEW



PART PLAN TOP OF FIXED PIER DETAILS


IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
DESIGN SHEET NO. ____ OF ____ FILE NO. ____ DESIGN NO. ____

CORRECTION 10-10 - CONCRETE SEALER ARTICLE 2403.21 D CHANGED TO ARTICLE 2403.03, P. 3. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 4546-BTCDE - THIS SHEET ISSUED 07-08.




NOTE:
PLUG 3" ϕ PVC PIPE WITH EXPANDING FOAM PRIOR TO BACKFILLING BEHIND ABUTMENTS.

PART LONGITUDINAL SECTION NEAR GUTTER
(FOR DETAILS OF INTERMEDIATE DIAPHRAGM SEE DESIGN SHEET ----).




CONCRETE SEALER SHALL BE APPLIED TO THE ABUTMENT SEAT AND PRESTRESSED BEAM ENDS IN ACCORDANCE WITH ARTICLE 2403.03, P. 3, OF THE STANDARD SPECIFICATIONS. THE SEALING SHALL INCLUDE PORTIONS OF THE PRESTRESSED BEAM END THAT ARE NOT EMBEDDED IN THE ABUTMENT DIAPHRAGMS AS DETAILED ON THIS SHEET.


CONCRETE SEALER LIMITS FOR PRESTRESSED BEAM




DETAIL "A"



PART SECTION
(SEE CROSS SECTION THRU SLAB FOR NUMBER OF DIAPHRAGM HOOP BARS BETWEEN BEAMS)




PART PLAN TOP OF FIXED PIER DETAILS




PART PLAN VIEW

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
DESIGN SHEET NO. ____ OF ____ FILE NO. ____ DESIGN NO. ____



NOTE:
 PLUG 3" ϕ PVC PIPE WITH
 EXPANDING FOAM PRIOR
 TO BACKFILLING BEHIND
 ABUTMENTS.


PART LONGITUDINAL SECTION NEAR GUTTER
 (FOR DETAILS OF INTERMEDIATE DIAPHRAGM SEE DESIGN SHEET ----).




CONCRETE SEALER SHALL BE APPLIED TO THE ABUTMENT SEAT AND PRESTRESSED BEAM ENDS IN ACCORDANCE WITH ARTICLE 2403.03, P, 3, OF THE STANDARD SPECIFICATIONS. THE SEALING SHALL INCLUDE PORTIONS OF THE PRESTRESSED BEAM END THAT ARE NOT EMBEDDED IN THE ABUTMENT DIAPHRAGMS AS DETAILED ON THIS SHEET.

CONCRETE SEALER LIMITS FOR PRESTRESSED BEAM


DETAIL "A"



PART SECTION



PART PLAN TOP OF FIXED PIER DETAILS




PART PLAN VIEW

(SEE CROSS SECTION THRU SLAB FOR NUMBER OF DIAPHRAGM HOOP BARS BETWEEN BEAMS)

CORRECTION 10-10 - CONCRETE SEALER ARTICLE 2403.21 D CHANGED TO ARTICLE 2403.03, P, 3. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 4547-BTCDE - THIS SHEET ISSUED 07-08.


IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. ____ OF ____ FILE NO. ____ DESIGN NO. ____

CORRECTION 10-10 - CONCRETE SEALER ARTICLE 2403.03, P. 3, ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 4548-BTCDE - THIS SHEET ISSUED 07-08.




NOTE:
PLUG 3" ϕ PVC PIPE WITH EXPANDING FOAM PRIOR TO BACKFILLING BEHIND ABUTMENTS.

PART LONGITUDINAL SECTION NEAR GUTTER
(FOR DETAILS OF INTERMEDIATE DIAPHRAGM SEE DESIGN SHEET ----).




CONCRETE SEALER SHALL BE APPLIED TO THE ABUTMENT SEAT AND PRESTRESSED BEAM ENDS IN ACCORDANCE WITH ARTICLE 2403.03, P. 3, OF THE STANDARD SPECIFICATIONS. THE SEALING SHALL INCLUDE PORTIONS OF THE PRESTRESSED BEAM END THAT ARE NOT EMBEDDED IN THE ABUTMENT DIAPHRAGMS AS DETAILED ON THIS SHEET.


CONCRETE SEALER LIMITS FOR PRESTRESSED BEAM




DETAIL "A"



PART SECTION
(SEE CROSS SECTION THRU SLAB FOR NUMBER OF DIAPHRAGM HOOP BARS BETWEEN BEAMS)



PART PLAN TOP OF FIXED PIER DETAILS



PART PLAN VIEW


IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
DESIGN SHEET NO. ____ OF ____ FILE NO. ____ DESIGN NO. ____

DESIGN TEAM	PART PLAN & LONGIT. SECTION - "BTC", "BTD" OR "BTE" BEAMS, STUB ABUT., 15°01' - 30° SKEW R.A.	STANDARD SHEET 4548-BTCDE	COUNTY	PROJECT NUMBER	SHEET NUMBER
6/26/2015 1:27:54 PM bkloss	W:\Highway\Bridges\MethodsSection\CADD Concept Drafts\EnglishBTStubBridges.dgn 4548-BTCDE 11x17.pdf.pltcf				



CORRECTION 04-14 - ADDED REFERRAL NOTE TO SUMMARY QUANTITIES SHEET FOR THE DRAIN WEIGHT. NOTE ABOUT CHOICE OF EPOXY OR STAINLESS STEEL DECK TO BARRIER RAIL BARS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 4556-BTC-4 - THIS SHEET ISSUED 07-08.

TABLE OF SIZE OF 'b2' BAR	
LONGEST ADJACENT SPAN	BTC BEAM BAR SIZE
30'-0	** 4
35'-0	** 4
40'-0	** 4
45'-0	** 4
50'-0	** 4
55'-0	** 4
60'-0	** 6
65'-0	** 7
70'-0	** 7
75'-0	** 8
80'-0	** 9
85'-0	** 9
90'-0	7
95'-0	7
100'-0	8
105'-0	8
110'-0	8
115'-0	8
120'-0	8
125'-0	
130'-0	
135'-0	
140'-0	
145'-0	
150'-0	
155'-0	

THE MIDPOINT OF THE 'b2' BAR IS TO BE PLACED AT THE \bar{C} OF PIER.
 ** INDICATES 'b2' BAR PLACED IN TOP DECK ONLY.




HALF SECTION NEAR ABUTMENT (FIXED PIER SHOWN) HALF SECTION NEAR PIER



DATA FOR ONE DRAIN	
BEAM SIZE	BTC
DRAIN WEIGHT (LBS.)	106
DRAIN LENGTH (FT.)	5'-5 3/4

NOTE: FOR DETAILS OF INTERMEDIATE DIAPHRAGMS SEE DESIGN SHEET -----

SUPERSTRUCTURE NOTES:
 THE BRIDGE DECK AS SHOWN INCLUDES 1/2" INTEGRAL WEARING SURFACE.
 THE PIER AND ABUTMENT DIAPHRAGM CONCRETE IS TO BE PLACED MONOLITHICALLY WITH THE BRIDGE DECK.
 COST OF ALL PREFORMED EXPANSION JOINT FILLER MATERIAL IS TO BE INCLUDED IN THE PRICE BID FOR "STRUCTURAL CONCRETE (BRIDGE)".
 ALL BEAMS ARE TO BE SET VERTICAL.
 FORMS FOR THE BRIDGE DECK AND BARRIER RAIL ARE TO BE SUPPORTED BY THE PRESTRESSED CONCRETE BEAMS.
 CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR SHALL BE 2 INCHES UNLESS OTHERWISE NOTED OR SHOWN.
 ALL DECK AND DIAPHRAGM REINFORCING IS TO BE WIRED IN PLACE AND ADEQUATELY SUPPORTED BEFORE CONCRETE IS PLACED.
 TOP TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 2 1/2" CLEAR BELOW TOP OF DECK. BOTTOM TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 1" CLEAR ABOVE BOTTOM OF DECK.
 TOP AND BOTTOM REINFORCING STEEL IS TO BE SUPPORTED BY INDIVIDUAL BAR CHAIRS SPACED AT NOT MORE THAN 3'-0 CENTERS LONGITUDINALLY AND TRANSVERSELY, OR BY CONTINUOUS ROWS OF BAR HIGH CHAIRS OR DECK BOLSTERS SPACED 4'-0 APART. I.M. 451.01 REQUIREMENTS SHALL APPLY FOR BAR CHAIRS, BAR HIGH CHAIRS, AND DECK BOLSTERS.




HALF SECTION NEAR PIER (EXPANSION PIER SHOWN)

NOTE: "STAINLESS STEEL" LEVEL OR "REBAR EPOXY A" LEVEL SHOULD BE ON OR OFF DEPENDING ON BARRIER RAIL STEEL EMBEDDED IN THE BRIDGE DECK.
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____

CORRECTION 04-14 - ADDED REFERRAL NOTE TO SUMMARY QUANTITIES SHEET FOR THE DRAIN WEIGHT. NOTE ABOUT CHOICE OF EPOXY OR STAINLESS STEEL DECK TO BARRIER RAIL BARS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 4556-BTD-4 - THIS SHEET ISSUED 07-08.

TABLE OF SIZE OF 'b2' BAR	
LONGEST ADJACENT SPAN	BTD BEAM BAR SIZE
30'-0	
35'-0	
40'-0	
45'-0	
50'-0	** 4
55'-0	** 4
60'-0	** 5
65'-0	** 6
70'-0	** 6
75'-0	** 7
80'-0	** 8
85'-0	** 8
90'-0	** 9
95'-0	** 9
100'-0	7
105'-0	7
110'-0	8
115'-0	8
120'-0	8
125'-0	8
130'-0	9
135'-0	9
140'-0	
145'-0	
150'-0	
155'-0	

THE MIDPOINT OF THE 'b2' BAR IS TO BE PLACED AT THE ϕ OF PIER.
 ** INDICATES 'b2' BAR PLACED IN TOP DECK ONLY.



HALF SECTION NEAR ABUTMENT


HALF SECTION NEAR PIER

(FIXED PIER SHOWN)

NOTE: FOR DETAILS OF INTERMEDIATE DIAPHRAGMS SEE DESIGN SHEET -----

SUPERSTRUCTURE NOTES:

THE BRIDGE DECK AS SHOWN INCLUDES 1/2" INTEGRAL WEARING SURFACE.
 THE PIER AND ABUTMENT DIAPHRAGM CONCRETE IS TO BE PLACED MONOLITHICALLY WITH THE BRIDGE DECK.
 COST OF ALL PREFORMED EXPANSION JOINT FILLER MATERIAL IS TO BE INCLUDED IN THE PRICE BID FOR "STRUCTURAL CONCRETE (BRIDGE)". ALL BEAMS ARE TO BE SET VERTICAL.
 FORMS FOR THE BRIDGE DECK AND BARRIER RAIL ARE TO BE SUPPORTED BY THE PRESTRESSED CONCRETE BEAMS.
 CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR SHALL BE 2 INCHES UNLESS OTHERWISE NOTED OR SHOWN.
 ALL DECK AND DIAPHRAGM REINFORCING IS TO BE WIRED IN PLACE AND ADEQUATELY SUPPORTED BEFORE CONCRETE IS PLACED.
 TOP TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 2 1/2" CLEAR BELOW TOP OF DECK. BOTTOM TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 1" CLEAR ABOVE BOTTOM OF DECK.
 TOP AND BOTTOM REINFORCING STEEL IS TO BE SUPPORTED BY INDIVIDUAL BAR CHAIRS SPACED AT NOT MORE THAN 3'-0 CENTERS LONGITUDINALLY AND TRANSVERSELY, OR BY CONTINUOUS ROWS OF BAR HIGH CHAIRS OR DECK BOLSTERS SPACED 4'-0 APART. I.M. 451.01 REQUIREMENTS SHALL APPLY FOR BAR CHAIRS, BAR HIGH CHAIRS, AND DECK BOLSTERS.




HALF SECTION NEAR PIER


(EXPANSION PIER SHOWN)

NOTE: "STAINLESS STEEL" LEVEL OR "REBAR EPOXY A" LEVEL SHOULD BE ON OR OFF DEPENDING ON BARRIER RAIL STEEL EMBEDDED IN THE BRIDGE DECK.

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____




INTERIOR BEAMS



EXTERIOR BEAMS

TYPICAL DECK AND HAUNCH DETAIL

* FOR DECK THICKNESS OVER BEAMS SEE HAUNCH AND CAMBER DETAILS ON DESIGN SHEET -----



DRAIN DETAILS

NOTE: DRAIN WEIGHTS ARE INCLUDED ON THE SUMMARY QUANTITIES SHEET.
 NOTE: DRAINS ARE TO BE GALVANIZED. ----- DRAINS REQUIRED. SEE "SITUATION PLAN" FOR LOCATION. WEIGHT OF DRAINS IS INCLUDED IN THE QUANTITY FOR "-----". WEIGHT IS BASED ON ROLLED TUBE.



DATA FOR ONE DRAIN	
BEAM SIZE	BTD
DRAIN WEIGHT (LBS.)	120
DRAIN LENGTH (FT.)	6'-2 3/4

CORRECTION 04-14 - ADDED REFERRAL NOTE TO SUMMARY QUANTITIES SHEET FOR THE DRAIN WEIGHT. NOTE ABOUT CHOICE OF EPOXY OR STAINLESS STEEL DECK TO BARRIER RAIL BARS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 4556-BTE-4 - THIS SHEET ISSUED 07-08.

TABLE OF SIZE OF 'b2' BAR

LONGEST ADJACENT SPAN	BTE BEAM BAR SIZE
30'-0	
35'-0	
40'-0	
45'-0	
50'-0	
55'-0	
60'-0	** 4
65'-0	** 5
70'-0	** 6
75'-0	** 6
80'-0	** 7
85'-0	** 7
90'-0	** 8
95'-0	** 8
100'-0	** 9
105'-0	** 9
110'-0	7
115'-0	7
120'-0	7
125'-0	8
130'-0	8
135'-0	8
140'-0	9
145'-0	9
150'-0	9
155'-0	9


THE MIDPOINT OF THE 'b2' BAR IS TO BE PLACED AT THE \bar{C} OF PIER.
**** INDICATES 'b2' BAR PLACED IN TOP DECK ONLY.**



DATA FOR ONE DRAIN

BEAM SIZE	BTE
DRAIN WEIGHT (LBS.)	136
DRAIN LENGTH (FT.)	6'-11 3/4

NOTE: DRAINS ARE TO BE GALVANIZED. ---- DRAINS REQUIRED. SEE "SITUATION PLAN" FOR LOCATION. WEIGHT OF DRAINS IS INCLUDED IN THE QUANTITY FOR "----". WEIGHT IS BASED ON ROLLED TUBE.



HALF SECTION NEAR ABUTMENT


HALF SECTION NEAR PIER

(FIXED PIER SHOWN)

NOTE: FOR DETAILS OF INTERMEDIATE DIAPHRAGMS SEE DESIGN SHEET ----.

SUPERSTRUCTURE NOTES:

THE BRIDGE DECK AS SHOWN INCLUDES 1/2" INTEGRAL WEARING SURFACE.
 THE PIER AND ABUTMENT DIAPHRAGM CONCRETE IS TO BE PLACED MONOLITHICALLY WITH THE BRIDGE DECK.
 COST OF ALL PREFORMED EXPANSION JOINT FILLER MATERIAL IS TO BE INCLUDED IN THE PRICE BID FOR "STRUCTURAL CONCRETE (BRIDGE)".
 ALL BEAMS ARE TO BE SET VERTICAL.
 FORMS FOR THE BRIDGE DECK AND BARRIER RAIL ARE TO BE SUPPORTED BY THE PRESTRESSED CONCRETE BEAMS.
 CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR SHALL BE 2 INCHES UNLESS OTHERWISE NOTED OR SHOWN.
 ALL DECK AND DIAPHRAGM REINFORCING IS TO BE WIRED IN PLACE AND ADEQUATELY SUPPORTED BEFORE CONCRETE IS PLACED.
 TOP TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 2 1/2" CLEAR BELOW TOP OF DECK. BOTTOM TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 1" CLEAR ABOVE BOTTOM OF DECK.
 TOP AND BOTTOM REINFORCING STEEL IS TO BE SUPPORTED BY INDIVIDUAL BAR CHAIRS SPACED AT NOT MORE THAN 3'-0" CENTERS LONGITUDINALLY AND TRANSVERSELY, OR BY CONTINUOUS ROWS OF BAR HIGH CHAIRS OR DECK BOLSTERS SPACED 4'-0" APART. I.M. 451.01 REQUIREMENTS SHALL APPLY FOR BAR CHAIRS, BAR HIGH CHAIRS, AND DECK BOLSTERS.



HALF SECTION NEAR PIER

(EXPANSION PIER SHOWN)

NOTE: "STAINLESS STEEL" LEVEL OR "REBAR EPOXY A" LEVEL SHOULD BE ON OR OFF DEPENDING ON BARRIER RAIL STEEL EMBEDDED IN THE BRIDGE DECK.



IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____

CORRECTION 04-14 - ADDED REFERRAL NOTE TO SUMMARY QUANTITIES SHEET FOR THE DRAIN WEIGHT. NOTE ABOUT CHOICE OF EPOXY OR STAINLESS STEEL DECK TO BARRIER RAIL BARS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 4556-BTE-5 - THIS SHEET ISSUED 07-08.

TABLE OF SIZE OF 'b2' BAR	
LONGEST ADJACENT SPAN	BTE BEAM BAR SIZE
30'-0	---
35'-0	---
40'-0	---
45'-0	---
50'-0	---
55'-0	---
60'-0	** 4
65'-0	** 5
70'-0	** 6
75'-0	** 6
80'-0	** 7
85'-0	** 7
90'-0	** 8
95'-0	** 8
100'-0	** 9
105'-0	** 9
110'-0	7
115'-0	7
120'-0	7
125'-0	8
130'-0	8
135'-0	8
140'-0	9
145'-0	9
150'-0	9
155'-0	9


THE MIDPOINT OF THE 'b2' BAR IS TO BE PLACED AT THE \bar{C} OF PIER.

** INDICATES 'b2' BAR PLACED IN TOP DECK ONLY.




NOTE: DRAINS ARE TO BE GALVANIZED. ---- DRAINS REQUIRED. SEE "SITUATION PLAN" FOR LOCATION. WEIGHT OF DRAINS IS INCLUDED IN THE QUANTITY FOR "----". WEIGHT IS BASED ON ROLLED TUBE.

DATA FOR ONE DRAIN	
BEAM SIZE	BTE
DRAIN WEIGHT (LBS.)	136
DRAIN LENGTH (FT.)	6'-11 3/4



HALF SECTION NEAR ABUTMENT

HALF SECTION NEAR PIER (FIXED PIER SHOWN)



HALF SECTION NEAR PIER (EXPANSION PIER SHOWN)

NOTE: FOR DETAILS OF INTERMEDIATE DIAPHRAGMS SEE DESIGN SHEET ----.

SUPERSTRUCTURE NOTES:

THE BRIDGE DECK AS SHOWN INCLUDES 1/2" INTEGRAL WEARING SURFACE.
 THE PIER AND ABUTMENT DIAPHRAGM CONCRETE IS TO BE PLACED MONOLITHICALLY WITH THE BRIDGE DECK.
 COST OF ALL PREFORMED EXPANSION JOINT FILLER MATERIAL IS TO BE INCLUDED IN THE PRICE BID FOR "STRUCTURAL CONCRETE (BRIDGE)".
 ALL BEAMS ARE TO BE SET VERTICAL.
 FORMS FOR THE BRIDGE DECK AND BARRIER RAIL ARE TO BE SUPPORTED BY THE PRESTRESSED CONCRETE BEAMS.
 CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR SHALL BE 2 INCHES UNLESS OTHERWISE NOTED OR SHOWN.
 ALL DECK AND DIAPHRAGM REINFORCING IS TO BE WIRED IN PLACE AND ADEQUATELY SUPPORTED BEFORE CONCRETE IS PLACED.
 TOP TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 2 1/2" CLEAR BELOW TOP OF DECK. BOTTOM TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 1" CLEAR ABOVE BOTTOM OF DECK. TOP AND BOTTOM REINFORCING STEEL IS TO BE SUPPORTED BY INDIVIDUAL BAR CHAIRS SPACED AT NOT MORE THAN 3'-0 CENTERS LONGITUDINALLY AND TRANSVERSELY, OR BY CONTINUOUS ROWS OF BAR HIGH CHAIRS OR DECK BOLSTERS SPACED 4'-0 APART. I.M. 451.01 REQUIREMENTS SHALL APPLY FOR BAR CHAIRS, BAR HIGH CHAIRS, AND DECK BOLSTERS.


NOTE: "STAINLESS STEEL" LEVEL OR "REBAR EPOXY A" LEVEL SHOULD BE ON OR OFF DEPENDING ON BARRIER RAIL STEEL EMBEDDED IN THE BRIDGE DECK.

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____

CORRECTION 04-14 - ADDED REFERRAL NOTE TO SUMMARY QUANTITIES SHEET FOR THE DRAIN WEIGHT. NOTE ABOUT CHOICE OF EPOXY OR STAINLESS STEEL DECK TO BARRIER RAIL BARS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 4559-BTC-5 - THIS SHEET ISSUED 07-08.

TABLE OF SIZE OF 'b2' BAR	
LONGEST ADJACENT SPAN	BTC BEAM BAR SIZE
30'-0	** 4
35'-0	** 4
40'-0	** 4
45'-0	** 4
50'-0	** 4
55'-0	** 4
60'-0	** 6
65'-0	** 7
70'-0	** 7
75'-0	** 8
80'-0	** 9
85'-0	** 9
90'-0	7
95'-0	7
100'-0	8
105'-0	8
110'-0	8
115'-0	8
120'-0	8
125'-0	
130'-0	
135'-0	
140'-0	
145'-0	
150'-0	
155'-0	


THE MIDPOINT OF THE 'b2' BAR IS TO BE PLACED AT THE CL OF PIER.
 ** INDICATES 'b2' BAR PLACED IN TOP DECK ONLY.



HALF SECTION NEAR ABUTMENT

SLAB AREA = 29.27 SQ. FT.
 SLAB AREA DOES NOT INCLUDE THE HAUNCH.

HALF SECTION NEAR PIER (FIXED PIER SHOWN)




HALF SECTION NEAR PIER (EXPANSION PIER SHOWN)

NOTE: FOR DETAILS OF INTERMEDIATE DIAPHRAGMS SEE DESIGN SHEET -----

SUPERSTRUCTURE NOTES:


THE BRIDGE DECK AS SHOWN INCLUDES 1/2" INTEGRAL WEARING SURFACE.
 THE PIER AND ABUTMENT DIAPHRAGM CONCRETE IS TO BE PLACED MONOLITHICALLY WITH THE BRIDGE DECK.
 COST OF ALL PREFORMED EXPANSION JOINT FILLER MATERIAL IS TO BE INCLUDED IN THE PRICE BID FOR "STRUCTURAL CONCRETE (BRIDGE)".
 ALL BEAMS ARE TO BE SET VERTICAL.
 FORMS FOR THE BRIDGE DECK AND BARRIER RAIL ARE TO BE SUPPORTED BY THE PRESTRESSED CONCRETE BEAMS.
 CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR SHALL BE 2 INCHES UNLESS OTHERWISE NOTED OR SHOWN.
 ALL DECK AND DIAPHRAGM REINFORCING IS TO BE WIRED IN PLACE AND ADEQUATELY SUPPORTED BEFORE CONCRETE IS PLACED.
 TOP TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 2 1/2" CLEAR BELOW TOP OF DECK. BOTTOM TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 1" CLEAR ABOVE BOTTOM OF DECK.
 TOP AND BOTTOM REINFORCING STEEL IS TO BE SUPPORTED BY INDIVIDUAL BAR CHAIRS SPACED AT NOT MORE THAN 3'-0 CENTERS LONGITUDINALLY AND TRANSVERSELY, OR BY CONTINUOUS ROWS OF BAR HIGH CHAIRS OR DECK BOLSTERS SPACED 4'-0 APART. I.M. 451.01 REQUIREMENTS SHALL APPLY FOR BAR CHAIRS, BAR HIGH CHAIRS, AND DECK BOLSTERS.
 TRANSVERSE DECK REINFORCING MAY BE SPLICED WITH ONE LAP LOCATED AS FOLLOWS:
 TOP BAR - LAP MIDWAY BETWEEN BEAMS (MIN. LAP = 1'-10).
 BOTTOM BARS - LAP OVER BEAMS (MIN. LAP = 1'-10).
 PAYMENT FOR REINFORCING BARS SHALL BE BASED ON NO SPLICES, AND NO ALLOWANCE SHALL BE MADE FOR THE ADDITIONAL LENGTH OF BAR REQUIRED FOR THE USE OF SPLICES.



DRAIN DETAILS

NOTE: DRAINS ARE TO BE GALVANIZED. ----- DRAINS REQUIRED. SEE "SITUATION PLAN" FOR LOCATION. WEIGHT OF DRAINS IS INCLUDED IN THE QUANTITY FOR "-----". WEIGHT IS BASED ON ROLLED TUBE.

DATA FOR ONE DRAIN	
BEAM SIZE	BTC
DRAIN WEIGHT (LBS.)	106
DRAIN LENGTH (FT.)	5'-5 3/4



TYPICAL DECK AND HAUNCH DETAIL




* FOR DECK THICKNESS OVER BEAMS SEE HAUNCH AND CAMBER DETAILS ON DESIGN SHEET -----

NOTE: "STAINLESS STEEL" LEVEL OR "REBAR EPOXY A" LEVEL SHOULD BE ON OR OFF DEPENDING ON BARRIER RAIL STEEL EMBEDDED IN THE BRIDGE DECK.
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____

CORRECTION 04-14 - ADDED REFERRAL NOTE TO SUMMARY QUANTITIES SHEET FOR THE DRAIN WEIGHT. NOTE ABOUT CHOICE OF EPOXY OR STAINLESS STEEL DECK TO BARRIER RAIL BARS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 4559-BTD-5 - THIS SHEET ISSUED 07-08.

TABLE OF SIZE OF 'b2' BAR	
LONGEST ADJACENT SPAN	BTD BEAM BAR SIZE
30'-0	
35'-0	
40'-0	
45'-0	
50'-0	** 4
55'-0	** 4
60'-0	** 5
65'-0	** 6
70'-0	** 6
75'-0	** 7
80'-0	** 8
85'-0	** 8
90'-0	** 9
95'-0	** 9
100'-0	7
105'-0	7
110'-0	8
115'-0	8
120'-0	8
125'-0	8
130'-0	9
135'-0	9
140'-0	
145'-0	
150'-0	
155'-0	

THE MIDPOINT OF THE 'b2' BAR IS TO BE PLACED AT THE CL OF PIER.
 ** INDICATES 'b2' BAR PLACED IN TOP DECK ONLY.




NOTE: DRAINS ARE TO BE GALVANIZED. ----- DRAINS REQUIRED. SEE "SITUATION PLAN" FOR LOCATION. WEIGHT OF DRAINS IS INCLUDED IN THE QUANTITY FOR "-----". WEIGHT IS BASED ON ROLLED TUBE.

DATA FOR ONE DRAIN	
BEAM SIZE	BTD
DRAIN WEIGHT (LBS.)	120
DRAIN LENGTH (FT.)	6'-2 3/4

NOTE: FOR DETAILS OF INTERMEDIATE DIAPHRAGMS SEE DESIGN SHEET -----

SUPERSTRUCTURE NOTES:

THE BRIDGE DECK AS SHOWN INCLUDES 1/2" INTEGRAL WEARING SURFACE.
 THE PIER AND ABUTMENT DIAPHRAGM CONCRETE IS TO BE PLACED MONOLITHICALLY WITH THE BRIDGE DECK.
 COST OF ALL PREFORMED EXPANSION JOINT FILLER MATERIAL IS TO BE INCLUDED IN THE PRICE BID FOR "STRUCTURAL CONCRETE (BRIDGE)".
 ALL BEAMS ARE TO BE SET VERTICAL.
 FORMS FOR THE BRIDGE DECK AND BARRIER RAIL ARE TO BE SUPPORTED BY THE PRESTRESSED CONCRETE BEAMS.
 CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR SHALL BE 2 INCHES UNLESS OTHERWISE NOTED OR SHOWN.
 ALL DECK AND DIAPHRAGM REINFORCING IS TO BE WIRED IN PLACE AND ADEQUATELY SUPPORTED BEFORE CONCRETE IS PLACED.
 TOP TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 2 1/2" CLEAR BELOW TOP OF DECK. BOTTOM TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 1" CLEAR ABOVE BOTTOM OF DECK.
 TOP AND BOTTOM REINFORCING STEEL IS TO BE SUPPORTED BY INDIVIDUAL BAR CHAIRS SPACED AT NOT MORE THAN 3'-0 CENTERS LONGITUDINALLY AND TRANSVERSELY, OR BY CONTINUOUS ROWS OF BAR HIGH CHAIRS OR DECK BOLSTERS SPACED 4'-0 APART. I.M. 451.01 REQUIREMENTS SHALL APPLY FOR BAR CHAIRS, BAR HIGH CHAIRS, AND DECK BOLSTERS.
 TRANSVERSE DECK REINFORCING MAY BE SPLICED WITH ONE LAP LOCATED AS FOLLOWS:
 TOP BAR - LAP MIDWAY BETWEEN BEAMS (MIN. LAP = 1'-10).
 BOTTOM BARS - LAP OVER BEAMS (MIN. LAP = 1'-10).
 PAYMENT FOR REINFORCING BARS SHALL BE BASED ON NO SPLICES, AND NO ALLOWANCE SHALL BE MADE FOR THE ADDITIONAL LENGTH OF BAR REQUIRED FOR THE USE OF SPLICES.






NOTE: "STAINLESS STEEL" LEVEL OR "REBAR EPOXY A" LEVEL SHOULD BE ON OR OFF DEPENDING ON BARRIER RAIL STEEL EMBEDDED IN THE BRIDGE DECK.
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____

CORRECTION 04-14 - ADDED REFERRAL NOTE TO SUMMARY QUANTITIES SHEET FOR THE DRAIN WEIGHT. NOTE ABOUT CHOICE OF EPOXY OR STAINLESS STEEL DECK TO BARRIER RAIL BARS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 4559-BTE-6 - THIS SHEET ISSUED 07-08.

TABLE OF SIZE OF 'b2' BAR	
LONGEST ADJACENT SPAN	BTE BEAM BAR SIZE
30'-0	
35'-0	
40'-0	
45'-0	
50'-0	
55'-0	
60'-0	** 4
65'-0	** 5
70'-0	** 6
75'-0	** 6
80'-0	** 7
85'-0	** 7
90'-0	** 8
95'-0	** 8
100'-0	** 9
105'-0	** 9
110'-0	7
115'-0	7
120'-0	7
125'-0	8
130'-0	8
135'-0	8
140'-0	9
145'-0	9
150'-0	9
155'-0	9

THE MIDPOINT OF THE 'b2' BAR IS TO BE PLACED AT THE CL OF PIER.
 ** INDICATES 'b2' BAR PLACED IN TOP DECK ONLY.




DATA FOR ONE DRAIN	
BEAM SIZE	BTE
DRAIN WEIGHT (LBS.)	136
DRAIN LENGTH (FT.)	6'-11 3/4

NOTE: DRAINS ARE TO BE GALVANIZED. ---- DRAINS REQUIRED. SEE "SITUATION PLAN" FOR LOCATION. WEIGHT OF DRAINS IS INCLUDED IN THE QUANTITY FOR "----". WEIGHT IS BASED ON ROLLED TUBE.

HALF SECTION NEAR ABUTMENT

SLAB AREA = 29.24 SQ. FT.
 SLAB AREA DOES NOT INCLUDE THE HAUNCH.

HALF SECTION NEAR PIER (FIXED PIER SHOWN)



HALF SECTION NEAR PIER (EXPANSION PIER SHOWN)

NOTE: FOR DETAILS OF INTERMEDIATE DIAPHRAGMS SEE DESIGN SHEET ----

SUPERSTRUCTURE NOTES:

THE BRIDGE DECK AS SHOWN INCLUDES 1/2" INTEGRAL WEARING SURFACE.
 THE PIER AND ABUTMENT DIAPHRAGM CONCRETE IS TO BE PLACED MONOLITHICALLY WITH THE BRIDGE DECK.
 COST OF ALL PREFORMED EXPANSION JOINT FILLER MATERIAL IS TO BE INCLUDED IN THE PRICE BID FOR "STRUCTURAL CONCRETE (BRIDGE)".
 ALL BEAMS ARE TO BE SET VERTICAL.
 FORMS FOR THE BRIDGE DECK AND BARRIER RAIL ARE TO BE SUPPORTED BY THE PRESTRESSED CONCRETE BEAMS.
 CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR SHALL BE 2 INCHES UNLESS OTHERWISE NOTED OR SHOWN.
 ALL DECK AND DIAPHRAGM REINFORCING IS TO BE WIRED IN PLACE AND ADEQUATELY SUPPORTED BEFORE CONCRETE IS PLACED.
 TOP TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 2 1/2" CLEAR BELOW TOP OF DECK. BOTTOM TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 1" CLEAR ABOVE BOTTOM OF DECK.
 TOP AND BOTTOM REINFORCING STEEL IS TO BE SUPPORTED BY INDIVIDUAL BAR CHAIRS SPACED AT NOT MORE THAN 3'-0" CENTERS LONGITUDINALLY AND TRANSVERSELY, OR BY CONTINUOUS ROWS OF BAR HIGH CHAIRS OR DECK BOLSTERS SPACED 4'-0" APART. I.M. 451.01 REQUIREMENTS SHALL APPLY FOR BAR CHAIRS, BAR HIGH CHAIRS, AND DECK BOLSTERS.
 TRANSVERSE DECK REINFORCING MAY BE SPLICED WITH ONE LAP LOCATED AS FOLLOWS:
 TOP BAR - LAP MIDWAY BETWEEN BEAMS (MIN. LAP = 1'-10").
 BOTTOM BARS - LAP OVER BEAMS (MIN. LAP = 1'-10").
 PAYMENT FOR REINFORCING BARS SHALL BE BASED ON NO SPLICES, AND NO ALLOWANCE SHALL BE MADE FOR THE ADDITIONAL LENGTH OF BAR REQUIRED FOR THE USE OF SPLICES.


NOTE: "STAINLESS STEEL" LEVEL OR "REBAR EPOXY A" LEVEL SHOULD BE ON OR OFF DEPENDING ON BARRIER RAIL STEEL EMBEDDED IN THE BRIDGE DECK.
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____

CORRECTION 04-14 - ADDED REFERRAL NOTE TO SUMMARY QUANTITIES SHEET FOR THE DRAIN WEIGHT. NOTE ABOUT CHOICE OF EPOXY OR STAINLESS STEEL DECK TO BARRIER RAIL BARS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 4560-BTC-6 - THIS SHEET ISSUED 07-08.

TABLE OF SIZE OF 'b2' BAR	
LONGEST ADJACENT SPAN	BTC BEAM BAR SIZE
30'-0"	** 4
35'-0"	** 4
40'-0"	** 4
45'-0"	** 4
50'-0"	** 4
55'-0"	** 4
60'-0"	** 6
65'-0"	** 7
70'-0"	** 7
75'-0"	** 8
80'-0"	** 9
85'-0"	** 9
90'-0"	7
95'-0"	7
100'-0"	8
105'-0"	8
110'-0"	8
115'-0"	8
120'-0"	8
125'-0"	
130'-0"	
135'-0"	
140'-0"	
145'-0"	
150'-0"	
155'-0"	



THE MIDPOINT OF THE 'b2' BAR IS TO BE PLACED AT THE CL OF PIER.

** INDICATES 'b2' BAR PLACED IN TOP DECK ONLY.



HALF SECTION NEAR ABUTMENT

HALF SECTION NEAR PIER (FIXED PIER SHOWN)




NOTE: DRAINS ARE TO BE GALVANIZED. ---- DRAINS REQUIRED. SEE "SITUATION PLAN" FOR LOCATION. WEIGHT OF DRAINS IS INCLUDED IN THE QUANTITY FOR "----". WEIGHT IS BASED ON ROLLED TUBE.

DATA FOR ONE DRAIN	
BEAM SIZE	BTC
DRAIN WEIGHT (LBS.)	106
DRAIN LENGTH (FT.)	5'-5 3/4

NOTE: FOR DETAILS OF INTERMEDIATE DIAPHRAGMS SEE DESIGN SHEET ----

SUPERSTRUCTURE NOTES:

THE BRIDGE DECK AS SHOWN INCLUDES 1/2" INTEGRAL WEARING SURFACE.
 THE PIER AND ABUTMENT DIAPHRAGM CONCRETE IS TO BE PLACED MONOLITHICALLY WITH THE BRIDGE DECK.
 COST OF ALL PREFORMED EXPANSION JOINT FILLER MATERIAL IS TO BE INCLUDED IN THE PRICE BID FOR "STRUCTURAL CONCRETE (BRIDGE)". ALL BEAMS ARE TO BE SET VERTICAL.
 FORMS FOR THE BRIDGE DECK AND BARRIER RAIL ARE TO BE SUPPORTED BY THE PRESTRESSED CONCRETE BEAMS.
 CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR SHALL BE 2 INCHES UNLESS OTHERWISE NOTED OR SHOWN.
 ALL DECK AND DIAPHRAGM REINFORCING IS TO BE WIRED IN PLACE AND ADEQUATELY SUPPORTED BEFORE CONCRETE IS PLACED.
 TOP TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 2 1/2" CLEAR BELOW TOP OF DECK. BOTTOM TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 1" CLEAR ABOVE BOTTOM OF DECK. TOP AND BOTTOM REINFORCING STEEL IS TO BE SUPPORTED BY INDIVIDUAL BAR CHAIRS SPACED AT NOT MORE THAN 3'-0" CENTERS LONGITUDINALLY AND TRANSVERSELY, OR BY CONTINUOUS ROWS OF BAR HIGH CHAIRS OR DECK BOLSTERS SPACED 4'-0" APART. I.M. 451.01 REQUIREMENTS SHALL APPLY FOR BAR CHAIRS, BAR HIGH CHAIRS, AND DECK BOLSTERS.
 TRANSVERSE DECK REINFORCING MAY BE SPLICED WITH ONE LAP LOCATED AS FOLLOWS:
 TOP BAR - LAP MIDWAY BETWEEN BEAMS (MIN. LAP = 1'-10").
 BOTTOM BARS - LAP OVER BEAMS (MIN. LAP = 1'-10").
 PAYMENT FOR REINFORCING BARS SHALL BE BASED ON NO SPLICES, AND NO ALLOWANCE SHALL BE MADE FOR THE ADDITIONAL LENGTH OF BAR REQUIRED FOR THE USE OF SPLICES.



HALF SECTION NEAR PIER (EXPANSION PIER SHOWN)

NOTE: "STAINLESS STEEL" LEVEL OR "REBAR EPOXY A" LEVEL SHOULD BE ON OR OFF DEPENDING ON BARRIER RAIL STEEL EMBEDDED IN THE BRIDGE DECK.


IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____

CORRECTION 04-14 - ADDED REFERRAL NOTE TO SUMMARY QUANTITIES SHEET FOR THE DRAIN WEIGHT. NOTE ABOUT CHOICE OF EPOXY OR STAINLESS STEEL DECK TO BARRIER RAIL BARS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 4560-BTD-6 - THIS SHEET ISSUED 07-08.

TABLE OF SIZE OF 'b2' BAR	
LONGEST ADJACENT SPAN	BTD BEAM BAR SIZE
30'-0	
35'-0	
40'-0	
45'-0	
50'-0	** 4
55'-0	** 4
60'-0	** 5
65'-0	** 6
70'-0	** 6
75'-0	** 7
80'-0	** 8
85'-0	** 8
90'-0	** 9
95'-0	** 9
100'-0	7
105'-0	7
110'-0	8
115'-0	8
120'-0	8
125'-0	8
130'-0	9
135'-0	9
140'-0	
145'-0	
150'-0	
155'-0	


THE MIDPOINT OF THE 'b2' BAR IS TO BE PLACED AT THE \bar{C} OF PIER.

** INDICATES 'b2' BAR PLACED IN TOP DECK ONLY.




SLAB AREA = 31.93 SQ. FT.
SLAB AREA DOES NOT INCLUDE THE HAUNCH.

FOR DETAILS OF RAIL AND RAIL REINFORCING SEE STANDARD BARRIER RAIL SHEET




INTERIOR BEAMS



EXTERIOR BEAMS
TYPICAL DECK AND HAUNCH DETAIL

* FOR DECK THICKNESS OVER BEAMS SEE HAUNCH AND CAMBER DETAILS ON DESIGN SHEET



DRAIN DETAILS

NOTE: DRAIN WEIGHTS ARE INCLUDED ON THE SUMMARY QUANTITIES SHEET.
NOTE: DRAINS ARE TO BE GALVANIZED. --- DRAINS REQUIRED. SEE "SITUATION PLAN" FOR LOCATION. WEIGHT OF DRAINS IS INCLUDED IN THE QUANTITY FOR "----". WEIGHT IS BASED ON ROLLED TUBE.

DATA FOR ONE DRAIN	
BEAM SIZE	BTD
DRAIN WEIGHT (LBS.)	120
DRAIN LENGTH (FT.)	6'-2 3/4

HALF SECTION NEAR ABUTMENT


HALF SECTION NEAR PIER

(FIXED PIER SHOWN)

NOTE: FOR DETAILS OF INTERMEDIATE DIAPHRAGMS SEE DESIGN SHEET

SUPERSTRUCTURE NOTES:

THE BRIDGE DECK AS SHOWN INCLUDES 1/2" INTEGRAL WEARING SURFACE.
THE PIER AND ABUTMENT DIAPHRAGM CONCRETE IS TO BE PLACED MONOLITHICALLY WITH THE BRIDGE DECK.
COST OF ALL PREFORMED EXPANSION JOINT FILLER MATERIAL IS TO BE INCLUDED IN THE PRICE BID FOR "STRUCTURAL CONCRETE (BRIDGE)". ALL BEAMS ARE TO BE SET VERTICAL.
FORMS FOR THE BRIDGE DECK AND BARRIER RAIL ARE TO BE SUPPORTED BY THE PRESTRESSED CONCRETE BEAMS.
CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR SHALL BE 2 INCHES UNLESS OTHERWISE NOTED OR SHOWN.
ALL DECK AND DIAPHRAGM REINFORCING IS TO BE WIRED IN PLACE AND ADEQUATELY SUPPORTED BEFORE CONCRETE IS PLACED.
TOP TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 2 1/2" CLEAR BELOW TOP OF DECK. BOTTOM TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 1" CLEAR ABOVE BOTTOM OF DECK. TOP AND BOTTOM REINFORCING STEEL IS TO BE SUPPORTED BY INDIVIDUAL BAR CHAIRS SPACED AT NOT MORE THAN 3'-0 CENTERS LONGITUDINALLY AND TRANSVERSELY, OR BY CONTINUOUS ROWS OF BAR HIGH CHAIRS OR DECK BOLSTERS SPACED 4'-0 APART. I.M. 451.01 REQUIREMENTS SHALL APPLY FOR BAR CHAIRS, BAR HIGH CHAIRS, AND DECK BOLSTERS.
TRANSVERSE DECK REINFORCING MAY BE SPLICED WITH ONE LAP LOCATED AS FOLLOWS:
TOP BAR - LAP MIDWAY BETWEEN BEAMS (MIN. LAP = 1'-10).
BOTTOM BARS - LAP OVER BEAMS (MIN. LAP = 1'-10).
PAYMENT FOR REINFORCING BARS SHALL BE BASED ON NO SPLICES, AND NO ALLOWANCE SHALL BE MADE FOR THE ADDITIONAL LENGTH OF BAR REQUIRED FOR THE USE OF SPLICES.



HALF SECTION NEAR PIER

(EXPANSION PIER SHOWN)




NOTE: "STAINLESS STEEL" LEVEL OR "REBAR EPOXY A" LEVEL SHOULD BE ON OR OFF DEPENDING ON BARRIER RAIL STEEL EMBEDDED IN THE BRIDGE DECK.

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____

CORRECTION 04-14 - ADDED REFERRAL NOTE TO SUMMARY QUANTITIES SHEET FOR THE DRAIN WEIGHT. NOTE ABOUT CHOICE OF EPOXY OR STAINLESS STEEL DECK TO BARRIER RAIL BARS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 4560-BTE-6 - THIS SHEET ISSUED 07-08.

TABLE OF SIZE OF 'b2' BAR	
LONGEST ADJACENT SPAN	BTE BEAM BAR SIZE
30'-0	
35'-0	
40'-0	
45'-0	
50'-0	
55'-0	
60'-0	** 4
65'-0	** 5
70'-0	** 6
75'-0	** 6
80'-0	** 7
85'-0	** 7
90'-0	** 8
95'-0	** 8
100'-0	** 9
105'-0	** 9
110'-0	7
115'-0	7
120'-0	7
125'-0	8
130'-0	8
135'-0	8
140'-0	9
145'-0	9
150'-0	9
155'-0	9

THE MIDPOINT OF THE 'b2' BAR IS TO BE PLACED AT THE ϕ OF PIER.
 ** INDICATES 'b2' BAR PLACED IN TOP DECK ONLY.




NOTE: DRAINS ARE TO BE GALVANIZED. ----- DRAINS REQUIRED. SEE "SITUATION PLAN" FOR LOCATION. WEIGHT OF DRAINS IS INCLUDED IN THE QUANTITY FOR "-----". WEIGHT IS BASED ON ROLLED TUBE.

DATA FOR ONE DRAIN	
BEAM SIZE	BTE
DRAIN WEIGHT (LBS.)	136
DRAIN LENGTH (FT.)	6'-11 $\frac{3}{4}$

NOTE: FOR DETAILS OF INTERMEDIATE DIAPHRAGMS SEE DESIGN SHEET -----

SUPERSTRUCTURE NOTES:

THE BRIDGE DECK AS SHOWN INCLUDES 1/2" INTEGRAL WEARING SURFACE.
 THE PIER AND ABUTMENT DIAPHRAGM CONCRETE IS TO BE PLACED MONOLITHICALLY WITH THE BRIDGE DECK.
 COST OF ALL PREFORMED EXPANSION JOINT FILLER MATERIAL IS TO BE INCLUDED IN THE PRICE BID FOR "STRUCTURAL CONCRETE (BRIDGE)".
 ALL BEAMS ARE TO BE SET VERTICAL.
 FORMS FOR THE BRIDGE DECK AND BARRIER RAIL ARE TO BE SUPPORTED BY THE PRESTRESSED CONCRETE BEAMS.
 CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR SHALL BE 2 INCHES UNLESS OTHERWISE NOTED OR SHOWN.
 ALL DECK AND DIAPHRAGM REINFORCING IS TO BE WIRED IN PLACE AND ADEQUATELY SUPPORTED BEFORE CONCRETE IS PLACED.
 TOP TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 2 1/2" CLEAR BELOW TOP OF DECK. BOTTOM TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 1" CLEAR ABOVE BOTTOM OF DECK.
 TOP AND BOTTOM REINFORCING STEEL IS TO BE SUPPORTED BY INDIVIDUAL BAR CHAIRS SPACED AT NOT MORE THAN 3'-0 CENTERS LONGITUDINALLY AND TRANSVERSELY, OR BY CONTINUOUS ROWS OF BAR HIGH CHAIRS OR DECK BOLSTERS SPACED 4'-0 APART. I.M. 451.01 REQUIREMENTS SHALL APPLY FOR BAR CHAIRS, BAR HIGH CHAIRS, AND DECK BOLSTERS.
 TRANSVERSE DECK REINFORCING MAY BE SPLICED WITH ONE LAP LOCATED AS FOLLOWS:
 TOP BAR - LAP MIDWAY BETWEEN BEAMS (MIN. LAP = 1'-10).
 BOTTOM BARS - LAP OVER BEAMS (MIN. LAP = 1'-10).
 PAYMENT FOR REINFORCING BARS SHALL BE BASED ON NO SPLICES, AND NO ALLOWANCE SHALL BE MADE FOR THE ADDITIONAL LENGTH OF BAR REQUIRED FOR THE USE OF SPLICES.




NOTE: "STAINLESS STEEL" LEVEL OR "REBAR EPOXY A" LEVEL SHOULD BE ON OR OFF DEPENDING ON BARRIER RAIL STEEL EMBEDDED IN THE BRIDGE DECK.
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____

CORRECTION 04-14 - ADDED REFERRAL NOTE TO SUMMARY QUANTITIES SHEET FOR THE DRAIN WEIGHT. NOTE ABOUT CHOICE OF EPOXY OR STAINLESS STEEL DECK TO BARRIER RAIL BARS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 4561-BTC-5 - THIS SHEET ISSUED 07-08.

TABLE OF SIZE OF 'b2' BAR	
LONGEST ADJACENT SPAN	BTC BEAM BAR SIZE
30'-0	** 4
35'-0	** 4
40'-0	** 4
45'-0	** 4
50'-0	** 4
55'-0	** 4
60'-0	** 6
65'-0	** 7
70'-0	** 7
75'-0	** 8
80'-0	** 9
85'-0	** 9
90'-0	7
95'-0	7
100'-0	8
105'-0	8
110'-0	8
115'-0	8
120'-0	8
125'-0	
130'-0	
135'-0	
140'-0	
145'-0	
150'-0	
155'-0	


THE MIDPOINT OF THE 'b2' BAR IS TO BE PLACED AT THE C OF PIER.

** INDICATES 'b2' BAR PLACED IN TOP DECK ONLY.




HALF SECTION NEAR ABUTMENT

HALF SECTION NEAR PIER (FIXED PIER SHOWN)



TYPICAL DECK AND HAUNCH DETAIL

* FOR DECK THICKNESS OVER BEAMS SEE HAUNCH AND CAMBER DETAILS ON DESIGN SHEET -----



DRAIN DETAILS


NOTE: DRAINS ARE TO BE GALVANIZED. ----- DRAINS REQUIRED. SEE "SITUATION PLAN" FOR LOCATION. WEIGHT OF DRAINS IS INCLUDED IN THE QUANTITY FOR "-----". WEIGHT IS BASED ON ROLLED TUBE.

DATA FOR ONE DRAIN	
BEAM SIZE	BTC
DRAIN WEIGHT (LBS.)	106
DRAIN LENGTH (FT.)	5'-5 3/4

NOTE: FOR DETAILS OF INTERMEDIATE DIAPHRAGMS SEE DESIGN SHEET -----

SUPERSTRUCTURE NOTES:

THE BRIDGE DECK AS SHOWN INCLUDES 1/2" INTEGRAL WEARING SURFACE.
 THE PIER AND ABUTMENT DIAPHRAGM CONCRETE IS TO BE PLACED MONOLITHICALLY WITH THE BRIDGE DECK.
 COST OF ALL PREFORMED EXPANSION JOINT FILLER MATERIAL IS TO BE INCLUDED IN THE PRICE BID FOR "STRUCTURAL CONCRETE (BRIDGE)". ALL BEAMS ARE TO BE SET VERTICAL.
 FORMS FOR THE BRIDGE DECK AND BARRIER RAIL ARE TO BE SUPPORTED BY THE PRESTRESSED CONCRETE BEAMS.
 CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR SHALL BE 2 INCHES UNLESS OTHERWISE NOTED OR SHOWN.
 ALL DECK AND DIAPHRAGM REINFORCING IS TO BE WIRED IN PLACE AND ADEQUATELY SUPPORTED BEFORE CONCRETE IS PLACED.
 TOP TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 2 1/2" CLEAR BELOW TOP OF DECK. BOTTOM TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 1" CLEAR ABOVE BOTTOM OF DECK. TOP AND BOTTOM REINFORCING STEEL IS TO BE SUPPORTED BY INDIVIDUAL BAR CHAIRS SPACED AT NOT MORE THAN 3'-0 CENTERS LONGITUDINALLY AND TRANSVERSELY, OR BY CONTINUOUS ROWS OF BAR HIGH CHAIRS OR DECK BOLSTERS SPACED 4'-0 APART. I.M. 451.01 REQUIREMENTS SHALL APPLY FOR BAR CHAIRS, BAR HIGH CHAIRS, AND DECK BOLSTERS.
 TRANSVERSE DECK REINFORCING MAY BE SPLICED WITH ONE LAP LOCATED AS FOLLOWS:
 TOP BAR - LAP MIDWAY BETWEEN BEAMS (MIN. LAP = 1'-10).
 BOTTOM BARS - LAP OVER BEAMS (MIN. LAP = 1'-10).
 PAYMENT FOR REINFORCING BARS SHALL BE BASED ON NO SPLICES, AND NO ALLOWANCE SHALL BE MADE FOR THE ADDITIONAL LENGTH OF BAR REQUIRED FOR THE USE OF SPLICES.



HALF SECTION NEAR PIER (EXPANSION PIER SHOWN)

NOTE: "STAINLESS STEEL" LEVEL OR "REBAR EPOXY A" LEVEL SHOULD BE ON OR OFF DEPENDING ON BARRIER RAIL STEEL EMBEDDED IN THE BRIDGE DECK.


IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____

CORRECTION 04-14 - ADDED REFERRAL NOTE TO SUMMARY QUANTITIES SHEET FOR THE DRAIN WEIGHT. NOTE ABOUT CHOICE OF EPOXY OR STAINLESS STEEL DECK TO BARRIER RAIL BARS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 4561-BTC-6 - THIS SHEET ISSUED 07-08.

TABLE OF SIZE OF 'b2' BAR	
LONGEST ADJACENT SPAN	BTC BEAM BAR SIZE
30'-0	***4
35'-0	***4
40'-0	***4
45'-0	***4
50'-0	***4
55'-0	***4
60'-0	***6
65'-0	***7
70'-0	***7
75'-0	***8
80'-0	***9
85'-0	***9
90'-0	7
95'-0	7
100'-0	8
105'-0	8
110'-0	8
115'-0	8
120'-0	8
125'-0	
130'-0	
135'-0	
140'-0	
145'-0	
150'-0	
155'-0	


THE MIDPOINT OF THE 'b2' BAR IS TO BE PLACED AT THE CL OF PIER.

** INDICATES 'b2' BAR PLACED IN TOP DECK ONLY.




HALF SECTION NEAR ABUTMENT

HALF SECTION NEAR PIER (FIXED PIER SHOWN)



TYPICAL DECK AND HAUNCH DETAIL



DRAIN DETAILS


NOTE: DRAINS ARE TO BE GALVANIZED. ----- DRAINS REQUIRED. SEE "SITUATION PLAN" FOR LOCATION. WEIGHT OF DRAINS IS INCLUDED IN THE QUANTITY FOR "-----". WEIGHT IS BASED ON ROLLED TUBE.

DATA FOR ONE DRAIN	
BEAM SIZE	BTC
DRAIN WEIGHT (LBS.)	106
DRAIN LENGTH (FT.)	5'-5 3/4

NOTE: FOR DETAILS OF INTERMEDIATE DIAPHRAGMS SEE DESIGN SHEET -----

SUPERSTRUCTURE NOTES:

THE BRIDGE DECK AS SHOWN INCLUDES 1/2" INTEGRAL WEARING SURFACE.
 THE PIER AND ABUTMENT DIAPHRAGM CONCRETE IS TO BE PLACED MONOLITHICALLY WITH THE BRIDGE DECK.
 COST OF ALL PREFORMED EXPANSION JOINT FILLER MATERIAL IS TO BE INCLUDED IN THE PRICE BID FOR "STRUCTURAL CONCRETE (BRIDGE)". ALL BEAMS ARE TO BE SET VERTICAL.
 FORMS FOR THE BRIDGE DECK AND BARRIER RAIL ARE TO BE SUPPORTED BY THE PRESTRESSED CONCRETE BEAMS.
 CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR SHALL BE 2 INCHES UNLESS OTHERWISE NOTED OR SHOWN.
 ALL DECK AND DIAPHRAGM REINFORCING IS TO BE WIRED IN PLACE AND ADEQUATELY SUPPORTED BEFORE CONCRETE IS PLACED.
 TOP TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 2 1/2" CLEAR BELOW TOP OF DECK. BOTTOM TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 1" CLEAR ABOVE BOTTOM OF DECK. TOP AND BOTTOM REINFORCING STEEL IS TO BE SUPPORTED BY INDIVIDUAL BAR CHAIRS SPACED AT NOT MORE THAN 3'-0 CENTERS LONGITUDINALLY AND TRANSVERSELY, OR BY CONTINUOUS ROWS OF BAR HIGH CHAIRS OR DECK BOLSTERS SPACED 4'-0 APART. I.M. 451.01 REQUIREMENTS SHALL APPLY FOR BAR CHAIRS, BAR HIGH CHAIRS, AND DECK BOLSTERS.
 TRANSVERSE DECK REINFORCING MAY BE SPLICED WITH ONE LAP LOCATED AS FOLLOWS:
 TOP BAR - LAP MIDWAY BETWEEN BEAMS (MIN. LAP = 1'-10).
 BOTTOM BARS - LAP OVER BEAMS (MIN. LAP = 1'-10).
 PAYMENT FOR REINFORCING BARS SHALL BE BASED ON NO SPLICES, AND NO ALLOWANCE SHALL BE MADE FOR THE ADDITIONAL LENGTH OF BAR REQUIRED FOR THE USE OF SPLICES.




HALF SECTION NEAR PIER (EXPANSION PIER SHOWN)

NOTE: "STAINLESS STEEL" LEVEL OR "REBAR EPOXY A" LEVEL SHOULD BE ON OR OFF DEPENDING ON BARRIER RAIL STEEL EMBEDDED IN THE BRIDGE DECK.
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____

CORRECTION 04-14 - ADDED REFERRAL NOTE TO SUMMARY QUANTITIES SHEET FOR THE DRAIN WEIGHT. NOTE ABOUT CHOICE OF EPOXY OR STAINLESS STEEL DECK TO BARRIER RAIL BARS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 4561-BTD-5 - THIS SHEET ISSUED 07-08.


TABLE OF SIZE OF 'b2' BAR	
LONGEST ADJACENT SPAN	BTD BEAM BAR SIZE
30'-0	---
35'-0	---
40'-0	---
45'-0	---
50'-0	** 4
55'-0	** 4
60'-0	** 5
65'-0	** 6
70'-0	** 6
75'-0	** 7
80'-0	** 8
85'-0	** 8
90'-0	** 9
95'-0	** 9
100'-0	7
105'-0	7
110'-0	8
115'-0	8
120'-0	8
125'-0	8
130'-0	9
135'-0	9
140'-0	---
145'-0	---
150'-0	---
155'-0	---

THE MIDPOINT OF THE 'b2' BAR IS TO BE PLACED AT THE \bar{C} OF PIER.
 ** INDICATES 'b2' BAR PLACED IN TOP DECK ONLY.




HALF SECTION NEAR ABUTMENT

HALF SECTION NEAR PIER (FIXED PIER SHOWN)




INTERIOR BEAMS



EXTERIOR BEAMS

TYPICAL DECK AND HAUNCH DETAIL

* FOR DECK THICKNESS OVER BEAMS SEE HAUNCH AND CAMBER DETAILS ON DESIGN SHEET -----



DRAIN DETAILS


NOTE: DRAINS ARE TO BE GALVANIZED. ----- DRAINS REQUIRED. SEE "SITUATION PLAN" FOR LOCATION. WEIGHT OF DRAINS IS INCLUDED IN THE QUANTITY FOR "-----". WEIGHT IS BASED ON ROLLED TUBE.

DATA FOR ONE DRAIN	
BEAM SIZE	BTD
DRAIN WEIGHT (LBS.)	120
DRAIN LENGTH (FT.)	6'-2 3/4

NOTE: FOR DETAILS OF INTERMEDIATE DIAPHRAGMS SEE DESIGN SHEET -----

SUPERSTRUCTURE NOTES:

THE BRIDGE DECK AS SHOWN INCLUDES 1/2" INTEGRAL WEARING SURFACE.
 THE PIER AND ABUTMENT DIAPHRAGM CONCRETE IS TO BE PLACED MONOLITHICALLY WITH THE BRIDGE DECK.
 COST OF ALL PREFORMED EXPANSION JOINT FILLER MATERIAL IS TO BE INCLUDED IN THE PRICE BID FOR "STRUCTURAL CONCRETE (BRIDGE)".
 ALL BEAMS ARE TO BE SET VERTICAL.
 FORMS FOR THE BRIDGE DECK AND BARRIER RAIL ARE TO BE SUPPORTED BY THE PRESTRESSED CONCRETE BEAMS.
 CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR SHALL BE 2 INCHES UNLESS OTHERWISE NOTED OR SHOWN.
 ALL DECK AND DIAPHRAGM REINFORCING IS TO BE WIRED IN PLACE AND ADEQUATELY SUPPORTED BEFORE CONCRETE IS PLACED.
 TOP TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 2 1/2" CLEAR BELOW TOP OF DECK. BOTTOM TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 1" CLEAR ABOVE BOTTOM OF DECK.
 TOP AND BOTTOM REINFORCING STEEL IS TO BE SUPPORTED BY INDIVIDUAL BAR CHAIRS SPACED AT NOT MORE THAN 3'-0" CENTERS LONGITUDINALLY AND TRANSVERSELY, OR BY CONTINUOUS ROWS OF BAR HIGH CHAIRS OR DECK BOLSTERS SPACED 4'-0" APART. I.M. 451.01 REQUIREMENTS SHALL APPLY FOR BAR CHAIRS, BAR HIGH CHAIRS, AND DECK BOLSTERS.
 TRANSVERSE DECK REINFORCING MAY BE SPLICED WITH ONE LAP LOCATED AS FOLLOWS:
 TOP BAR - LAP MIDWAY BETWEEN BEAMS (MIN. LAP = 1'-10").
 BOTTOM BARS - LAP OVER BEAMS (MIN. LAP = 1'-10").
 PAYMENT FOR REINFORCING BARS SHALL BE BASED ON NO SPLICES, AND NO ALLOWANCE SHALL BE MADE FOR THE ADDITIONAL LENGTH OF BAR REQUIRED FOR THE USE OF SPLICES.



HALF SECTION NEAR PIER (EXPANSION PIER SHOWN)




NOTE: "STAINLESS STEEL" LEVEL OR "REBAR EPOXY A" LEVEL SHOULD BE ON OR OFF DEPENDING ON BARRIER RAIL STEEL EMBEDDED IN THE BRIDGE DECK.

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____

CORRECTION 04-14 - ADDED REFERRAL NOTE TO SUMMARY QUANTITIES SHEET FOR THE DRAIN WEIGHT. NOTE ABOUT CHOICE OF EPOXY OR STAINLESS STEEL DECK TO BARRIER RAIL BARS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 4561-BTE-5 - THIS SHEET ISSUED 07-08.

TABLE OF SIZE OF 'b2' BAR	
LONGEST ADJACENT SPAN	BTE BEAM BAR SIZE
30'-0	
35'-0	
40'-0	
45'-0	
50'-0	
55'-0	
60'-0	** 4
65'-0	** 5
70'-0	** 6
75'-0	** 6
80'-0	** 7
85'-0	** 7
90'-0	** 8
95'-0	** 8
100'-0	** 9
105'-0	** 9
110'-0	7
115'-0	7
120'-0	7
125'-0	8
130'-0	8
135'-0	8
140'-0	9
145'-0	9
150'-0	9
155'-0	9

THE MIDPOINT OF THE 'b2' BAR IS TO BE PLACED AT THE \bar{C} OF PIER.
 ** INDICATES 'b2' BAR PLACED IN TOP DECK ONLY.




DATA FOR ONE DRAIN	
BEAM SIZE	BTE
DRAIN WEIGHT (LBS.)	136
DRAIN LENGTH (FT.)	6'-11 3/4

NOTE: DRAINS ARE TO BE GALVANIZED. ----- DRAINS REQUIRED. SEE "SITUATION PLAN" FOR LOCATION. WEIGHT OF DRAINS IS INCLUDED IN THE QUANTITY FOR "-----". WEIGHT IS BASED ON ROLLED TUBE.

NOTE: FOR DETAILS OF INTERMEDIATE DIAPHRAGMS SEE DESIGN SHEET -----

SUPERSTRUCTURE NOTES:
 THE BRIDGE DECK AS SHOWN INCLUDES 1/2" INTEGRAL WEARING SURFACE.
 THE PIER AND ABUTMENT DIAPHRAGM CONCRETE IS TO BE PLACED MONOLITHICALLY WITH THE BRIDGE DECK.
 COST OF ALL PREFORMED EXPANSION JOINT FILLER MATERIAL IS TO BE INCLUDED IN THE PRICE BID FOR "STRUCTURAL CONCRETE (BRIDGE)".
 ALL BEAMS ARE TO BE SET VERTICAL.
 FORMS FOR THE BRIDGE DECK AND BARRIER RAIL ARE TO BE SUPPORTED BY THE PRESTRESSED CONCRETE BEAMS.
 CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR SHALL BE 2 INCHES UNLESS OTHERWISE NOTED OR SHOWN.
 ALL DECK AND DIAPHRAGM REINFORCING IS TO BE WIRED IN PLACE AND ADEQUATELY SUPPORTED BEFORE CONCRETE IS PLACED.
 TOP TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 2 1/2" CLEAR BELOW TOP OF DECK. BOTTOM TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 1" CLEAR ABOVE BOTTOM OF DECK.
 TOP AND BOTTOM REINFORCING STEEL IS TO BE SUPPORTED BY INDIVIDUAL BAR CHAIRS SPACED AT NOT MORE THAN 3'-0" CENTERS LONGITUDINALLY AND TRANSVERSELY, OR BY CONTINUOUS ROWS OF BAR HIGH CHAIRS OR DECK BOLSTERS SPACED 4'-0" APART. I.M. 451.01 REQUIREMENTS SHALL APPLY FOR BAR CHAIRS, BAR HIGH CHAIRS, AND DECK BOLSTERS.
 TRANSVERSE DECK REINFORCING MAY BE SPLICED WITH ONE LAP LOCATED AS FOLLOWS:
 TOP BAR - LAP MIDWAY BETWEEN BEAMS (MIN. LAP = 1'-10").
 BOTTOM BARS - LAP OVER BEAMS (MIN. LAP = 1'-10").
 PAYMENT FOR REINFORCING BARS SHALL BE BASED ON NO SPLICES, AND NO ALLOWANCE SHALL BE MADE FOR THE ADDITIONAL LENGTH OF BAR REQUIRED FOR THE USE OF SPLICES.





NOTE: "STAINLESS STEEL" LEVEL OR "REBAR EPOXY A" LEVEL SHOULD BE ON OR OFF DEPENDING ON BARRIER RAIL STEEL EMBEDDED IN THE BRIDGE DECK.
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____


CORRECTION 04-14 - ADDED REFERRAL NOTE TO SUMMARY QUANTITIES SHEET FOR THE DRAIN WEIGHT. NOTE ABOUT CHOICE OF EPOXY OR STAINLESS STEEL DECK TO BARRIER RAIL BARS. ENGLISHBTSTUBABUTMENTBRIDGES.DGN - 4561-BTE-6 - THIS SHEET ISSUED 07-08.

TABLE OF SIZE OF 'b2' BAR	
LONGEST ADJACENT SPAN	BTE BEAM BAR SIZE
30'-0	---
35'-0	---
40'-0	---
45'-0	---
50'-0	---
55'-0	---
60'-0	***4
65'-0	***5
70'-0	***6
75'-0	***6
80'-0	***7
85'-0	***7
90'-0	***8
95'-0	***8
100'-0	***9
105'-0	***9
110'-0	7
115'-0	7
120'-0	7
125'-0	8
130'-0	8
135'-0	8
140'-0	9
145'-0	9
150'-0	9
155'-0	9

THE MIDPOINT OF THE 'b2' BAR IS TO BE PLACED AT THE CL OF PIER.
 ** INDICATES 'b2' BAR PLACED IN TOP DECK ONLY.




INTERIOR BEAMS




EXTERIOR BEAMS

TYPICAL DECK AND HAUNCH DETAIL

* FOR DECK THICKNESS OVER BEAMS SEE HAUNCH AND CAMBER DETAILS ON DESIGN SHEET -----



HALF SECTION NEAR ABUTMENT



DRAIN DETAILS

NOTE: DRAIN WEIGHTS ARE INCLUDED ON THE SUMMARY QUANTITIES SHEET.
 NOTE: DRAINS ARE TO BE GALVANIZED. ----- DRAINS REQUIRED. SEE "SITUATION PLAN" FOR LOCATION. WEIGHT OF DRAINS IS INCLUDED IN THE QUANTITY FOR "-----". WEIGHT IS BASED ON ROLLED TUBE.

DATA FOR ONE DRAIN	
BEAM SIZE	BTE
DRAIN WEIGHT (LBS.)	136
DRAIN LENGTH (FT.)	6'-11 3/4


SLAB AREA = 29.22 SQ. FT.
 SLAB AREA DOES NOT INCLUDE THE HAUNCH.

NOTE: FOR DETAILS OF INTERMEDIATE DIAPHRAGMS SEE DESIGN SHEET -----

SUPERSTRUCTURE NOTES:

THE BRIDGE DECK AS SHOWN INCLUDES 1/2" INTEGRAL WEARING SURFACE.
 THE PIER AND ABUTMENT DIAPHRAGM CONCRETE IS TO BE PLACED MONOLITHICALLY WITH THE BRIDGE DECK.
 COST OF ALL PREFORMED EXPANSION JOINT FILLER MATERIAL IS TO BE INCLUDED IN THE PRICE BID FOR "STRUCTURAL CONCRETE (BRIDGE)". ALL BEAMS ARE TO BE SET VERTICAL.
 FORMS FOR THE BRIDGE DECK AND BARRIER RAIL ARE TO BE SUPPORTED BY THE PRESTRESSED CONCRETE BEAMS.
 CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR SHALL BE 2 INCHES UNLESS OTHERWISE NOTED OR SHOWN.
 ALL DECK AND DIAPHRAGM REINFORCING IS TO BE WIRED IN PLACE AND ADEQUATELY SUPPORTED BEFORE CONCRETE IS PLACED.
 TOP TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 2 1/2" CLEAR BELOW TOP OF DECK. BOTTOM TRANSVERSE REINFORCING STEEL IS TO BE PARALLEL TO AND 1" CLEAR ABOVE BOTTOM OF DECK. TOP AND BOTTOM REINFORCING STEEL IS TO BE SUPPORTED BY INDIVIDUAL BAR CHAIRS SPACED AT NOT MORE THAN 3'-0" CENTERS LONGITUDINALLY AND TRANSVERSELY, OR BY CONTINUOUS ROWS OF BAR HIGH CHAIRS OR DECK BOLSTERS SPACED 4'-0" APART. I.M. 451.01 REQUIREMENTS SHALL APPLY FOR BAR CHAIRS, BAR HIGH CHAIRS, AND DECK BOLSTERS.
 TRANSVERSE DECK REINFORCING MAY BE SPLICED WITH ONE LAP LOCATED AS FOLLOWS:
 TOP BAR - LAP MIDWAY BETWEEN BEAMS (MIN. LAP = 1'-10").
 BOTTOM BARS - LAP OVER BEAMS (MIN. LAP = 1'-10").
 PAYMENT FOR REINFORCING BARS SHALL BE BASED ON NO SPLICES, AND NO ALLOWANCE SHALL BE MADE FOR THE ADDITIONAL LENGTH OF BAR REQUIRED FOR THE USE OF SPLICES.

HALF SECTION NEAR PIER (FIXED PIER SHOWN)



HALF SECTION NEAR PIER (EXPANSION PIER SHOWN)

NOTE: "STAINLESS STEEL" LEVEL OR "REBAR EPOXY A" LEVEL SHOULD BE ON OR OFF DEPENDING ON BARRIER RAIL STEEL EMBEDDED IN THE BRIDGE DECK.

IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. _____ OF _____ FILE NO. _____ DESIGN NO. _____