

232_07
9/28/22

EROSION CONTROL (SALVAGE AND REMOVAL PROJECTS)

Following the completion of work in a disturbed area, place seed and fertilize the disturbed area as follows:

SEEDING:

3 lbs. of Tall Fescue (Fawn) per 1000 sq. ft.

FERTILIZER:

17 lbs. of 13-13-13 (or equivalent) commercial fertilizer per 1000 sq. ft.

ESTIMATED AREA: <<_____>> acres.

Preparing the seedbed and furnishing and applying seed and fertilizer is incidental to mobilization and will not be paid for separately.