

290_02
9/28/22

SMALL QUANTITY CONCRETE TESTING

- Test air and slump once per 30 cy placed, or minimum of once per day.
- Verification gradations will not be required for this project. However, the Contractor will be expected to provide certified plant inspection.
- The Contractor has the option of using the following minimum opening times in lieu of flexural testing:
 - 48 hours for pedestrian traffic
 - 72 hours for curb and gutter or patching