



TYPICAL SECTION




4'-0" x 9'-0" x 28'-0" FOR 19D, 20D & 21C




4'-0" x 10'-0" x 30'-0" FOR 20F, 21E & 22A

H IN FT.	CL ABUT. BRG.	CL PIERING BRG.	DES. BRG. (TONS)	FOOTING SIZE
201'-4	19D	49		
213'-10	20D	48		4' x 9' x 28'
226'-4	20D	50		
243'-0	21C	50		
201'-4	20E	47		
213'-10	20E	48		4' x 9' x 30'
226'-4	20E	50		
243'-0	21D	50		
201'-4	20F	48		
213'-10	20F	49		4' x 10' x 30'
226'-4	21E	49		
243'-0	22A	48		
201'-4	20G	49		
213'-10	20G	50		4' x 10' x 31'
226'-4	21F	50		
243'-0	22B	50		
201'-4	20G	50		
213'-10	21F	50		4' x 10' x 31'
226'-4	22B	49		
243'-0	22B	50		




4'-0" x 9'-0" x 30'-0" FOR 20E & 21D




4'-0" x 10'-0" x 31'-0" FOR 20G, 21F & 22B

FOOTING SIZE	REINFORCING STEEL (ONE FOOTING)				TOTAL WEIGHT (LB.)	STRUCTURAL CONCRETE (CY)
	BAR	NO., SIZE & SPACING	LENGTH	WEIGHT (LB.)		
4' x 9' x 28'	d2	50 - #10 AS SHOWN	10'-6	2259	4580	37.3
	f1	28 - #5 @ 1'-0	8'-8	253		
	f2	9 - #5 @ 1'-0	27'-8	260		
	g1	33 - #7 AS SHOWN	8'-8	585		
	g2	13 - #9 @ 0'-8	27'-8	1223		
	d2	50 - #10 AS SHOWN	10'-6	2259		
4' x 9' x 30'	f1	30 - #5 @ 1'-0	8'-8	271	5088	40.0
	g1	9 - #5 @ 1'-0	29'-8	278		
	f2	35 - #7 AS SHOWN	8'-8	620		
	g2	13 - #10 @ 0'-8	29'-8	1660		
	d2	50 - #10 AS SHOWN	10'-6	2259		
	f1	30 - #5 @ 1'-0	9'-8	302		
4' x 10' x 30'	f2	10 - #5 @ 1'-0	29'-8	309	5280	44.4
	g1	34 - #8 AS SHOWN	9'-8	878		
	g2	12 - #10 @ 0'-10	29'-8	1532		
	d2	50 - #10 AS SHOWN	10'-6	2259		
	f1	31 - #5 @ 1'-0	9'-8	313		
	f2	10 - #5 @ 1'-0	30'-8	320		
4' x 10' x 31'	g1	35 - #8 AS SHOWN	9'-8	903	5379	45.9
	g2	12 - #10 @ 0'-10	30'-8	1584		




d2
NOTE: D = PIN DIAMETER.
DIMENSIONS ARE OUT TO OUT.



d2 BAR LAYOUT
(SEE SECTION A-A ON SHEET H44-56-07.)

NOTE:
SEE SHEET H44-58-07 FOR FOOTING NOTES.

LATEST REVISION DATE	 APPROVED BY BRIDGE ENGINEER	 Iowa Department of Transportation Highway Division	STANDARD DESIGN - 44' ROADWAY, THREE SPAN BRIDGE
			PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES
			HL93 SUPERSTRUCTURE MARCH, 2007 HS25 SUBSTRUCTURE
			TEE PIER - STEEL PILE FOOTINGS, H=25' TO 40' 30° SKEW
			H44-59-07