


REVISED 12-07 - OPEN RAIL REINFORCING QUANTITY CHANGED

BILL OF REINFORCING STEEL FOR SUPERSTRUCTURE - 130' BRIDGE																		
LOCATION	SKEW	SHAPE	0°				15°				30°				45°			
			BAR	NO.	LENGTH	WEIGHT	BAR	NO.	LENGTH	WEIGHT	BAR	NO.	LENGTH	WEIGHT	BAR	NO.	LENGTH	WEIGHT
SLAB LONGITUDINAL BOTTOM			9a1	39	29'-10	3956	39	29'-10	3956	39	29'-10	3956	39	29'-10	3956	39	29'-10	3956
SLAB LONGITUDINAL BOTTOM			9a2	39	44'-6	5901	39	44'-6	5901	39	44'-6	5901	39	44'-6	5901	39	44'-6	5901
SLAB LONGITUDINAL BOTTOM			9a3	39	41'-3	5470	39	41'-3	5470	39	41'-3	5470	39	41'-3	5470	39	41'-3	5470
SLAB LONGITUDINAL BOTTOM			9a4	40	33'-10	4601	40	33'-10	4601	40	33'-10	4601	40	33'-10	4601	40	33'-10	4601
SLAB LONGITUDINAL BOTTOM			10a5	20	41'-0	3528	20	41'-0	3528	20	41'-0	3528	20	41'-0	3528	20	41'-0	3528
SLAB LONGITUDINAL BOTTOM, AT RAIL			9a6	8	39'-8	1079	8	39'-8	1079	8	39'-8	1079	8	39'-8	1079	8	39'-8	1079
SLAB LONGITUDINAL BOTTOM, AT RAIL			9a7	8	13'-0	354	8	13'-0	354	8	13'-0	354	8	13'-0	354	8	13'-0	354
SLAB LONGITUDINAL BOTTOM, AT RAIL			9a8	4	48'-8	662	4	48'-8	662	4	48'-8	662	4	48'-8	662	4	48'-8	662
SLAB LONGITUDINAL BOTTOM, AT RAIL			8a9	8	32'-4	691	8	32'-4	691	8	32'-4	691	8	32'-4	691	8	32'-4	691
SLAB LONGITUDINAL BOTTOM, AT RAIL			9a10	4	29'-0	394	4	29'-0	394	4	29'-0	394	4	29'-0	394	4	29'-0	394
SLAB LONGITUDINAL TOP			6b1	39	6'-7	386	39	6'-7	386	39	6'-7	386	39	6'-7	386	39	6'-7	386
SLAB LONGITUDINAL TOP			11b2	39	28'-9	5957	39	28'-9	5957	39	28'-9	5957	39	28'-9	5957	39	28'-9	5957
SLAB LONGITUDINAL TOP			11b3	39	30'-6	6320	39	30'-6	6320	39	30'-6	6320	39	30'-6	6320	39	30'-6	6320
SLAB LONGITUDINAL TOP			7b4	39	22'-7	1800	39	22'-7	1800	39	22'-7	1800	39	22'-7	1800	39	22'-7	1800
SLAB LONGITUDINAL TOP			10b5	40	25'-6	4389	40	25'-6	4389	40	25'-6	4389	40	25'-6	4389	40	25'-6	4389
SLAB LONGITUDINAL TOP			6b6	20	34'-4	1031	20	34'-4	1031	20	34'-4	1031	20	34'-4	1031	20	34'-4	1031
SLAB LONGITUDINAL TOP, AT RAIL			6b8	8	29'-1	349	8	29'-1	349	8	29'-1	349	8	29'-1	349	8	29'-1	349
SLAB LONGITUDINAL TOP, AT RAIL			11b9	8	32'-9	1392	8	32'-9	1392	8	32'-9	1392	8	32'-9	1392	8	32'-9	1392
SLAB LONGITUDINAL TOP, AT RAIL			6b10	4	23'-0	138	4	23'-0	138	4	23'-0	138	4	23'-0	138	4	23'-0	138
SLAB LONGITUDINAL TOP, AT RAIL			7b11	8	34'-4	561	8	34'-4	561	8	34'-4	561	8	34'-4	561	8	34'-4	561
SLAB LONGITUDINAL TOP, AT RAIL			11b12	8	23'-9	1009	8	23'-9	1009	8	23'-9	1009	8	23'-9	1009	8	23'-9	1009
SLAB TRANSVERSE, BOTTOM			6c1	127	32'-10	6263	127	34'-0	6486	116	32'-10	5721	104	32'-10	5129			
SLAB TRANSVERSE ENDS, BOTTOM			6c2	-	-	-	-	-	-	28	VARIES	800	52	VARIES	1426			
SLAB TRANSVERSE, TOP			5d1	127	32'-10	4349	127	34'-0	4504	116	32'-10	3972	104	32'-10	3561			
SLAB TRANSVERSE ENDS, TOP			5d2	-	-	-	-	-	-	28	VARIES	555	52	VARIES	990			
SLAB, TRANSVERSE AT ABUTMENT			8e1	20	32'-10	1753	-	-	-	-	-	-	-	-	-			
SLAB, TRANSVERSE AT ABUTMENT			8e2	-	-	-	20	33'-11	1811	20	37'-6	2003	20	45'-4	2421			
SLAB, HAIRPINS, AT ABUTMENT			6e3	72	6'-10	739	72	6'-11	748	72	7'-3	784	72	7'-11	856			
PIER CAP HOOPS			5h1	40	8'-1	337	40	8'-1	337	60	8'-1	506	60	8'-1	506			
PIER CAP ENDS			8h2	4	14'-5	154	4	14'-5	154	4	14'-5	154	4	14'-5	154			
PIER CAP, BOTTOM LONGITUDINAL			8h3	8	29'-10	637	8	30'-11	660	8	34'-5	735	8	42'-2	901			
PIER CAP, TOP LONGITUDINAL			8h4	4	32'-10	351	4	34'-0	363	4	37'-11	405	4	46'-6	497			
TOP OF SLAB, TRANSVERSE, AT RAIL			5j1	252	8'-6	2234	252	8'-6	2234	252	8'-6	2234	250	8'-6	2216			
WING, VERTICAL			5m1-4	32	SHOWN	117	32	SHOWN	117	32	SHOWN	117	32	SHOWN	117			
WING, HORIZONTAL			5n1	24	6'-8	167	24	6'-8	167	24	6'-8	167	24	6'-8	167			
PAVING SUPPORT, TRANSVERSE			5p1	30	8'-10	276	32	8'-10	295	34	8'-10	313	42	8'-10	387			
PAVING SUPPORT LONGITUDINAL			5p3	6	30'-2	189	6	31'-3	196	6	34'-10	218	6	42'-7	266			
SUB TOTAL - LBS.						67,534				68,040		68,652			69,562			
BARRIER RAIL - SEE LIST ON RAIL SHEET J30-41-06						7746				7746		7746			7746			
OPEN RAIL - SEE LIST ON RAIL SHEET J30-44-06						8150				8150		8150			8150			
TOTAL - LBS.						75,280				75,786		76,398			77,308			
						75,684				76,190		76,802			77,712			
TOTAL - LBS.						73,801				74,272		74,598			75,250			
SAME AS ABOVE EXCEPT ALL "H" BARS DELETED						74,205				74,676		75,002			75,654			

ESTIMATED QUANTITIES FOR SUPERSTRUCTURE - 130' BRIDGE									
ITEM	SKEW	WITH MONOLITHIC PIER CAP				WITH NON-MONOLITHIC PIER CAP			
		0°	15°	30°	45°	0°	15°	30°	45°
WITH BARRIER RAIL	*STRUCTURAL CONCRETE (BRIDGE) C.Y.	314.8	315.8	319.2	326.6	309.9	310.7	313.6	319.7
CONCRETE BARRIER OR OPEN RAIL	REINFORCING STEEL EPOXY COATED LBS.	75,280	75,786	76,398	77,308	73,801	74,272	74,598	75,250
	LIN. FT.	282.0	282.2	282.9	284.5	282.0	282.2	282.9	284.5
WITH OPEN RAIL	*STRUCTURAL CONCRETE (BRIDGE) C.Y.	314.6	315.6	319.0	326.3	309.6	310.5	313.3	319.5
	REINFORCING STEEL EPOXY COATED LBS.	75,684	76,190	76,802	77,712	74,205	74,676	75,002	75,654
* INCLUDES 4 WINGS @ 0.71 C.Y. EACH; EXCLUDES RAIL CONCRETE.									



12-07 LATEST REVISION DATE	 APPROVED BY BRIDGE ENGINEER	 STANDARD DESIGN - 30' ROADWAY, 3 SPAN BRIDGES CONTINUOUS CONCRETE SLAB BRIDGES NOVEMBER, 2006	
		SUPERSTRUCTURE DETAILS 130'-0 BRIDGE	J30-15E-06
		EPOXY COATED REINFORCING	