


REVISED 12-07 - OPEN RAIL REINFORCING QUANTITY CHANGED

BILL OF REINFORCING STEEL FOR SUPERSTRUCTURE - 100' BRIDGE																			
LOCATION	SKEW	SHAPE	0°				15°				30°				45°				
			BAR	NO.	LENGTH	WEIGHT	BAR	NO.	LENGTH	WEIGHT	BAR	NO.	LENGTH	WEIGHT	BAR	NO.	LENGTH	WEIGHT	
SLAB LONGITUDINAL BOTTOM			8a1	39	23'-4	2430	39	23'-4	2430	39	23'-4	2430	39	23'-4	2430	39	23'-4	2430	
SLAB LONGITUDINAL BOTTOM			8a2	39	33'-6	3488	39	33'-6	3488	39	33'-6	3488	39	33'-6	3488	39	33'-6	3488	
SLAB LONGITUDINAL BOTTOM			8a3	39	31'-6	3280	39	31'-6	3280	39	31'-6	3280	39	31'-6	3280	39	31'-6	3280	
SLAB LONGITUDINAL BOTTOM			9a4	40	29'-10	4057	40	29'-10	4057	40	29'-10	4057	40	29'-10	4057	40	29'-10	4057	
SLAB LONGITUDINAL BOTTOM			9a5	20	32'-0	2176	20	32'-0	2176	20	32'-0	2176	20	32'-0	2176	20	32'-0	2176	
SLAB LONGITUDINAL BOTTOM, AT RAIL			8a6	8	36'-10	787	8	36'-10	787	8	36'-10	787	8	36'-10	787	8	36'-10	787	
SLAB LONGITUDINAL BOTTOM, AT RAIL			8a7	4	37'-4	399	4	37'-4	399	4	37'-4	399	4	37'-4	399	4	37'-4	399	
SLAB LONGITUDINAL BOTTOM, AT RAIL			8a8	8	26'-1	557	8	26'-1	557	8	26'-1	557	8	26'-1	557	8	26'-1	557	
SLAB LONGITUDINAL BOTTOM, AT RAIL			8a9	4	22'-6	240	4	22'-6	240	4	22'-6	240	4	22'-6	240	4	22'-6	240	
SLAB LONGITUDINAL TOP			6b1	39	5'-10	342	39	5'-10	342	39	5'-10	342	39	5'-10	342	39	5'-10	342	
SLAB LONGITUDINAL TOP			10b2	39	26'-9	4489	39	26'-9	4489	39	26'-9	4489	39	26'-9	4489	39	26'-9	4489	
SLAB LONGITUDINAL TOP			10b3	39	27'-6	4615	39	27'-6	4615	39	27'-6	4615	39	27'-6	4615	39	27'-6	4615	
SLAB LONGITUDINAL TOP			7b4	39	15'-4	1222	39	15'-4	1222	39	15'-4	1222	39	15'-4	1222	39	15'-4	1222	
SLAB LONGITUDINAL TOP			6b5	40	12'-7	756	40	12'-7	756	40	12'-7	756	40	12'-7	756	40	12'-7	756	
SLAB LONGITUDINAL TOP			9b6	40	22'-9	3094	40	22'-9	3094	40	22'-9	3094	40	22'-9	3094	40	22'-9	3094	
SLAB LONGITUDINAL TOP			6b7	20	26'-10	806	20	26'-10	806	20	26'-10	806	20	26'-10	806	20	26'-10	806	
SLAB LONGITUDINAL TOP, AT RAIL			6b8	8	24'-4	292	8	24'-4	292	8	24'-4	292	8	24'-4	292	8	24'-4	292	
SLAB LONGITUDINAL TOP, AT RAIL			9b9	8	23'-6	639	8	23'-6	639	8	23'-6	639	8	23'-6	639	8	23'-6	639	
SLAB LONGITUDINAL TOP, AT RAIL			6b10	4	21'-0	126	4	21'-0	126	4	21'-0	126	4	21'-0	126	4	21'-0	126	
SLAB LONGITUDINAL TOP, AT RAIL			6b11	8	26'-4	316	8	26'-4	316	8	26'-4	316	8	26'-4	316	8	26'-4	316	
SLAB LONGITUDINAL TOP, AT RAIL			10b12	8	19'-0	654	8	19'-0	654	8	19'-0	654	8	19'-0	654	8	19'-0	654	
SLAB TRANSVERSE, BOTTOM			6c1	97	32'-10	4784	97	34'-0	4954	86	32'-10	4241	74	32'-10	3649				
SLAB TRANSVERSE ENDS, BOTTOM			6c2	-	-	-	-	-	-	28	VARIES	800	52	VARIES	1426				
SLAB TRANSVERSE, TOP			5d1	97	32'-10	3322	97	34'-0	3440	86	32'-10	2945	74	32'-10	2534				
SLAB TRANSVERSE ENDS, TOP			5d2	-	-	-	-	-	-	28	VARIES	555	52	VARIES	990				
SLAB, TRANSVERSE AT ABUTMENT			8e1	20	32'-10	1753	-	-	-	-	-	-	-	-	-				
SLAB, TRANSVERSE AT ABUTMENT			8e2	-	-	-	20	33'-11	1811	20	37'-6	2003	20	45'-4	2421				
SLAB, HAIRPINS, AT ABUTMENT			6e3	72	6'-10	739	72	6'-11	748	72	7'-3	784	72	7'-11	856				
PIER CAP HOOPS			5h1	56	7'-5	433	56	7'-5	433	56	7'-5	433	70	7'-5	541				
PIER CAP ENDS			8h2	4	14'-5	154	4	14'-5	154	4	14'-5	154	4	14'-5	154				
PIER CAP, BOTTOM LONGITUDINAL			8h3	8	29'-10	637	8	30'-11	660	8	34'-5	735	8	42'-2	901				
PIER CAP, TOP LONGITUDINAL			8h4	4	32'-10	351	4	34'-0	363	4	37'-11	405	4	46'-6	497				
TOP OF SLAB, TRANSVERSE, AT RAIL			5j1	192	8'-6	1702	192	8'-6	1702	192	8'-6	1702	190	8'-6	1684				
WING, VERTICAL			5m1-4	32	SHOWN	117	32	SHOWN	117	32	SHOWN	117	32	SHOWN	117				
WING, HORIZONTAL			5n1	24	6'-8	167	24	6'-8	167	24	6'-8	167	24	6'-8	167				
PAVING SUPPORT, TRANSVERSE			5p1	30	8'-10	276	32	8'-10	295	34	8'-10	313	42	8'-10	387				
PAVING SUPPORT LONGITUDINAL			5p3	6	30'-2	189	6	31'-3	196	6	34'-6	218	6	42'-7	266				
SUB TOTAL - LBS.						49,389					49,805					50,337			51,355
BARRIER RAIL - SEE LIST ON RAIL SHEET J30-41-06						6153					6153					6153			6153
OPEN RAIL - SEE LIST ON RAIL SHEET J30-44-06						6371					6371					6371			6371
TOTAL - LBS.			WITH MONOLITHIC PIER CAP			55,542	WITH BARRIER RAIL			55,958	WITH OPEN RAIL			56,490				57,508	
						55,760				56,176				56,708				57,726	
TOTAL - LBS.			WITH NON-MONOLITHIC PIER CAP			53,967	WITH BARRIER RAIL			54,348	WITH OPEN RAIL			54,763				55,415	
SAME AS ABOVE EXCEPT ALL "H" BARS DELETED						54,185				54,566				54,981				55,633	

ESTIMATED QUANTITIES FOR SUPERSTRUCTURE - 100' BRIDGE											
ITEM	SKEW	WITH MONOLITHIC PIER CAP				WITH NON-MONOLITHIC PIER CAP					
		0°	15°	30°	45°	0°	15°	30°	45°		
WITH *STRUCTURAL CONCRETE (BRIDGE) C.Y.		212.3	213.3	216.8	224.5	207.3	208.2	211.2	217.6		
BARRIER RAIL REINFORCING STEEL EPOXY COATED LBS.		55,542	55,958	56,490	57,508	53,967	54,348	54,763	55,415		
CONCRETE BARRIER OR OPEN RAIL LIN. FT.		222.0	222.2	222.9	224.5	222.0	222.2	222.9	224.5		
WITH *STRUCTURAL CONCRETE (BRIDGE) C.Y.		212.1	213.1	216.6	224.3	207.1	208.0	211.0	217.5		
OPEN RAIL REINFORCING STEEL EPOXY COATED LBS.		55,760	56,176	56,708	57,726	54,185	54,566	54,981	55,633		
* INCLUDES 4 WINGS @ 0.71 C.Y. EACH; EXCLUDES RAIL CONCRETE.											



12-07 LATEST REVISION DATE	APPROVED BY BRIDGE ENGINEER	 Iowa Department of Transportation Highway Division	
		STANDARD DESIGN - 30' ROADWAY, 3 SPAN BRIDGES CONTINUOUS CONCRETE SLAB BRIDGES NOVEMBER, 2006	
		SUPERSTRUCTURE DETAILS 100'-0 BRIDGE EPOXY COATED REINFORCING	J30-09E-06