Iowa Department of Transportation

Project Development Division

TRIPLE REINFORCED CONCRETE BOX CULVERT STANDARDS

GENERAL NOTES :

1. THE RCB CULVERT SECTIONS ARE DESIGNED FOR MS18 LIVE LOAD AND EARTH FILLS OF VARYING HEIGHTS.
2. THE MAXIMUM SERVICE LOAD STRESS (MPa) IN THE REINFORCING STEEL FOR CRACK CONTROL SHALL BE:

$$fsa = 29\,800 / \sqrt[3]{dcA}$$

dc AND A ARE IN mm AND mm² RESPECTIVELY

3. METAL BAR CHAIRS SPACED AT NOT OVER 900 mm C-C IN EITHER DIRECTION ARE TO BE USED TO SUPPORT ALL SLAB AND FLOOR STEEL AS OUTLINED IN THE STANDARD SPECIFICATIONS (ARTICLE 2404.07).
4. THE CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR EDGE OR END OF REINFORCING BAR TO BE 50 mm UNLESS OTHERWISE NOTED.
5. LONGITUDINAL REINFORCING IS NOT TO EXTEND THRU THE CONSTRUCTION JOINTS, EXCEPT FOR rl DOWEL BARS IN SLAB.
6. ALL REINFORCING STEEL IS TO BE SECURELY WIRED IN PLACE BEFORE THE CONCRETE IS POURED (ARTICLE 2404.06).
7. FLOOR OF BARREL IS TO BE FINISHED SMOOTH. SIDES OF FOOTING ARE TO BE FORMED TO INSURE CORRECT LINE AND GRADE.
8. ALL EXPOSED CORNERS 90° OR SHARPER TO BE FILLETED WITH A 20 mm DRESSED AND BEVELED STRIP.
9. THE PERMISSIBLE CONSTRUCTION JOINT AT THE TOP OF THE WALLS MAY BE LOWERED AT THE CONTRACTOR'S OPTION WITH ENGINEERS APPROVAL.
10. THE REINFORCEMENT SUPPLIED FOR THIS STRUCTURE SHALL BE GRADE 400 REINFORCEMENT IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS. THE DESIGN STRESSES ARE BASED ON 400 GRADE REINFORCEMENT.
11. THE VERTICAL BARS IN THE WALLS MAY BE SPLICED ABOVE THE FOOTING AT THE CONTRACTOR'S OPTION AS FOLLOWS:

BAR SIZE NUMBER	15	20	25	30
MINIMUM SPLICE LENGTH	640 mm	790 mm	1320 mm	1850 mm

THIS SPLICE, IF USED, WILL BE AT THE CONTRACTOR'S EXPENSE.

12. REBAR CLEARANCES WILL BE AS FOLLOWS:

VERTICAL, TOP	50 mm	
VERTICAL, BOTTOM	90 mm	OR 75 mm IF THE OVERALL HEIGHT OF THE CULVERT IS NOT IN 10 mm INCREMENTS
TRANSVERSE	50 mm	
EDGE CLEARANCE	50 mm	EXCEPT, TOP OF FLOOR 60 mm TO NEAR TRANSVERSE REINF. BAR OR BOTTOM OF FLOOR 90 mm TO NEAR TRANSVERSE REINF. BAR.

13. ALL CONSTRUCTION JOINTS SHALL BE FORMED WITH A BEVELED KEYWAY EXCEPT AT BELL JOINTS.

ALL BEVELED KEYWAYS SHALL BE CENTERED.

KEYWAY SIZE SHALL BE 50 mm x 100 mm EXCEPT AS FOLLOWS :
KEYWAY BETWEEN THE FLOOR AND WALL SHALL BE 50 mm x 150 mm WHEN THE WALL IS GREATER THAN 255 mm WIDE.

14. IF 0 mm OF FILL IS SPECIFIED, DETAILS FOR PAVING NOTCH AND REFERENCE TO EPOXY COATING OF SLAB REINFORCING STEEL, IF APPLICABLE, SHALL BE INCLUDED IN THE FINAL PLANS.
15. ALL DIMENSIONS ARE IN MILLIMETERS (mm) UNLESS OTHERWISE NOTED OR SHOWN.

SPECIFICATIONS :

DESIGN: AASHTO SERIES OF 1992, EXCEPT AS MODIFIED IN GENERAL NOTES 2 ABOVE.
CONSTRUCTION: STANDARD SPECIFICATIONS OF THE IOWA DEPARTMENT OF TRANSPORTATION SPECIFICATION, CURRENT SERIES, PLUS CURRENT SUPPLEMENTAL SPECIFICATIONS AND SPECIAL PROVISIONS.

DESIGN STRESSES :

DESIGN STRESSES FOR THE FOLLOWING MATERIALS ARE IN ACCORDANCE WITH THE AASHTO STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES, SERIES OF 1992.
REINFORCING STEEL IN ACCORDANCE WITH SECTION 8, GRADE 400.
CONCRETE IN ACCORDANCE WITH SECTION 8, f'c = 24 MPa.

INDEX FOR CULVERT STANDARD

MTRRCB 3000-2400-94	CULVERT BARREL DETAILS VARIABLE DIMENSIONS AND QUANTITIES TABLE
MTRRCB 3000-3000-94	CULVERT BARREL DETAILS VARIABLE DIMENSIONS AND QUANTITIES TABLE
MTRRCB 3000-3600-94	CULVERT BARREL DETAILS VARIABLE DIMENSIONS AND QUANTITIES TABLE
MTRRCB 3600-1800-94	CULVERT BARREL DETAILS VARIABLE DIMENSIONS AND QUANTITIES TABLE
MTRRCB 3600-2400-94	CULVERT BARREL DETAILS VARIABLE DIMENSIONS AND QUANTITIES TABLE
MTRRCB 3600-3000-94	CULVERT BARREL DETAILS VARIABLE DIMENSIONS AND QUANTITIES TABLE
MTRRCB 3600-3600-94	CULVERT BARREL DETAILS VARIABLE DIMENSIONS AND QUANTITIES TABLE
MTRRCB 2-94	CULVERT BARREL DETAILS - PLAN
MTRH 0-1-94	DIMENSION TABLE
MTRH 0-2-94	PLAN VIEW - APRON REINFORCING, TOP AND BOTTOM
MTRH 0-3-94	TYPICAL SECTION - NEAR CENTER OF APRON, CURTAIN WALL PLAN AND SECTION AND DETAILS
MTRH 0-4-94	TYPICAL VIEW - FRONT AND BACK FACE REINFORCING, WINGWALLS, CENTER WALL
MTRH 0-5-94	BENT BAR DETAILS AND BILL OF REINFORCING FOR ONE HEADWALL 0° SKEW, 3000 mm AND 3600 mm SPANS
MTRH 15-1-94	DIMENSION TABLE
MTRH 15-2-94	PLAN VIEW - APRON REINFORCING, TOP AND BOTTOM
MTRH 15-3-94	TYPICAL SECTION - NEAR CENTER OF APRON, CURTAIN WALL PLAN AND SECTION AND DETAILS
MTRH 15-4-94	TYPICAL VIEW - FRONT AND BACK FACE REINFORCING, WINGWALLS, CENTER WALL
MTRH 15-5-94	BENT BAR DETAILS AND BILL OF REINFORCING FOR ONE HEADWALL 15° SKEW, 3000 mm AND 3600 mm SPANS
MTRH 30-1-94	DIMENSION TABLE
MTRH 30-2-94	PLAN VIEW - APRON REINFORCING, TOP AND BOTTOM
MTRH 30-3-94	TYPICAL SECTION - NEAR CENTER OF APRON, CURTAIN WALL PLAN AND SECTION AND DETAILS
MTRH 30-4-94	TYPICAL VIEW - FRONT AND BACK FACE REINFORCING, WINGWALLS, CENTER WALL
MTRH 30-5-94	BENT BAR DETAILS AND BILL OF REINFORCING FOR ONE HEADWALL 30° SKEW, 3000 mm AND 3600 mm SPANS
MTRH 45-1-94	DIMENSION TABLE
MTRH 45-2-94	PLAN VIEW - TOP APRON REINFORCING
MTRH 45-3-94	PLAN VIEW - BOTTOM APRON REINFORCING
MTRH 45-4-94	TYPICAL SECTION - NEAR CENTER OF APRON, CURTAIN WALL PLAN AND SECTION AND DETAILS
MTRH 45-5-94	TYPICAL VIEW - FRONT AND BACK FACE REINFORCING, WINGWALLS, CENTER WALL
MTRH 45-6-94	BENT BAR DETAILS AND BILL OF REINFORCING FOR ONE HEADWALL 45° SKEW, 3000 mm AND 3600 mm SPANS
MTRCBJ 1-94	CULVERT BELL JOINT DETAILS AND ESTIMATE OF QUANTITIES TABLE - 3000 mm SPAN
MTRCBJ 2-94	CULVERT BELL JOINT DETAILS AND ESTIMATE OF QUANTITIES TABLE - 3600 mm SPAN
MTRCBJ 3-94	PERMISSIBLE CULVERT BELL JOINT DETAILS

LATEST REVISION DATE : 04-02

APPROVED BY : William A. Stanbrough

STANDARD DESIGN

GENERAL INFORMATION

FOR

TRIPLE REINFORCED CONCRETE BOX CULVERTS

PROJECT DEVELOPMENT DIVISION

IOWA DEPARTMENT OF TRANSPORTATION

DECEMBER, 1994

MTRRCB-GI-94

REVISED 04-02 - ADDED MTRCBJ 3-94 STANDARD SHEET. GENERAL NOTE 12 CHANGED THE BOTTOM VERTICAL CLEARANCE TO 90 mm.
TRCBGIM.SOI

REVISED : 12/96 ; GENERAL NOTE #13 CHANGED.

XXXXXXXXXXSYSTEMTIME XXXXXXXUSERNAME XXXXXXXXXX