

CHAPTER 9 PORTLAND CEMENT CONCRETE (PCC) PAVEMENT

9.00	GENERAL	9-1
9.01	PRE-CONCRETING CONFERENCE	9-1
9.02	"PCC PLANT PAGE" (FORMS 800240E AND 800240M)	9-1
9.03	USE OF COMMERCIAL READY MIX CONCRETE ON PAVING PROJECTS	9-1
9.04	CONCRETE DELIVERY TIMES	9-2
9.10	EQUIPMENT	9-3
9.11	TEMPLATE FOR CHECKING GRADES ON DRIVES ON URBAN PAVING PROJECTS	9-3
9.12	OPERATION OF EQUIPMENT ON GRANULAR SUBBASE	9-3
9.13	ACCUMULATION OF MATERIALS IN TRANSPORTING VEHICLES	9-4
9.14	PCC FINISHING MACHINES	9-4
9.15	OPERATING FINISHING EQUIPMENT ON PREVIOUSLY PLACED CONCRETE IN MULTIPLE-LANE CONSTRUCTION WORK	9-4
	Protection of Pavement	9-4
	Surface Cleaning	9-5
	Other Equipment	9-5
9.16	EQUIPMENT WEIGHT LIMITATIONS ON NEW PAVEMENTS & PCC OVERLAYS	9-5
	Joint Cleaning & Sealing Equipment Used on New Pavement & Unbonded PCC Overlays	9-5
	Sawing Equipment Used on Bonded PCC Overlays	9-5
	Joint Cleaning and Sealing Equipment Used on Bonded PCC Overlays	9-5
9.20	PAVEMENT JOINTS	9-6
9.21	JOINT SAWING	9-6
9.22	CLEANING JOINTS	9-6
9.23	SEALING SAWED JOINTS	9-6
	Joint Filling	9-6
	Sealing Equipment	9-7
	Backer Rod	9-7
9.24	RESERVED FOR FUTURE USE	9-7
9.25	CD, ED, EE & EF JOINTS, AND OTHER DOWELED SUPPORT ASSEMBLIES	9-7
	Expansion Joints	9-7

	Bond Breakers -----	9-7
	Dowel Tolerances -----	9-8
	Dowel Assembly Placement -----	9-8
	Marking Joint Locations -----	9-9
	Blanking Bands -----	9-9
9.26	LONGITUDINAL JOINTS DESIGN -----	9-9
	Tie Bar Placement -----	9-10
9.27	LONGITUDINAL JOINT (L JOINT) TIE-STEEL INSPECTION -----	9-10
	Procedure -----	9-10
	Frequency -----	9-11
	Documentation -----	9-11
	Tolerance -----	9-11
	Out-of-Tolerance -----	9-11
	Retrofit -----	9-12
	Price Adjustments -----	9-12
9.30	INTAKES AND UTILITY ACCESSES -----	9-13
9.31	INTAKE CONSTRUCTION ON PAVING JOBS -----	9-13
9.32	BOX-OUTS FOR UTILITY ACCESSES -----	9-13
9.33	BOX-OUTS FOR SLIPFORM PAVING -----	9-13
9.40	SURFACE FINISHING -----	9-14
9.41	USE OF WATER IN FINISHING CONCRETE -----	9-14
9.42	MICROTEXTURE AND MACROTEXTURE -----	9-14
9.43	GROOVE DEPTH DETERMINATION -----	9-16
9.44	PAVEMENT CROWN -----	9-17
9.45	STRAIGHTEDGEING PAVEMENT SURFACE -----	9-17
9.46	PAVEMENT DATE AND STATION STAMPING -----	9-17
9.50	PROTECTION, CURING, AND REPAIR -----	9-18
9.51	PREVENTION OF RAIN DAMAGE TO PLASTIC CONCRETE -----	9-18
9.52	CURING OF KEYED AND DOWELED JOINTS -----	9-18
9.53	REPAIR OF DEFICIENT PAVEMENT -----	9-18
	Recommended Repair Method -----	9-19
9.54	MUD BALL REPAIR -----	9-20
9.55	COLD WEATHER PAVING AND PLANT OPERATIONS -----	9-21
	Cold Weather Pavement Protection -----	9-21

	Cold Weather Plant Operation -----	9-22
9.56	CURING -----	9-22
9.60	CONCRETE MATERIALS ISSUES -----	9-23
9.61	CONCRETE SAMPLING LOCATIONS-----	9-23
9.62	TESTING PROCEDURES -----	9-23
9.63	AIR ENTRAINMENT IN PLASTIC CONCRETE-----	9-23
	Aggregate Correction Factor -----	9-23
	Control of Air Content -----	9-24
	Verification -----	9-24
	Air Content Outside Tolerance-----	9-24
	Air Content More Than 0.5% Below Lower Target Content -----	9-24
	Price Adjustment -----	9-25
9.64	CONCRETE VIBRATION AND CONSOLIDATION -----	9-25
9.65	PAVEMENT THICKNESS CORES -----	9-26
9.66	PAVEMENT SMOOTHNESS-----	9-26
9.67	QUALITY MANAGEMENT CONCRETE (QM-C) -----	9-26
	Measurement and Payment -----	9-27
9.70	PCC Patching -----	9-29
9.71	Full-Depth PCC Patches -----	9-29
	Materials-----	9-29
	PCC Placement-----	9-29
	Curing -----	9-30
	Patch Thickness -----	9-30
	Saw Cuts -----	9-30
9.72	Partial-Depth PCC Patches-----	9-31
	Materials-----	9-31

