

## CHAPTER 8 HOT MIX ASPHALT (HMA) PAVEMENT, BASES, AND SUBBASES

<b>8.00</b>	<b>TABLES AND REPORT FORMS</b>	<b>8-1</b>
8.01	TABLES FOR BITUMINOUS MATERIALS AND HMA CONSTRUCTION	8-1
8.02	REPORT FORMS	8-1
	Form Identification and Use	8-1
<b>8.10</b>	<b>ACCEPTANCE AND TESTING</b>	<b>8-2</b>
8.11	FIELD TESTS AND CERTIFICATION OF MATERIALS	8-2
	Asphalt Materials	8-2
	Aggregates	8-2
8.12	RESPONSIBILITY AND DOCUMENTING HMA MIXTURE PROPORTIONING CHANGES	8-3
	Adjusting Asphalt Binder Contents	8-3
	Documenting Corrective Action for Noncomplying Air Voids Test on Specimens Taken from Constructed Pavement	8-3
	Adjusting Aggregate Proportions	8-4
	Filler/Bitumen Ratio	8-4
8.13	DENSITY CONTROLS FOR HMA CONSTRUCTION	8-4
	Uncompacted HMA Samples	8-4
	Compacted HMA Samples	8-5
	Procedures for Construction of Test Strips	8-7
	Resolving Density-Void Conflicts	8-10
8.14	TESTING FOR SMOOTHNESS	8-11
	Use of Straightedge and Rolling Surface Checker	8-11
8.15	CHECKING TRANSVERSE JOINTS FOR SMOOTHNESS	8-11
<b>8.20</b>	<b>MEASUREMENTS AND PAYMENT COMPUTATIONS</b>	<b>8-14</b>
8.21	ASPHALT BINDER	8-14
	Tank Measurement and Asphalt Binder Content Determination	8-14
	Measuring Asphalt Binder for Small Quantities	8-15
	Asphalt Binder Quantities and Pay Adjustments	8-15
8.22	TARGET VALUES FOR ASPHALT BINDER CONTENT IN JOB MIXES	8-15
8.23	WEIGHING OF HMA MATERIALS	8-16
<b>8.30</b>	<b>EQUIPMENT USE AND INSPECTION</b>	<b>8-17</b>

8.31	INSPECTION AT HMA PLANTS -----	8-17
8.32	INSPECTING THE MIXING TIME OF HMA PLANTS -----	8-17
<b>8.40</b>	<b>GENERAL CONSTRUCTION -----</b>	<b>8-19</b>
8.41	UNSTABLE SUBGRADES AND SUBBASES -----	8-19
	Locating Unstable Areas -----	8-19
	Determining Cause -----	8-19
	Overdepth Aeration and Recomaction -----	8-19
	Special Treatments -----	8-20
8.42	STAKING METHOD FOR HMA PAVEMENTS -----	8-20
8.43	GUIDELINE STRINGS AND EDGE ALIGNMENT -----	8-20
8.44	LONGITUDINAL JOINTS -----	8-21
8.45	TACK COATS USING EMULSIONS -----	8-21
	For Dilution -----	8-21
	Application Rate for Diluted Emulsion -----	8-21
	Sample for Compliance -----	8-22
	Measurement for Pay -----	8-22
	Settlement of Diluted Emulsions -----	8-22
<b>8.50</b>	<b>BASE, INTERMEDIATE, AND SURFACE COURSES -----</b>	<b>8-23</b>
8.51	HMA WEDGE CONSTRUCTION FOR SUPERELEVATION OF CURVES -----	8-23
	Automatic Slope Control -----	8-23
	Placement of Wedge -----	8-24
	Sequence of Placement -----	8-24
8.52	LAYING WIDTHS FOR HMA -----	8-25
8.53	SPREAD RATES FOR HMA BASE, INTERMEDIATE, AND SURFACE COURSES -----	8-25
8.54	HMA RESURFACING ON CITY STREETS -----	8-26
	Preliminary Layout -----	8-26
	Construction -----	8-27
	Thickness Taper at Curb Line -----	8-28
	Extending Paver Width -----	8-28
8.55	COLD WEATHER HMA CONSTRUCTION -----	8-28
	Temperature Determination for Placing HMA and Liquid Bitumens -----	8-29
8.56	RELEASE AGENTS AND SOLVENTS -----	8-29
<b>8.60</b>	<b>RUMBLE STRIPS IN HMA PAVEMENTS -----</b>	<b>8-30</b>

8.61	MILLED SHOULDER RUMBLE STRIPS-----	8-30
8.62	MILLED CENTERLINE RUMBLE STRIPS -----	8-30
<b>8.70</b>	<b>INSPECTOR'S GUIDE - HMA PAVING &amp; RESURFACING-----</b>	<b>8-32</b>
	Additional Requirements for Interstate Projects-----	8-34
	Additional Requirements for Full-Depth Paving -----	8-34
	Additional Requirements for Winter Shutdown -----	8-34
<b>8.80</b>	<b>USE OF SPECIAL EQUIPMENT -----</b>	<b>8-35</b>
	Material Transfer Vehicles -----	8-35
	Other Material Transfer Vehicles-----	8-35
	Mat Smoothness Machine -----	8-37
	Windrow Pick-up Equipment -----	8-37

