



REVISED 11-09 - THIS SHEET WAS ADDED FOR A 75 TON STEEL PILING OPTION.




TYPICAL SECTION




NOTE: D = PIN DIAMETER.
DIMENSIONS ARE OUT TO OUT.

H IN FT.	CL - CL ABUT. BRG. FT.	PILING (HP10x57)			FOOTING SIZE
		NO. & LAYOUT	DES. BRG. (TONS)	LRFD DES. BRG. (KIPS)	
18	201'-4"	15A	72	207	3'-6" x 8' x 24'
	213'-10"	15A	75	215	
	226'-4"	16A	73	211	
	243'-0"	16A	75	220	
	201'-4"	15A	73	212	3'-6" x 8' x 24'
	213'-10"	15A	75	220	
	226'-4"	16A	75	215	
	243'-0"	17A	75	216	
22 TO 24	19 TO 21	15A	75	216	3'-6" x 8' x 24'
	213'-10"	16A	73	210	
	226'-4"	16A	75	219	
	243'-0"	18A	74	212	


FOOTING SIZE	REINFORCING STEEL (ONE FOOTING)					STRUCTURAL CONCRETE (CY)
	BAR	NO., SIZE & SPACING	LENGTH	WEIGHT (LB.)	TOTAL WEIGHT (LB.)	
3'-6" x 8' x 24'	d2	48 - #9 AS SHOWN	8'-7"	1401	3018	24.9
	f1	24 - #5 @ 1'-0"	7'-8"	192		
	f2	8 - #5 @ 1'-0"	23'-8"	197		
	g1	30 - #7 @ 0'-9 1/2"	7'-8"	470		
	g2	12 - #8 @ 0'-8"	23'-8"	758		



- ① FOR DETERMINING ACTUAL PILE LENGTHS IN FIELD.
- ② FOR ESTIMATING PILE LENGTHS USING AASHTO LRFD SPECIFICATIONS.



3'-6" x 8'-0" x 24'-0" FOR 15A, 16A & 17A



3'-6" x 8'-0" x 24'-0" FOR 18A

FOOTING NOTES:

THESE FOOTINGS ARE DESIGNED AND DETAILED TO BE USED WITH THE CAP AND COLUMN DETAILS OF THE TEE PIERS AS SHOWN ON SHEET H44-58-07.

BATTER PILES IN EXTERIOR ROWS 1:4 IN THE DIRECTION SHOWN.

STEEL PILING USED AS POINT BEARING SHALL HAVE A MINIMUM DISTANCE OF APPROXIMATELY 10 FEET FROM BOTTOM OF FOOTING TO TOP OF BEARING ROCK. THE PILE LAYOUTS ARE SUCH THAT THE DISTANCE CENTER TO CENTER OF ADJACENT PILING SHALL NOT EXCEED 8'-0".

11-09 LATEST REVISION DATE	 APPROVED BY BRIDGE ENGINEER	 STANDARD DESIGN - 44' ROADWAY, THREE SPAN BRIDGE PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES MARCH, 2007
		TEE PIER - 75 TON STEEL PILE FOOTINGS 15° SKEW - H=16' TO 24'
		H44-62-07