

Install delineators and object markers according to SI-211.

For grading requirements, see RL-14A.

For general guardrail details, see BA-200.



① See BA-203.

② See BA-205.

Possible Contract Items:

- Steel Beam Guardrail
- Steel Beam Guardrail End Anchor, W-Beam
- Steel Beam Guardrail End Terminal

Possible Tabulation:
108-8B

 Iowa Department of Transportation	REVISION	
	New	04-20-10
STANDARD ROAD PLAN		BA-252
		SHEET 1 of 1
REVISIONS: New. Replaces RE-55A.		
 APPROVED BY DESIGN METHODS ENGINEER		
STEEL BEAM GUARDRAIL INSTALLATION AT SIDE OBSTACLE (ONE-WAY PROTECTION)		