

REVISED 01-10 - THE SPECIFICATION REFERENCES CHANGED. ADDED ADDITIONAL SHEETS TO THE INDEX.

GENERAL CONSIDERATIONS:

THE H24-06 BRIDGE STANDARDS, IF PROPERLY USED, PROVIDE THE STRUCTURAL PLANS NECESSARY TO CONSTRUCT THREE SPAN 24' ROADWAY PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES WITH LENGTHS OF 138'-10, 151'-4, 163'-10, 176'-4, 188'-10, 201'-4, 213'-10, 226'-4 AND 243'-0.

THESE BRIDGES MAY BE BUILT ON A 0°, 15°, 30° OR 45° SKEW. THESE PLANS SHOW THE BRIDGES SKEWED IN ONE DIRECTION, BUT ALL DIMENSIONS AND DETAILS WOULD BE THE SAME FOR THE OPPOSITE SKEW.

THESE BRIDGES ARE DESIGNED FOR HL93 LOADING PLUS 20 LBS. PER SQ. FT. OF ROADWAY FOR FUTURE WEARING SURFACE. CONTROL OF CRACKING BY DISTRIBUTION OF REINFORCEMENT FOR SLAB DESIGN BASED ON PRE LRFD 2005 INTERIMS.

NOTE THAT WHEN APPROACH PAVEMENT IS TO BE PLACED, THE TEMPORARY PAVING BLOCKS SHALL BE REMOVED AND A PROPER JOINT FOR EXPANSION SHALL BE PROVIDED BETWEEN THE BRIDGE AND THE APPROACH PAVING.

THE FLOOR SLAB AS SHOWN INCLUDES 1/2" INTEGRAL WEARING SURFACE.

THE ABUTMENTS FOR THESE BRIDGES ARE BUILT INTEGRAL WITH THE SUPERSTRUCTURE. THEREFORE, IT IS IMPORTANT THAT A PROPER JOINT FOR EXPANSION BE PROVIDED BETWEEN THE BRIDGE AND APPROACH PAVING, WHEN APPROACH PAVING IS NEEDED.

THE INTEGRAL ABUTMENT DESIGN UTILIZED ON THESE BRIDGES RESTRICTS THEIR USE IN THE FOLLOWING MANNER:

- (1) THE 201'-4, 213'-10, 226'-4 AND 243'-0 BRIDGES SHALL USE STEEL PILES AT THE ABUTMENTS.
- (2) THESE BRIDGES ARE NOT TO BE USED WHEN POINT BEARING FOR THE ABUTMENT STEEL PILING WOULD BE OBTAINED ON ROCK AT A DISTANCE LESS THAN 15 FEET FROM THE BOTTOM OF FOOTING.
- (3) THE ABUTMENT PILING ARE TO BE DRIVEN THROUGH OVERSIZED HOLES PREBORED TO A MINIMUM OF 10 FEET BELOW THE BOTTOM OF FOOTING. THE PREBORED HOLES SHALL BE IN ACCORDANCE WITH SECTION 2501.19 OF THE STANDARD SPECIFICATIONS. THE ELEVATION OF THE BOTTOM OF THE PREBORED HOLE SHALL BE SHOWN ON THE PLANS.

THESE STANDARDS GIVE MOST OF THE INFORMATION NECESSARY TO BUILD THESE BRIDGES ON EITHER A CREST VERTICAL CURVE OR A STRAIGHT GRADE. BECAUSE OF THE INFINITE NUMBER OF GRADE POSSIBILITIES IT WILL BE NECESSARY TO SHOW ON THE PLANS THE ABUTMENT AND PIER STEP DIMENSIONS. TO HELP IN OBTAINING THIS STEP INFORMATION SEE "EXAMPLES OF BRIDGE SEAT AND STEP CALCULATIONS" ON SHEET H24-02-06 .

THE ABUTMENT FOOTING AND PIER CAP CONCRETE QUANTITIES SHOWN IN THESE PLANS ARE CALCULATED BASED ON A 0.3% GRADE. FOR HIGHER GRADES, THESE CONCRETE QUANTITIES FOR BRIDGES SKEWED AT 15°, 30°, AND 45° MAY NEED TO BE INCREASED. IN ADDITION, THE LAYOUT OF THE PIER CAP STEP REINFORCING STEEL IS GRADE DEPENDENT FOR BRIDGES SKEWED AT 15°, 30°, AND 45°. SEE SHEETS H24-17-06, H24-24-06, AND H24-31-06 TO DETERMINE THE ADDITIONAL CONCRETE QUANTITIES REQUIRED AND FOR THE LAYOUT AND QUANTITY OF THE PIER CAP STEP REINFORCING STEEL.

PROVIDE TOP OF SLAB ELEVATIONS AND WING ELEVATIONS A, B AND C AS NOTED ON THE STANDARD SHEETS (LONGITUDINAL SECTION).

VARIOUS TYPES OF PIERS MAY BE USED WITH THESE STANDARDS. IT SHOULD BE NOTED THAT THE DETAILS FOR THE PIER DIAPHRAGM ON THE SUPERSTRUCTURE DEPEND ON THE TYPE OF PIER USED.

THE PIERS AND ABUTMENTS FOR THESE STANDARDS HAVE BEEN DESIGNED FOR THE USE OF BOTH FRICTION AND POINT BEARING PILES. IT IS NECESSARY THAT THE TYPE AND LENGTH FOR BOTH THE ABUTMENT AND PIER PILES BE DESIGNATED ON THE FRONT SHEET OF THE PLANS.

THESE STANDARDS ARE FOR USE FOR BRIDGES WITH NON-EPOXY COATED REINFORCING. REINFORCING BAR LAP LENGTHS ARE BASED ON THE USE OF NON-EPOXY COATED REINFORCING.

FOR PIERS SUBJECT TO SCOUR THE DESIGN BEARING SHALL BE OBTAINED BELOW SCOUR ELEVATION. SCOUR ELEVATION SHALL BE SHOWN ON THE FRONT SHEET.

CONCRETE INTERMEDIATE DIAPHRAGMS SHALL BE USED FOR OVERPASS BRIDGES. THE DESIGNER SHALL ADJUST THE CONCRETE AND REINFORCING QUANTITIES ACCORDINGLY.

3" WING PVC PIPE IS INCIDENTAL TO STRUCTURAL CONCRETE.

KEYWAY DIMENSIONS SHOWN ON THE PLANS ARE BASED ON NOMINAL DIMENSIONS UNLESS STATED OTHERWISE. IN ADDITION, THE BEVEL USED ON THE KEYWAY SHALL BE LIMITED TO A MAXIMUM OF 10 DEGREES FROM VERTICAL.

INDEX FOR H24-06 STANDARDS:

H24-01-06	INDEX & GENERAL NOTES
H24-02-06	GENERAL INFORMATION
H24-03-06	SUPERSTRUCTURE DETAILS
H24-04-06	SUPERSTRUCTURE DETAILS-MISC.
H24-05-06	ABUTMENT DETAILS FOR 0° SKEW, A & B BEAMS
H24-06-06	ABUTMENT DETAILS FOR 0° SKEW, C BEAMS
H24-07-06	LONGITUDINAL SECTION FOR 0° SKEW, A & B BEAMS
H24-08-06	LONGITUDINAL SECTION FOR 0° SKEW, C BEAMS
H24-09-06	SUPERSTRUCTURE DETAILS FOR 0° SKEW
H24-10-06	DECK & ABUTMENT REINF. FOR 0° SKEW
H24-11-06	ABUTMENT DETAILS FOR 15° SKEW, A & B BEAMS
H24-12-06	ABUTMENT DETAILS FOR 15° SKEW, C BEAMS
H24-13-06	LONGITUDINAL SECTION FOR 15° SKEW, A & B BEAMS
H24-14-06	LONGITUDINAL SECTION FOR 15° SKEW, C BEAMS
H24-15-06	SUPERSTRUCTURE DETAILS FOR 15° SKEW
H24-16-06	DECK & ABUTMENT REINF. FOR 15° SKEW
H24-17-06	ADDITIONAL QUANTITIES FOR 15° SKEW
H24-18-06	ABUTMENT DETAILS FOR 30° SKEW, A & B BEAMS
H24-19-06	ABUTMENT DETAILS FOR 30° SKEW, C BEAMS
H24-20-06	LONGITUDINAL SECTION FOR 30° SKEW, A & B BEAMS
H24-21-06	LONGITUDINAL SECTION FOR 30° SKEW, C BEAMS
H24-22-06	SUPERSTRUCTURE DETAILS FOR 30° SKEW
H24-23-06	DECK & ABUTMENT REINF. FOR 30° SKEW
H24-24-06	ADDITIONAL QUANTITIES FOR 30° SKEW
H24-25-06	ABUTMENT DETAILS FOR 45° SKEW, A & B BEAMS
H24-26-06	ABUTMENT DETAILS FOR 45° SKEW, C BEAMS
H24-27-06	LONGITUDINAL SECTION FOR 45° SKEW, A & B BEAMS
H24-28-06	LONGITUDINAL SECTION FOR 45° SKEW, C BEAMS
H24-29-06	SUPERSTRUCTURE DETAILS FOR 45° SKEW
H24-30-06	DECK & ABUTMENT REINF. FOR 45° SKEW
H24-31-06	ADDITIONAL QUANTITIES FOR 45° SKEW
H24-32-06	A BEAM DETAILS
H24-33-06	A BEAM DETAILS
H24-34-06	B BEAM DETAILS
H24-35-06	B BEAM DETAILS
H24-36-06	C BEAM DETAILS
H24-37-06	C BEAM DETAILS
H24-38-06	INTERMEDIATE STEEL DIAPHRAGMS
H24-39-06	OPEN RAIL DETAILS, 1 OF 2
H24-40-06	OPEN RAIL DETAILS, 2 OF 2
H24-01-06	PIER BEARING DETAILS

INDEX FOR H24-06 STANDARDS (CONT'D.):

H24-42-06	PILE BENT PIERS FOR 0° SKEW
H24-43-06	PILE BENT PIERS-HP14 PILES FOR 0° SKEW
H24-44-06	PILE BENT PIERS FOR 15° SKEW
H24-45-06	PILE BENT PIERS HP14 PILES FOR 15° SKEW
H24-46-06	PILE BENT PIERS FOR 30° SKEW
H24-47-06	PILE BENT PIERS HP14 PILES FOR 30° SKEW
H24-48-06	PILE BENT PIERS FOR 45° SKEW
H24-49-06	PILE BENT PIERS HP14 PILES FOR 45° SKEW
H24-50-06	TEE PIER CAP AND COLUMN, 0° SKEW
H24-51-06	TEE PIER-50 TON STEEL PILE FOOTINGS 0° SKEW, H=16' TO 24'
H24-52-06	TEE PIER-50 TON STEEL PILE FOOTINGS 0° SKEW, H=25' TO 40'
H24-53-06	TEE PIER-75 TON STEEL PILE FOOTINGS 0° SKEW, H=16' TO 24'
H24-54-06	TEE PIER-75 TON STEEL PILE FOOTINGS 0° SKEW, H=25' TO 40'
H24-55-06	TEE PIER-SPREAD FOOTINGS, 0° SKEW, H=16' TO 24'
H24-56-06	TEE PIER-SPREAD FOOTINGS, 0° SKEW, H=25' TO 40'
H24-57-06	TEE PIER CAP AND COLUMN, 15° SKEW
H24-58-06	TEE PIER-50 TON STEEL PILE FOOTINGS, 15° SKEW, H=16' TO 24'
H24-59-06	TEE PIER-50 TON STEEL PILE FOOTINGS, 15° SKEW, H=25' TO 40'
H24-60-06	TEE PIER-75 TON STEEL PILE FOOTINGS, 15° SKEW, H=16' TO 24'
H24-61-06	TEE PIER-75 TON STEEL PILE FOOTINGS, 15° SKEW, H=25' TO 40'
H24-62-06	TEE PIER-SPREAD FOOTINGS, 15° SKEW, H=16' TO 24'
H24-63-06	TEE PIER-SPREAD FOOTINGS, 15° SKEW, H=25' TO 40'
H24-64-06	TEE PIER CAP AND COLUMN, 30° SKEW
H24-65-06	TEE PIER-50 TON STEEL PILE FOOTINGS, 30° SKEW, H=16' TO 24'
H24-66-06	TEE PIER-50 TON STEEL PILE FOOTINGS, 30° SKEW, H=25' TO 40'
H24-67-06	TEE PIER-75 TON STEEL PILE FOOTINGS, 30° SKEW, H=16' TO 24'
H24-68-06	TEE PIER-75 TON STEEL PILE FOOTINGS, 30° SKEW, H=25' TO 40'
H24-69-06	TEE PIER-SPREAD FOOTINGS, 30° SKEW, H=16' TO 24'
H24-70-06	TEE PIER-SPREAD FOOTINGS, 30° SKEW, H=25' TO 40'
H24-71-06	TEE PIER CAP AND COLUMN, 45° SKEW
H24-72-06	TEE PIER-50 TON STEEL PILE FOOTINGS, 45° SKEW, H=16' TO 24'
H24-73-06	TEE PIER-50 TON STEEL PILE FOOTINGS, 45° SKEW, H=25' TO 40'
H24-74-06	TEE PIER-75 TON STEEL PILE FOOTINGS, 45° SKEW, H=16' TO 24'
H24-75-06	TEE PIER-75 TON STEEL PILE FOOTINGS, 45° SKEW, H=25' TO 40'
H24-76-06	TEE PIER-SPREAD FOOTINGS, 45° SKEW, H=16' TO 24'
H24-77-06	TEE PIER-SPREAD FOOTINGS, 45° SKEW, H=25' TO 40'
H24-78-06	SUBDRAIN DETAILS
H24-79-06	WING ARMORING DETAILS, A & B BEAMS
H24-80-06	WING ARMORING DETAILS, C BEAMS
H24-81-06	ABUTMENT BACKFILL DETAIL, A & B BEAMS - 0° SKEW
H24-82-06	ABUTMENT BACKFILL DETAIL, A & B BEAMS - SKEWED
H24-83-06	ABUTMENT BACKFILL DETAIL, C BEAMS - 0° SKEW
H24-84-06	ABUTMENT BACKFILL DETAIL, C BEAMS - SKEWED

THESE BRIDGE PLANS LABEL ALL REINFORCING STEEL WITH ENGLISH NOTATION (501 IS 3/8 INCH DIAMETER BAR). ENGLISH REINFORCING STEEL RECEIVED IN THE FIELD MAY DISPLAY THE FOLLOWING "BAR DESIGNATION". THE "BAR DESIGNATION" IS THE STAMPED IMPRESSION ON THE REINFORCING BARS, AND IS EQUIVALENT TO THE BAR DIAMETER IN MILLIMETERS.

ENGLISH SIZE	3	4	5	6	7	8	9	10	11
BAR DESIGNATION	10	13	16	19	22	25	29	32	36


DESIGN STRESSES:

DESIGN STRESSES FOR THE FOLLOWING MATERIALS ARE IN ACCORDANCE WITH THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, 4TH Ed, SERIES OF 2007. REINFORCING STEEL IN ACCORDANCE WITH LRFD AASHTO SECTION 5, GRADE 60. CONCRETE IN ACCORDANCE WITH LRFD AASHTO SECTION 5, f'c = 3,500 PSI. FOR STANDARD PRESTRESSED CONCRETE BEAMS, SEE SHEETS H24-32-06 THRU H24-37-06

SPECIFICATIONS:

DESIGN:
AASHTO LRFD 4th Ed, SERIES OF 2007.

CONSTRUCTION:
IOWA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2009, PLUS APPLICABLE GENERAL SUPPLEMENTAL SPECIFICATIONS, DEVELOPMENTAL SPECIFICATIONS, SUPPLEMENTAL SPECIFICATIONS AND SPECIAL PROVISIONS SHALL APPLY TO CONSTRUCTION WORK ON THIS PROJECT.

01-10 LATEST REVISION DATE	 APPROVED BY BRIDGE ENGINEER	 Iowa Department of Transportation Highway Division	
		STANDARD DESIGN - 24' ROADWAY, THREE SPAN BRIDGE PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGES DECEMBER, 2006	
		INDEX & GENERAL NOTES	H24-01-06