



H IN FT.	CL - CL ABUT. BRG.	PILING (HP10x57)			FOOTING SIZE
		NO. & LAYOUT	DES. BRG. (TONS)	LRFD DES. BRG. (KIPS)	
16 TO 18	160'-0"	10A	72	209	4' x 8' x 25'
	180'-0"	11A	73	211	
	200'-0"	12A	71	206	
	220'-0"	13A	72	208	
	240'-0"	14A	72	206	4' x 9' x 25'
	260'-0"	14B	75	216	
	280'-0"	16A	73	211	
	300'-0"	16D	74	214	
19 TO 21	320'-0"	16E	74	215	4' x 11' x 27'
	340'-0"	17B	75	216	
	160'-0"	10A	75	216	4' x 8' x 25'
	180'-0"	11A	75	218	
	200'-0"	12A	74	213	
	220'-0"	13A	74	214	
	240'-0"	14A	74	212	4' x 9' x 25'
	260'-0"	15A	74	213	
22 TO 24	280'-0"	16A	75	217	
	300'-0"	16D	75	219	4' x 11' x 27'
	320'-0"	16E	75	219	
	340'-0"	18A	73	210	
25 TO 27	160'-0"	10B	75	218	4' x 9' x 25'
	180'-0"	12B	70	202	
	200'-0"	12B	74	214	
	220'-0"	13B	75	216	
	240'-0"	14B	74	213	4' x 10' x 25'
	260'-0"	15A	75	218	
	280'-0"	16B	75	217	
	300'-0"	16E	73	212	4' x 12' x 27'
28 TO 30	320'-0"	17B	74	215	
	340'-0"	18A	74	214	4' x 10' x 25'
	160'-0"	11C	72	209	
	180'-0"	12C	71	204	
31 TO 33	200'-0"	12C	75	216	4' x 11' x 25'
	220'-0"	13C	75	217	
	240'-0"	14C	74	214	
	260'-0"	15B	75	218	4' x 11' x 27'
	280'-0"	16C	75	218	
	300'-0"	16E	75	215	4' x 12' x 27'
	320'-0"	17B	75	218	
	340'-0"	18A	75	217	
34 TO 36	160'-0"	11C	74	214	4' x 10' x 25'
	180'-0"	12C	72	209	
	200'-0"	13C	71	206	
	220'-0"	14C	71	204	4' x 11' x 27'
	240'-0"	14C	75	218	
	260'-0"	15C	75	216	4' x 12' x 27'
	280'-0"	16D	75	218	
	300'-0"	16E	75	218	

H IN FT.	CL - CL ABUT. BRG.	PILING (HP10x57)			FOOTING SIZE
		NO. & LAYOUT	DES. BRG. (TONS)	LRFD DES. BRG. (KIPS)	
37 TO 40	160'-0"	12F	70	203	4' x 12' x 27'
	180'-0"	12F	75	215	
	200'-0"	13F	75	215	
	220'-0"	14F	75	217	
	240'-0"	15D	71	205	
	260'-0"	15D	75	217	
	280'-0"	16E	74	215	
	300'-0"	17B	75	218	
340'-0"	18A	75	218		
	19A	75	219		




FOOTING SIZE	REINFORCING STEEL (ONE FOOTING)				TOTAL WEIGHT (LB.)	STRUCTURAL CONCRETE (CY)
	BAR	NO., SIZE & SPACING	LENGTH	WEIGHT (LB.)		
4' x 8' x 25'	d2	54 - #9 AS SHOWN	9'-1	1668	3141	29.6
	f1	25 - #5 @ 1'-0	7'-8	200		
	f2	8 - #5 @ 1'-0	24'-8	206		
	g1	27 - #6 @ 0'-11	7'-8	311		
	g2	15 - #7 @ 0'-6	24'-8	756		
	d2	54 - #9 AS SHOWN	9'-1	1668		
	f1	25 - #5 @ 1'-0	8'-8	226		
	f2	9 - #5 @ 1'-0	24'-8	232		
4' x 9' x 25'	g1	28 - #7 @ 0'-10 1/2	8'-8	496	3378	33.3
	g2	15 - #7 @ 0'-7	24'-8	756		
	d2	54 - #9 AS SHOWN	9'-1	1668		
	f1	25 - #5 @ 1'-0	9'-8	252		
	f2	10 - #5 @ 1'-0	24'-8	257		
	g1	28 - #8 @ 0'-10 1/2	9'-8	723		
	g2	15 - #7 @ 0'-8	24'-8	756		
	d2	54 - #9 AS SHOWN	9'-1	1668		
4' x 10' x 25'	f1	25 - #5 @ 1'-0	10'-8	278	3998	40.7
	f2	11 - #5 @ 1'-0	24'-8	283		
	g1	27 - #9 @ 0'-11	10'-8	979		
	g2	12 - #8 @ 0'-11	24'-8	790		
	d2	54 - #9 AS SHOWN	9'-1	1668		
	f1	27 - #5 @ 1'-0	10'-8	300		
	f2	11 - #5 @ 1'-0	26'-8	306		
	g1	34 - #8 @ 0'-9 1/2	10'-8	968		
4' x 11' x 25'	g2	14 - #9 @ 0'-9 1/2	26'-8	1269	4511	44.0
	d2	54 - #9 AS SHOWN	9'-1	1668		
	f1	27 - #5 @ 1'-0	11'-8	329		
	f2	12 - #5 @ 1'-0	26'-8	334		
	g1	33 - #9 @ 0'-9 1/2	11'-8	1309		
	g2	15 - #9 @ 0'-9 1/2	26'-8	1360		
4' x 12' x 27'	d2	54 - #9 AS SHOWN	9'-1	1668	5000	48.0
	f1	27 - #5 @ 1'-0	11'-8	329		
	f2	12 - #5 @ 1'-0	26'-8	334		
	g1	33 - #9 @ 0'-9 1/2	11'-8	1309		
	g2	15 - #9 @ 0'-9 1/2	26'-8	1360		
	d2	54 - #9 AS SHOWN	9'-1	1668		
	f1	27 - #5 @ 1'-0	11'-8	329		
	f2	12 - #5 @ 1'-0	26'-8	334		


- FOR DETERMINING ACTUAL PILE LENGTHS IN FIELD.
- FOR ESTIMATING PILE LENGTHS USING AASHTO LRFD SPECIFICATIONS.



d2 BAR LAYOUT
(SEE SECTION A-A ON SHEET RS40-126-10.)



4'-0 x 8'-0 x 25'-0 FOR 10A, 11A & 12A




4'-0 x 8'-0 x 25'-0 FOR 13A & 14A

FOOTING NOTES:

THESE FOOTINGS ARE DESIGNED AND DETAILED TO BE USED WITH THE CAP AND COLUMN DETAILS OF THE TEE PIERS AS SHOWN ON SHEET RS40-126-10.

BATTER PILES IN EXTERIOR ROWS 1:4 IN THE DIRECTION SHOWN.

STEEL PILING USED AS POINT BEARING SHALL HAVE A MINIMUM DISTANCE OF APPROXIMATELY 10 FEET FROM BOTTOM OF FOOTING TO TOP OF BEARING ROCK. THE PILE LAYOUTS ARE SUCH THAT THE DISTANCE CENTER TO CENTER OF ADJACENT PILING SHALL NOT EXCEED 8'-0.



TYPICAL SECTION

LATEST REVISION DATE	 Iowa Department of Transportation Highway Division		
		STANDARD DESIGN - 40' ROADWAY, 3 SPAN BRIDGES	
		ROLLED STEEL BEAM BRIDGES	
		JUNE, 2010	
	TEE PIER - 75 TON STEEL PILE FOOTINGS 10° SKEW - SHEET 1	RS40-131-10	