

CHAPTER 11 STRUCTURES

11.00 INTRODUCTION	11-1
11.01 REMOVAL OF BRIDGES	11-1
11.02 GUIDANCE FOR HEAVY EQUIPMENT & MATERIALS ON BRIDGES	11-1
11.03 TEMPORARY STRUCTURES FOR THE PROTECTION OF THE PUBLIC	11-3
11.05 PILE DRIVING CAP AND HAMMER INFORMATION	11-3
11.10 EARTHWORK FOR STRUCTURES	11-5
11.11 EXCAVATION	11-5
11.12 BACKFILLING STRUCTURES	11-5
Culverts	11-5
Bridge Abutments	11-5
Measurement and Payment	11-6
11.20 FOUNDATIONS	11-7
11.21 STAKING AND CHECKING LOCATIONS OF STRUCTURES	11-7
Check and Double Check	11-7
Documentation	11-8
Common Survey Errors to Avoid	11-8
Encountering Old Substructures	11-8
Setting Bench Marks (Post Construction)	11-8
11.22 PILING AND PILE DRIVING	11-9
Pile Driving	11-9
Vibratory Hammers	11-9
Gravity Hammers	11-10
Diesel Hammers	11-10
Bearing and Penetration	11-11
Retaps	11-11
Dynamic Pile Analyzer	11-12
Static Load Tests	11-13
11.23 SPLICING PILE	11-13
Welding Steel Pile	11-13
Concrete Pile	11-16
11.24 PILING ACCEPTANCE	11-17

Steel Pile -----	11-17
Wood Pile -----	11-17
Steel Pile Cutoffs -----	11-17
11.25 WAVE EQUATION -----	11-18
Hammer Data Form -----	11-18
Driving Graphs -----	11-18
Log of Piling Driven -----	11-20
11.26 PREBORED HOLES -----	11-21
Typical Preboring -----	11-21
Special Prebore Situations -----	11-22
Bentonite -----	11-22
11.27 DRILLED SHAFTS -----	11-23
11.30 BRIDGES -----	11-24
11.31 FALSEWORK -----	11-24
Temporary Fastenings -----	11-24
Falsework Plans -----	11-24
Falsework Inspection -----	11-25
Falsework Foundations -----	11-25
Materials -----	11-26
Project Quality -----	11-28
Miscellaneous Items -----	11-30
Falsework Adjacent To Traffic -----	11-30
Field Changes -----	11-30
Inspection during Concrete Placement -----	11-30
Removal of Falsework -----	11-31
11.32 BRIDGES - STEEL BEAM -----	11-31
Prebolting Meeting -----	11-32
Erecting Steel Beams -----	11-33
High Strength Fasteners -----	11-34
Painting -----	11-43
11.33 BRIDGES - CONCRETE BEAM -----	11-43
Precast - Prestressed Deck Panels -----	11-43
Pretensioned Prestressed Concrete Beam (PPC Beam) Erection -----	11-44
Diaphragms (Steel or Concrete) -----	11-44

11.40 REINFORCEMENT	11-46
General Placement Guidelines for Bridge Reinforcing Steel	11-46
11.41 PLACEMENT AND CHECKING (BRIDGE FLOORS)	11-46
Slab Thickness	11-46
Clearance of Bottom Reinforcement	11-46
Clearance of Top Mat Reinforcement	11-47
Cover Over Top Mat of Reinforcement	11-47
Slab Bridges	11-47
Special Attention Areas	11-47
11.42 EPOXY COATED REINFORCEMENT	11-48
Care and Handling	11-48
Field Inspection	11-50
Repair of Damaged Coating	11-50
11.43 CAGE STEEL (DRILLED SHAFTS)	11-51
11.44 SPLICING	11-51
Splice Approval	11-51
11.45 PAYMENT FOR REINFORCING STEEL	11-52
11.50 CONCRETE (STRUCTURAL, CLASS X, AND FLOWABLE MORTAR)	11-53
11.51 PCC PLANT PAGE (FORMS 800240E AND 800240M)	11-53
11.52 USE OF READY MIXED STRUCTURAL CONCRETE	11-53
Prepour Meeting	11-53
Inspector's Checklist	11-53
11.53 ADMIXTURES	11-57
Air Entraining Admixtures	11-58
Water Reducing Admixtures – Regular	11-58
Water Reducing Admixtures - Super Plasticizers	11-59
Retarding Admixtures	11-59
Accelerating Admixtures	11-60
Corrosion Inhibiting Admixtures	11-60
Finely Divided Mineral Admixtures	11-61
Pozzolan Materials	11-61
Fly Ash (Class C & F)	11-61
Silica Fume	11-61
Cementitious Materials	11-61

	Ground Granulated Blast Furnace Slag (GGBFS)-----	11-61
11.54	USE OF INSULATED FORMS FOR PROTECTION -----	11-62
	Checking Temperature of Concrete -----	11-62
11.55	DECK PLACEMENT AND HEAT OF HYDRATION -----	11-63
	Deck Placement-----	11-63
	Deck Concrete Temperature and Curing-----	11-63
	Placement Considerations -----	11-64
	Field Documentation -----	11-66
	Heat of Hydration -----	11-66
11.56	PLACEMENT METHODS (PUMPING, BELTING, AND CRANE BUCKET)-----	11-66
	Crane and Bucket-----	11-66
	Belt Placement-----	11-67
	Pump Placement-----	11-67
11.57	FORM REMOVAL-----	11-68
	Setting Beams -----	11-68
11.58	CLASS 3 CONCRETE SURFACE FINISH (RAIL AND BEAMS)-----	11-68
	Approval of Materials-----	11-68
	Application of Finish -----	11-68
	Concrete Railings -----	11-69
11.59	FLOWABLE MORTAR-----	11-69
	Backfilling Culverts - Typical Grading -----	11-70
	Plugging Culverts -----	11-72
	Backfilling Culverts - Under Bridges-----	11-72
	Filling Voids Between Culverts-----	11-72
11.60	DECKS AND OVERLAYS -----	11-74
11.61	DECK OVERLAY PREPARATION -----	11-74
	Class A Floor Repair -----	11-74
	Class A Surface Preparation -----	11-75
	Work on Adjacent Lanes -----	11-75
11.62	SEQUENCE OF POURING -----	11-76
	Use of Retarders -----	11-77
	Concrete Bridge Floors -----	11-80
	Placement Methods -----	11-86
11.63	INSTALLATION OF JOINTS -----	11-87

Preformed Neoprene Joints -----	11-87
Steel Extruded Expansion Joints (Strip Seals)-----	11-87
11.64 BRIDGE FLOORS -----	11-89
Finishing and Equipment-----	11-89
Profile Grades - Overlays -----	11-89
Transverse Grooving-----	11-90
Longitudinal Grooving In Hardened Concrete-----	11-90
Missed Texturing -----	11-90
11.65 CONCRETE -----	11-91
Concrete Mobile Mixers-----	11-91
Frequency of Checks -----	11-91
Density Testing -----	11-91
11.66 APPROACH SECTIONS -----	11-92
Approach Pavements to Bridge Abutments -----	11-92
“Movable” Abutments -----	11-93
“Fixed” Abutments -----	11-94
Bridge Approach Tapers -----	11-94
Shoulder Maintenance -----	11-94
11.67 SMOOTHNESS OF BRIDGE DECKS -----	11-95
Checklist -----	11-95
Specification 2428 -----	11-96
Surface Checking -----	11-97
11.70 BARRIER RAILS-----	11-98
11.71 CONCRETE F-SHAPE, OPEN, AND RETROFIT RAIL -----	11-98
Rail Concrete Placement and Bridge Deck Falsework-----	11-98
11.72 SLIP FORM BARRIER RAIL -----	11-99
Longitudinal Cracks -----	11-99
Reinforcement -----	11-99
Reinforcement Bar Cover -----	11-99
Misalignment and Nonuniform Top Elevation -----	11-99
Shadowing -----	11-100
Mix Design for Slip Form and Cast-in-Place-----	11-100
Curing of Slip Form Barrier Rail -----	11-101
Expansion Joint Construction in Barrier Rail -----	11-101

11.73	CAST-IN-PLACE (RETROFIT) BARRIER RAIL -----	11-102
	Preventing Dowel Installation Damage of Conduit -----	11-103
11.74	CAST-IN-PLACE OPEN BARRIER RAIL FORM REMOVAL -----	11-103
11.80	REINFORCED CONCRETE CULVERTS -----	11-104
11.81	DESIGN CHANGES ON CULVERTS -----	11-104
11.82	INSTALLING REINFORCING STEEL, PLACING CONCRETE, AND FORM REMOVAL -----	11-104
	Installing Reinforcing Steel -----	11-104
	Placing Concrete -----	11-105
	Removal of Wall Forms -----	11-105
	Removal of Slab Forms -----	11-106
11.83	BOX CULVERT CURTAIN WALLS -----	11-106
	Sheet Pile Curtain Wall -----	11-106
	Reinforcement Placement -----	11-106
11.84	BOX CULVERT BELL JOINTS -----	11-107