




DETAIL 'A'



SECTION A-A



PERSPECTIVE VIEW  
DITCH SLOPE AND BEVELED PIPE



PLAN

| TABLE OF OFFSETS AND DROPS (PAVED SHOULDERS) |        |       |       |       |       |        |       |       |       |       |       |       |       |       |       |       |
|----------------------------------------------|--------|-------|-------|-------|-------|--------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| Distance from Location Station (Feet)        | 517.98 | 500   | 475   | 450   | 400   | 350.69 | 350   | 325   | 300   | 275   | 250   | 225   | 200   | 175   | 150   | 125   |
| Offset from inside edge of Pavement (Feet)   | 6.00   | 6.00  | 6.00  | 6.00  | 6.00  | 6.00   | 6.03  | 7.32  | 8.79  | 10.44 | 12.27 | 14.28 | 16.47 | 18.84 | 21.40 | 24.13 |
| Cross-Slope from inside edge of Pavement     | 4.00%  | 3.36% | 2.47% | 2.00% | 2.00% | 2.00%  | 2.00% | 2.00% | 2.00% | 2.00% | 2.00% | 2.00% | 2.00% | 2.00% | 2.00% | 2.00% |
| Drop from inside edge of Pavement (Feet)     | 0.24   | 0.20  | 0.15  | 0.12  | 0.12  | 0.12   | 0.12  | 0.15  | 0.18  | 0.21  | 0.25  | 0.29  | 0.33  | 0.38  | 0.43  | 0.48  |
| POINT LOCATION                               | (D)    |       |       |       |       | (C)    |       |       |       |       |       |       |       |       |       | (B)   |

Detour Pavement options: 9" PCC or 12" HMA

- ① 'L-2' or 'KT-2' spaced at one-quarter median width. See PV-1.
- ② For PCC pavement, match existing roadway joints. 'CD' joints are required. See PV-1.
- ③ 'KT-2' joint, bend bars out for new pavement only.
- ④ Median crossover is symmetrical about centerline.
- ⑤ Beveled pipe and guard. See RF-27.
- ⑥ 2 foot 'C' joint.
- ⑦ Slotted drain for median crossover. See RF-45.

| DESIGN QUANTITY TABLE       |                          |
|-----------------------------|--------------------------|
| Detour Pavement<br>Sq. Yds. | Special Backfill<br>Tons |
| 3515                        | 1635                     |



Possible Contract Items:  
 Detour Pavement  
 Embankment In Place  
 Excavation, Class 10, Roadway and Borrow  
 Excavation, Class 13, Roadway and Borrow  
 Removal of Pavement  
 Special Backfill

Possible Tabulation:  
 112-8

|                                                |                                                                            |  |
|------------------------------------------------|----------------------------------------------------------------------------|--|
| <br><b>STANDARD ROAD PLAN</b>                  | REVISION<br>1 10-19-10                                                     |  |
|                                                | <b>PV-503</b>                                                              |  |
|                                                | SHEET 1 of 1                                                               |  |
|                                                | REVISIONS: Changed "Profile Grade" in the plan view to "Location Station". |  |
| APPROVED BY DESIGN METHODS ENGINEER<br>        |                                                                            |  |
| <b>MEDIAN CROSSOVER</b><br><b>(64' MEDIAN)</b> |                                                                            |  |