



**SPECIAL PROVISIONS
FOR
CONFORMITY WITH AND COORDINATION OF THE CONTRACT DOCUMENTS**

**Story County
IM-035-4(182)112--13-85**

**Effective Date
September 20, 2016**

THE STANDARD SPECIFICATIONS, SERIES 2015, ARE AMENDED BY THE FOLLOWING MODIFICATIONS AND ADDITIONS. THESE ARE SPECIAL PROVISIONS AND THEY SHALL PREVAIL OVER THOSE PUBLISHED IN THE STANDARD SPECIFICATIONS.

150124.01 DESCRIPTION.

A. With the exception of small or irregular areas, Automated Machine Guidance according to Article 1105.17 of the Standard Specifications will be required for the grading on this project. Automated Machine Guidance for the paving will be the Contractor's option.

B. Digital Contract Files.

1. Digital Files contained within the 85-0354-182_E_Files_(DataFiles).zip file package listed below (files are listed in descending order of precedence):
 - a. LandXML Geometry file: hv_dsn_182.xml within the "Alignment_Data_Files" subfolder.
 - b. LandXML surface files: All LandXML files within the "Machine_Control_Surfaces" subfolder.
 - c. Three dimensional line string CADD files: All DXF files contained within the "DXF_Files" subfolder.
2. See Appendix A for names, time stamps, and sizes of official files.
3. The digital files are available for download at the following web site for the project listed above: <http://www.iowadot.gov/contracts/lettings.html>.

150124.02 STANDARD SPECIFICATION REVISIONS.

Make the following changes to the Standard Specifications:

1101.03, DEFINITION OF TERMS.

Add to the definition of Contract (Also Contract Documents):

- Digital contract files specified in the contract documents,

1105.04, A.

Replace the Article:

In case of a discrepancy between contents of the contract documents, the following items listed by descending order shall prevail:

1. Addendum
2. Proposal Form
3. Special Provision
4. Digital Contract Files.
- 4 5. Plans
- 5 6. Standard Bridge Plans, Standard Culvert Plans, and Standard Road Plans
- 6 7. Developmental Specifications
- 7 8. Supplemental Specifications
- 8 9. General Supplemental Specifications
- 9 10. Standard Specifications
- 10 11. Materials I.M.

1105.04, D.

Replace the Article:

The Contractor shall not take advantage of any apparent error, omission, or discrepancy in the contract documents. The Engineer will be permitted to make such correction in interpretation as may be deemed necessary for the fulfillment of the intent of the contract documents subject to compensation as provided in Articles 1109.03, 1109.04 and 1109.16. Written notice of changes in the contract documents will be given to the Contractor by the Engineer. Field adjustment of digital contract files, if necessary, will be completed by the Engineer.

XML Files	File Size	File Updated
Existing		
exist_surf_85035171_Signed.xml	8,291 KB	6/29/2016 4:23 PM
exist_surf_85035182_Signed.xml	17,606 KB	7/5/2016 1:34 PM
exist_surf_PostStage1_Signed.xml	18,981 KB	6/29/2016 4:23 PM
exist_surf_PostStage4_Signed.xml	19,350 KB	6/29/2016 4:24 PM
Proposed		
<u>Interstate 35</u>		
prop_surf_subgrade_ML035_1_Signed.xml	399 KB	6/29/2016 4:24 PM
prop_surf_subgrade_ML035_2_Signed.xml	114 KB	6/29/2016 4:24 PM
prop_surf_subgrade_ML035_3_Signed.xml	23 KB	6/29/2016 4:24 PM
prop_surf_top_ML035_1_Signed.xml	382 KB	6/29/2016 4:24 PM
prop_surf_top_ML035_2_Signed.xml	267 KB	6/29/2016 4:24 PM
prop_surf_top_ML035_3_Signed.xml	48 KB	6/29/2016 4:24 PM
<u>US Highway 30 EB</u>		
prop_surf_subgrade_SUR030EB_Signed.xml	629 KB	6/29/2016 4:24 PM
prop_surf_subgrade_SUR030EBMedian_Signed.xml	85 KB	6/29/2016 4:24 PM
prop_surf_top_SUR030EB_Signed.xml	1,611 KB	6/29/2016 4:24 PM
<u>US Highway 30 EB Resurfacing</u>		
prop_surf_HMA_IntermediateTopEB_Signed.xml	267 KB	6/29/2016 4:24 PM
prop_surf_HMA_SurfaceCourseTopEB_Signed.xml	267 KB	6/29/2016 4:24 PM
<u>US Highway 30 WB</u>		
prop_surf_subgrade_SUR030WB_1_Signed.xml	305 KB	6/29/2016 4:24 PM
prop_surf_subgrade_SUR030WB_2_Signed.xml	751 KB	6/29/2016 4:24 PM
prop_surf_subgrade_SUR030WB_3_Signed.xml	47 KB	6/29/2016 4:24 PM
prop_surf_subgrade_SUR030WB_4_Signed.xml	39 KB	6/29/2016 4:24 PM
prop_surf_top_SUR030WB_123_Signed.xml	3,199 KB	6/29/2016 4:24 PM
prop_surf_top_SUR030WB_4_Signed.xml	77 KB	6/29/2016 4:24 PM
<u>US Highway 30 WB Resurfacing</u>		
prop_surf_HMA_IntermediateTopWB_Signed.xml	342 KB	6/29/2016 4:24 PM
prop_surf_HMA_SurfaceCourseTopWB_Signed.xml	450 KB	6/29/2016 4:24 PM
<u>Interstate 35 Ramp A</u>		
prop_surf_subgrade_ML035A_Signed.xml	632 KB	6/29/2016 4:24 PM
prop_surf_top_ML035A_Signed.xml	1,339 KB	6/29/2016 4:24 PM
<u>Interstate 35 Ramp B</u>		
prop_surf_subgrade_ML035B_Signed.xml	2,516 KB	6/29/2016 4:24 PM
prop_surf_top_ML035B_Signed.xml	4,663 KB	6/29/2016 4:24 PM
<u>Interstate 35 Ramp H (South)</u>		
prop_surf_subgrade_ML035H_S_Signed.xml	1,701 KB	6/29/2016 4:24 PM
prop_surf_top_ML035H_S_Signed.xml	3,764 KB	6/29/2016 4:24 PM
<u>Interstate 35 Ramp H (North)</u>		
prop_surf_subgrade_ML035H_N_Signed.xml	555 KB	6/29/2016 4:24 PM
prop_surf_top_ML035H_N_Signed.xml	1,475 KB	6/29/2016 4:24 PM
<u>Dayton Ramp A</u>		
prop_surf_subgrade_DAYA_Signed.xml	760 KB	6/29/2016 4:24 PM
prop_surf_top_DAYA_Signed.xml	1,691 KB	6/29/2016 4:24 PM

	File Size	File Updated
<u>Channel Grading (Jacked Pipe)</u>		
prop_surf_CHANNEL_Signed.xml	67 KB	6/29/2016 4:24 PM
<u>Stage 1 Shoulder Strengthening (US 30 WB)</u>		
prop_surf_subgrade_STG1_US30WB_Signed.xml	719 KB	7/19/2016 7:46 AM
prop_surf_top_STG1_US30WB_Signed.xml	1,256 KB	7/19/2016 7:46 AM
<u>Stage 4 Shoulder Strengthening (I-35 NB)</u>		
prop_surf_subgrade_STG4_ML035NB_Signed.xml	881 KB	7/19/2016 7:46 AM
prop_surf_top_STG4_ML035NB_Signed.xml	1,146 KB	7/19/2016 7:46 AM
<u>Stage 1 Shoulder Strengthening (US 30 WB)</u>		
prop_surf_subgrade_STG4_US30EB_Signed.xml	269 KB	7/19/2016 7:46 AM
prop_surf_top_STG4_US30EB_Signed.xml	350 KB	7/19/2016 7:46 AM
<u>3D DGN Files</u>		
85035182_CHANNEL_3d.dgn	59 KB	6/9/2016 3:35 PM
85035182_DAYA_3d.dgn	417 KB	6/9/2016 3:36 PM
85035182_ML035_3d.dgn	285 KB	6/9/2016 3:36 PM
85035182_ML035A_3d.dgn	400 KB	6/9/2016 1:17 PM
85035182_ML035B_3d.dgn	1,271 KB	6/9/2016 3:37 PM
85035182_ML035HN_3d.dgn	474 KB	6/9/2016 3:38 PM
85035182_ML035HS_3d.dgn	1,111 KB	6/9/2016 3:38 PM
85035182_STG1_SUR030WB_3d.dgn	564 KB	7/19/2016 8:38 AM
85035182_STG4_ML035NB_3d.dgn	481 KB	7/19/2016 8:39 AM
85035182_STG4_SUR030EB_3d.dgn	184 KB	7/19/2016 8:37 AM
85035182_SUR030EB_3d.dgn	421 KB	6/9/2016 3:40 PM
85035182_SUR030WB_3d.dgn	802 KB	6/9/2016 3:40 PM
85035182_WALL1_TempGrading_3d.dgn	102 KB	6/9/2016 3:41 PM