



**SPECIAL PROVISIONS
FOR
DEBRIS REMOVAL FROM WATERWAY AREAS**

**Clayton County
MB-052-6(501)80--77-22**

**Jones County
MB-038-6(501)66--77-53**

**Effective Date
January 19, 2022**

THE STANDARD SPECIFICATIONS, SERIES 2015, ARE AMENDED BY THE FOLLOWING MODIFICATIONS AND ADDITIONS. THESE ARE SPECIAL PROVISIONS AND THEY PREVAIL OVER THOSE PUBLISHED IN THE STANDARD SPECIFICATIONS.

150810.01 DESCRIPTION.

Work consists of removal of debris from waterway areas described in the contract documents and proper disposal.

150810.02 MATERIALS.

None.

150810.03 CONSTRUCTION.

- A.** Collect debris from waterway areas described in the contract documents. Sort debris if required for proper disposal. Load and transport debris to disposal site. Do not place debris within highway right-of-way or elsewhere within the waterway area. Non-hazardous debris may be transported to licensed landfills or alternate disposal site. Contact Engineer if hazardous debris is encountered. Hazardous debris will be disposed of by others.
- B.** Ensure alternate disposal site (if selected) does not impact culturally sensitive sites, graves, wetlands, or "Waters of the U.S.", including streams or stream banks below the ordinary high water mark, without approved U.S. Army Corps of Engineers Section 404 Permit.
- C.** Any damage to the bridge, riverbank, rip rap protection, or other material not to be removed shall be the responsibility of the Contractor and repaired at no cost to the Iowa DOT.
- D.** Contact the Engineer if site conditions differ substantially from the contract documents.

150810.04 METHOD OF MEASUREMENT.

Removal of Debris from Waterway Areas will not be measured for payment.

150810.05 BASIS OF PAYMENT.

Payment will be at the lump sum contract price. Payment is full compensation for collecting debris, sorting debris (if required), loading debris, delivery to disposal location, and landfill and permit fees (if necessary). No payment for overhaul will be allowed for material hauled to disposal site (whether landfill or alternate site is chosen).