IOWADOT

**SPECIAL PROVISIONS
FOR
SHADE STRUCTURE**

**Des Moines County
EDP-0977(653)--7Y-29**

**Effective Date
June 15, 2021**

THE STANDARD SPECIFICATIONS, SERIES 2015, ARE AMENDED BY THE FOLLOWING MODIFICATIONS AND ADDITIONS. THESE ARE SPECIAL PROVISIONS AND THEY SHALL PREVAIL OVER THOSE PUBLISHED IN THE STANDARD SPECIFICATIONS.

155061.01 DESCRIPTION.
Construction of the shade structure shall consist of furnishing necessary materials, excavating for and constructing the foundations, fabricating, painting and erecting of the steel columns and beams, and attachment of the glulam shade members.   Shade structure shall be placed on site with horizontal and vertical coordinates as shown on plans.

155061.02 MATERIALS.
Furnish materials complying with the contract documents. Reference detailed specifications are as follows:
- Special Provisions for Cast In-place Concrete
- Special Provisions for Structural Steel Framing
- Special Provisions for Architecturally Exposed Structural Steel Framing
- Special Provisions for Glued-Laminated Construction
- Special Provisions for High-Performance Coatings
- Special Provisions for Helical Foundation Piles

155061.03 CONSTRUCTION.
Construction of shade structure shall be as shown in the contract documents. Contractor shall make all efforts to conform to product details, finishes, and tolerances.   Concrete finishes shall be smooth, consistent, and without surface defects for all exposed surfaces including chamfer edge of exposed concrete foundation sleeve.

Contractor shall provide warranty against defects for all components of shade structure for a period of 5 years after the date of final installation.

155061.04 METHOD OF MEASUREMENT.
The Shade Structure will not be measured for payment.

155061.05 BASIS OF PAYMENT.

    A. Payment for the Shade Structure shall be at the lump sum contract price.

    B. Payment will be full compensation for excavating and constructing the foundations, furnishing material, labor and tools necessary for construction of the shade structure as shown in the contract documents.