



**SPECIAL PROVISIONS
FOR
SITE FURNISHINGS**

**Johnson County
RT-C052(105)--9H-52
NRT-C052(111)--9G-52**

**Effective Date
October 17, 2017**

THE STANDARD SPECIFICATIONS, SERIES 2015, ARE AMENDED BY THE FOLLOWING MODIFICATIONS AND ADDITIONS. THESE ARE SPECIAL PROVISIONS AND THEY SHALL PREVAIL OVER THOSE PUBLISHED IN THE STANDARD SPECIFICATIONS.

PART 1 - GENERAL

1.1 Description of Work

This work includes all labor, materials, tools, equipment, transportation, protection, and supervision necessary and required to furnish and install the site furnishings as specified in the contract documents and as follows:

- A. Benches (two)
- B. Bike Rack (one)

1.2 Coordination

Contractor shall be responsible for coordinating work under this section with other trades and disciplines impacting this work, including the contractor installing the benches and bike racks onto concrete paving.

1.3 Quality Assurance

- A. Benches shall be obtained from the following supplier:

DuMor, Inc.
15 Industrial Circle, P.O. Box 142
Mifflintown, PA 1709-0142
Phone: 1-800-598-
4018 www.dumor.com

- B. Bike Rack shall be obtained from one of the following acceptable suppliers:

- 1. Function First Design, LLC
120 S. Houghton Road, Ste. 138-153
Tucson, AZ 85747

520-322-9626
Sales@BikeRack.com

2. Victor Stanley
2103 Brickhouse Road
Dunkirk, MD 20754
410/257-7578
800/368-2573
3. Dero Play Core
42 Northern Stacks Drive
Minneapolis, MN 55421
888/337-6729

1.4 Submittals

- A. Product Information: Cut Sheet and Item numbers for benches and bike racks for verification to specifications prior to ordering.
- B. Warranty: Provide manufacturer's standard warranty.

1.5 Delivery, Storage, And Handling

- A. Deliver packaged materials in original, unopened packages.
- B. Protect from damage prior to and during installation. Damage, including scratches, chips, dents will be cause for rejection and replacement, and at no additional cost to Contracting Authority.

1.6 Field Conditions

Verify that concrete paving is constructed to the required dimensions and grades and are ready for installation of site furniture.

PART 2 - PRODUCTS

2.1 Site Furniture

- A. Provide the following site furniture from the following supplier:
 1. DuMor, Inc.
 - a. 6 foot Bench, Backless: 163-60 PL; Recycled Plastic Color: "Walnut"; S-2 surface mount.
 - b. 6 foot Bench, Backed: 88 Series 138 PL-60- PL; Recycled Plastic Color: "Walnut"; S-2 surface mount.
- B. Provide the following site furniture from the following acceptable suppliers or approved equal:
 1. Function First, Inc.
Bike Rack: The Bike Rib Series II Model # BR4 SR-BR4; Finish: hot dipped galvanized steel. Surface Mount; steel tube standard.
 2. Deco Play Core
Bike Rack: RR2H 38 inch, Finish: hot dipped galvanized steel, Surface Mount, steel tube standard.

3. Victor Stanley
Bike Rack: SBRCs-103, Finish: hot dipped galvanized steel, Surface Mount, steel tube standard.

PART 3 - EXECUTION

3.1 Examination

Examine areas where site furnishings are to be mounted, with Installer present, for compliance with requirements and conditions affecting installation and performance of the Work.

3.2 Installation

Install site furnishings in accordance with suppliers written recommendations.

PART 4 - METHOD OF MEASUREMENT AND BASIS OF PAYMENT

4.1 Method of Measurement: The Engineer will count each installed bench and bike rack that is in conformance with the construction documents.

5.1 Basis of Payment: Payment will be at the contract unit price bid for each site furnishing: Bench – Backed - metal and recycled plastic; and Bench – backless, metal and recycled plastic 6-foot; Site Furnishings: Bike Rack, Metal according to the contract documents. This payment shall be full compensation for all transportation, materials, tools, equipment, supervision and labor to furnish and install the site furniture in accordance with the contract documents. Payment includes manufacturer's standard warranty.